



MOLD BASES AND PLATES



Table of Contents

Introduction

Terms and Conditions of Sale.....	4
Sales and Ordering Information.....	5
Mold and Die Steels.....	8
Mold Base Benefits.....	9
DME Item Number System.....	10
Mold Base Terminology.....	11
Machining of Clamp Slots.....	12

American Standard Mold Bases

Sprue Bushings.....	16
Locating Rings.....	16
Clamp Slots.....	17
Guided Ejection Systems.....	18
Guide Pins and Bushings.....	19
Upper & Lower Assembly Screws.....	20-21
Return Pins, Stop Pins and Sprue Puller Pins.....	22
Ejector Assembly Screws.....	23
Leader Pin Vents,.....	23
Pry Slots.....	24
Lifting Holes.....	24
Pockets.....	25
Contour & Roughing Services.....	25
Spring Pockets.....	25
Mold Strap Holes.....	26
Mold Interlocks.....	26
Support Pillars.....	27
Insulator Sheets.....	27
Support Pillars.....	27
3-Plate Extension Bushings.....	28
Waterlines.....	28

Standard A-Series Mold Bases.....	31-121
--	---------------

B-Series Mold Bases.....	122
---------------------------------	------------

X-, AX- and T-Series Mold Bases.....	123-146
Features.....	124-125
X-Series.....	126-133
AX-Series.....	134-135
T-Series.....	136-146
3-Plate Extension Bushings.....	147
Ball Bushings for Floating Plates.....	148

Small and Shuttle Mold Bases.....	150
Small and Custom.....	152-155
Shuttle Mold Bases.....	156-159

Cavity Retainer Sets

Cavity Retainer Sets.....	162-184
---------------------------	---------

Mold Plates

Standard Mold Plates.....	188-193
Ejector Plates.....	194
Ejector Retainers.....	195
Spacer Blocks/Rails.....	196-199
Ejector Housings.....	200-201
Small Mold Base Ejector Plates, Retainers & Housings.....	202
Die Blocks & Plates.....	203-204
Cavity Insert Blocks.....	205
Large Mold Plates.....	206-210

Molding Supplies

Mold Cleaner and Mold Saver.....	214
----------------------------------	-----

Technical Reference

Metric Equivalents and Conversions.....	216
Steel Hardness Chart.....	217
Tensile Strength.....	218
Steel Designations.....	219
Tables for Determining Metric Tolerances.....	220-229

Index

3-Plate Extension Bushings.....	147	Mold Base 1329A.....	74-75
A-Series Mold Bases.....	11, 31	Mold Base 1518A.....	76-77
A-Slotted Rail.....	197	Mold Base 1524A.....	78-79
AX-Series Mold Bases.....	11, 134	Mold Base 1529A.....	80-81
Adapter Plates, Custom Universal.....	150	Mold Base 1616A.....	82-83
Adapter Plates, Small Mold Base.....	152	Mold Base 1620A.....	84-85
Additional Assembly SHCS, Minimum Recommended.....	20	Mold Base 1623A.....	86-87
Arburg Locating Rings.....	16	Mold Base 1626A.....	88-89
Assembly Screws (SHCS).....	20	Mold Base 1629A.....	90-91
B-Series Mold Bases.....	11, 122	Mold Base 1635A.....	92-93
Ball Bushings.....	148	Mold Base 1724A.....	94-95
Bolster Plate.....	see Support Plate	Mold Base 1729A.....	96-97
Cavity Insert Blocks.....	205	Mold Base 1818A.....	98-99
Cavity Retainer Sets.....	162	Mold Base 1820A.....	100-101
Clamp Slots.....	12, 17	Mold Base 1823A.....	102-103
Column.....	see Support Pillars	Mold Base 1826A.....	104-105
Contour Roughing Services.....	25	Mold Base 1829A.....	106-107
Core Retainer Plate.....	see B Plate	Mold Base 1835A.....	108-109
Determining Metric Tolerances.....	220	Mold Base 1924A.....	110-111
Die Blocks and Plates.....	203	Mold Base 1929A.....	112-113
Ejector Assembly Screws.....	20	Mold Base 1935A.....	114-115
Ejector Housing.....	23	Mold Base 2424A.....	116-117
Finish Ground Mold Plates.....	188	Mold Base 2429A.....	118-119
Floating Plate.....	see Stripper Plate	Mold Base 2435A.....	120-121
Guide Pins and Bushings.....	19	Mold Base Features.....	16-28, 124-125
Guided Ejection Systems.....	18	Mold Cleaner and Mold Saver.....	214
Insulator Sheets.....	27	Mold Plates.....	188-193
Interlocks.....	26	Mold Strap Holes.....	26
Leader Pin Vents.....	23	Parallels.....	see Spacer Blocks
Lifting Holes.....	24	Pillow.....	see Support Pillars
Locating Rings.....	16	Pockets.....	25
Lower Half.....	see B Plate	Pry Slots.....	24
Machining Services, Clamp Slots.....	12, 17	Rails.....	see Spacer Blocks
Metric Equivalents and Conversions.....	216	Rear Cavity Plate.....	see B Plate
Mold and Die Steel Descriptions.....	8	Return Pins.....	22
Mold Base 88A.....	36-37	Risers.....	see Spacer Blocks
Mold Base 812A.....	38-39	Rotary Ground Mold Plates.....	189
Mold Base 108A.....	40-41	Shuttle Mold Bases.....	156-159
Mold Base 1012A.....	42-43	Small Mold Bases.....	152-155
Mold Base 1016A.....	44-45	Spacer Blocks.....	196
Mold Base 1020A.....	46-47	Spacers.....	see Spacer Blocks
Mold Base 1112A.....	48-49	Spring Pockets.....	25
Mold Base 1114A.....	50-51	Sprue Bushings.....	16
Mold Base 1118A.....	52-53	Sprue Puller Pins.....	22
Mold Base 1123A.....	54-55	Steel Designations.....	8
Mold Base 1212A.....	56-57	Steel Hardness Chart.....	217
Mold Base 1215A.....	58-59	Stop Pins.....	22
Mold Base 1220A.....	60-61	Stripper Plate.....	11, 124
Mold Base 1223A.....	62-63	Support Pillars.....	27
Mold Base 1315A.....	64-65	Support Plate.....	11
Mold Base 1318A.....	66-67	T-Series Mold Bases.....	11, 136-146
Mold Base 1321A.....	68-69	Tensile Strength.....	218
Mold Base 1323A.....	70-71	Upper and Lower Assembly Screws.....	20-21
Mold Base 1326A.....	72-73	Waterlines.....	28
		X-Plate.....	see Stripper Plate
		X-Series Stripper Mold Bases.....	11, 126-133

Terms and Conditions of Sale

DME COMPANY LLC ("SELLER") TERMS AND CONDITIONS OF SALE

1. **ACCEPTANCE OF TERMS:** Seller's offer is expressly conditioned upon Buyer's acceptance of these Terms and Conditions, and Seller expressly objects to any additional or different terms proposed by Buyer. Any subsequent purchase order issued by Buyer shall constitute Buyer's agreement to these Terms and Conditions. Any contrary terms and conditions contained in any purchase order, facility entry form, or other instrument issued by the Buyer are expressly rejected and shall not apply to this transaction. Unless otherwise specified in the quotation, Seller's quotation shall expire 30 days from its date and may be modified or withdrawn by Seller before receipt of Buyer's conforming purchase order.

2. **PAYMENT TERMS:** Payment is due in accordance with any applicable progress, advance or other agreed upon payment schedule, or, if no such schedule has been agreed to, no later than 30 days from the date of invoice. Buyer shall pay a late payment charge computed at the lower of 1.5% per month on any overdue balance, or the maximum rate permitted by law. No cash discount is provided. If at any time Seller reasonably determines that Buyer's financial condition or payment history does not justify continuation of Seller's performance, Seller shall be entitled to require full or partial payment in advance or otherwise restructure payments, request additional forms of payment security, suspend its performance or terminate the order.

3. **DELIVERY**

3.1 In the United States, products are sold FCA Incoterms 2020 point of origin; for export sales, terms are FCA Incoterms port of export. Unless otherwise agreed in writing, title and risk of loss shall pass at the time of shipment. Buyer is responsible for all taxes, duties, fees, or other governmental charges related to its purchase of goods, with the sole exception of taxes on Seller's income. Unless otherwise agreed, Buyer shall pay all packing and delivery costs.

3.2 Seller's quoted lead times and targeted delivery dates are good faith estimates and are not binding on Seller. Buyer's acceptance of delivery of Seller's products from the carrier shall constitute a waiver of any claim for delay. If Seller notifies Buyer that the products are ready for shipment and Buyer delays delivery, then Seller may charge Buyer a storage fee equal to 1.5% of the contract price per month for each month of delay. Such storage fees are in addition to any other remedies Seller may have.

3.3 Buyer shall have a reasonable opportunity to inspect any products prior to shipment. Products shall be deemed to be accepted upon the earlier of: (i) inspection at Seller's plant (provided that no reasonable objection is then raised by Buyer), or (ii) if no inspection is requested, then at shipment. If an objection is made during inspection, then Products shall be deemed accepted upon resolution of the objection by Seller.

4. **WARRANTY:**

4.1 Seller's express product warranty be as stated in DME's order specification documentation and shall run from the date of shipment (the "Warranty Period"). During the Warranty Period, Seller warrants that the products and services sold hereunder will be free from material defects in material, workmanship and title (the "Warranty").

4.2 If, during the Warranty Period, Seller reasonably determines that the products do not meet the Warranty, then Seller shall, at its option, repair or replace the defective product or component thereof, reperform any defective services at Seller's expense, or refund or credit to Buyer its purchase price for the defective products or services.

4.3 The Warranty will be void and will not apply: (i) when Buyer fails to promptly notify Seller of any alleged defect, (ii) when Buyer fails to properly install, maintain, or operate the products, (iii) to any product or parts thereof with a useful life, under normal operating conditions, inherently shorter than 1 month, or (iv) to products which were not made by Seller or any of Seller's affiliates, provided that in such cases Seller shall use reasonable efforts to pass on to Buyer the manufacturer's warranty.

4.4 If Seller provides any parts or services to repair a product that is not under Warranty, then such parts and services will be billed to Buyer at Seller's prevailing rates for time and materials.

4.5 The Warranty set out above is the sole and exclusive warranty provided by Seller for its products and is in lieu of, and Seller expressly disclaims, all other warranties, express or implied, oral, written or statutory. **THERE ARE NO WARRANTIES OF MERCHANTABILITY OR FITNESS FOR PURPOSE FOR SELLER'S PRODUCTS.**

5. **LIMITATION OF LIABILITIES:**

5.1 Seller's total liability to Buyer arising out of or resulting from this Contract or related in any way to Seller's products or parts thereof shall not exceed the contract price for such products.

5.2 Seller shall not be liable for loss of profit or revenues, loss of use of prod-

ucts, interruption of business, downtime costs, increased operating costs, or any special, consequential, incidental indirect or punitive damages, whether incurred by Buyer or Buyer's customers.

5.3. Because the conditions of actual production in each end user's plant vary considerably, Buyer assumes all risk for the results obtained by use of Seller's products in the practice of any process, whether in terms of operating costs, general effectiveness, success or failure, and regardless of any oral or written statements made by Seller related to the use of its products.

6. **SECURITY INTEREST.** Buyer agrees that the Seller shall have and retain a purchase money security interest in the Products securing the payment of all sums becoming due hereunder. Such security interest shall attach, upon completion of manufacture, to the Products and to any parts or accessories attached to the Products and to the proceeds of any sale thereof. Buyer represents that the Products are being acquired for use in its business and that such Products will not, without prior written consent of the Seller, be sold or removed from the Buyer's place of business to which delivery is made. Buyer agrees upon Seller's request to execute any financing statements or other documents required to perfect, continue or renew Seller's security interest in the Products.

7. **CANCELLATION:** Unless otherwise agreed, Buyer may cancel all or any part of the order by written notice received by Seller before the completion of the order. On receipt of such cancellation notice, all work on the order or part thereof canceled will be stopped as promptly as is reasonably possible. Buyer will then be invoiced for and will pay to Seller as liquidated damages a cancellation charge. For completed items, the charge will be equal to their established prices. For items not completed, the charge will be equal to 135% of Seller's full cost as determined by Seller in accordance with Seller's standard accounting practices (which includes burden and overhead), plus a charge for any packing and storage, less a credit for the balance of the material as scrap.

8. **RETURNS:** All returned items require a Return Merchandise Authorization (RMA) number from DME. Returns are subject to a quality inspection to validate whether it can be returned to inventory. Mold bases, plates, special components, made-to-order products and other date-sensitive products are non-returnable items. Items returned to DME without prior authorization(RMA) may be returned to sender. Items returned for stated defect or non-conforming reason require detailed explanation. No products are returnable beyond 30 days after receipt.

9. **CONFIDENTIALITY.** Any nonpublic information, including without limitation, Seller's pricing information and the contents of Seller's quotation or proposal and Buyer's purchase order, exchanged between the parties is deemed confidential ("Confidential Information"). Each party agrees to maintain the other party's Confidential Information in confidence, to not disclose the same to any third parties, and to use it only in connection with this sale. These restrictions shall expire two (2) years after the date of disclosure. This provision does not modify or supersede any separate confidentiality or nondisclosure contract signed by the parties.

10. **FORCE MAJEURE:** Seller shall not be liable for any delay in performance or nonperformance which is due to war, fire, flood, pandemic, acts of God, acts of third parties, acts of governmental authority or any agency or commission thereof, accident, breakdown of products, differences with employees or similar or dissimilar causes beyond Seller's reasonable control, including but not limited to, those interfering with production, supply or transportation of products, raw materials or components or Seller's ability to obtain, on terms Seller deem reasonable, material, labor, products or transportation.

11. **MERGER CLAUSE:** This Contract entirely supersedes any prior oral or written representations, correspondence, proposals, or contracts between the parties regarding the products. This writing constitutes the final and total expression of such contract between the parties, and it is a complete and exclusive statement of the terms of that contract.

12. **ASSIGNMENT:** Neither party may assign this Contract without the written consent of the other party, except that Seller may assign this Contract to a third party that acquires substantially all of Seller's assets and Seller may assign the flow of funds arising out of this Contract.

13. **COMPLIANCE WITH LAWS.** Each party agrees to comply with all applicable laws in the performance of its obligations; Buyer shall not trans-ship, re-export, divert or redirect Products outside of the original country of delivery without Seller's prior written consent.

14. **GOVERNING LAW:** This Contract shall be governed by and construed in accordance with the laws of the State of Michigan, without regard to the Convention for the International Sale of Goods (CISG), which shall not apply.

Sales and Ordering Information

U.S.A.

TERMS AND CONDITIONS OF SALE: See previous page.

EMAIL ORDERS - U.S. - DME@DME.net Canada - DME_Canada@DME.net

PHONE ORDERS – TOLL FREE: 800-626-6653. Our Customer Service Dept. operates Monday through Friday from 8 a.m. to 6 p.m. E.S.T. Calls can be made from anywhere in the continental U.S. and Puerto Rico (Puerto Rico: use “137” prefix instead of “1”). Our Customer Service Representatives will be happy to answer your questions on DME products or services, provide on-the-spot feedback on product availability and shipping details, or take any messages you wish relayed to your local DME sales, manufacturing or technical service representatives.

eSTORE: Open 24/7 - quote, check stock, order

CHECKS OR MONEY ORDERS: When paying invoices by check or money order, please make payable to *DME Company*.

Include remittance copy of invoice and mail to:

- DME Company, PO Box 854867 Minneapolis, MN 55485-4867

MACHINING SERVICES: Prints for quotation on special machining work can be sent by EDI to dme_cad@dme.net

To obtain prices and delivery on special mold base orders or to check status of special work in progress please contact Customer Service.

CANADA

TERMS AND CONDITIONS OF SALE: See previous page.

PHONE ORDERS: Contact our Windsor, Ontario office at 800-387-6600

CHECK OR MONEY ORDERS: Make payable to *DME Company Ltd.* Include remittance copy of invoice and mail to: DME

Company 5345 Outer Drive - Unit 3, Old Castle, ON N9G 0C4

WALK-IN ORDERS, PICK-UPS, RETURNS, AND SPECIAL MACHINING: Contact our Windsor office.


Mold Bases: What Every Molder Should Know

Today's mold-building process is a complex one for the molder, who must grapple with a long list of design details before placing a tooling order. It's understandable that much of the buyer's attention goes to the "heart" of the injection mold, the core and cavity inserts, since they have the most visible influence on the molded part. Yet all sorts of ancillary tooling components, to which the molder might not be inclined to give much thought, can also make or break a mold.

One item that sometimes gets lost in the shuffle is the mold base, even though the wrong one can severely limit a mold's productivity. Rather than an afterthought, mold base selection should be considered critical to the profitability of the entire molding project.

When selecting a mold base for a particular job, first ask a few key questions about the part's design and processing demands: What kind of ejection does it need? Does it have a cam action or some other mold-action device? What are the volume requirements? What type of machine will it run on?

Answer these design and processing questions, and you'll be well on your way to picking the standardized or special-purpose mold base best suited to your application.



A-Series Mold Base Assembly

The most frequently used standard assembly, the A-Series Mold Base, is available in 43 sizes from 7.875 x 7.875 to 23.75 x 35.5.

Standard Mold Base Styles

For most applications, a standard mold base will fit the bill. The most common of these is the A-series, which has the flexibility to fit into the widest variety of molding applications.

A-style models have a four-plate design: (from top to bottom) top clamp plate, A-plate, B-plate, support plate, ejector retainer, ejector bar, and ejector housing. Mold makers using an A-series mold base typically machine through pockets in the A and B-plates to accept just about any kind of core and cavity insert.

The B-series mold base represents an economy version of the A-style. The B-series two-plate design combines the top clamp plate and the A-plate into one component called the A-Clamping Plate or ACP. Likewise, a beefed-up B-plate eliminates the need for a support plate on the core side of the mold.

Molders can use the less-costly B-series when the part design allows the cavity and core to be machined directly into the cavity plates. If the mold will be used with cavity inserts, they must be machined into blind pockets. The compactness of the B-series mold base also makes it applicable whenever overall mold height must be limited in order to fit the tool in a given molding machine.

"Core and cavity inserts ... have the most visible influence on the molded part yet ... mold base selection should be considered critical to the profitability of the entire molding project."

Special-Purpose Machines

Mold action and ejection requirements will often dictate the use one of three special-purpose mold bases instead of the simpler A- and B-series.

One of these is the X-series, or stripper-plate, mold base. Sandwiched between the A- and B-plates, its stripper (X) plate engages the edge of a part and pushes it off the core. Typically, the X-series sees use with round parts like cups, caps, and containers. This style of mold base comes in both five- and six-plate styles- -with the six-plate version including a support plate.

The AX-series mold base is used for parts requiring core detail in the cavity side of the mold. When the mold opens, that core detail is pulled so that the part remains on the ejector side of the mold. The AX-series is essentially an A-series mold base with an X-1-plate, located between the A- and B-plates but attached to the top half of the mold so that it can pull the part off the core detail.

The T-series, or three-plate, mold base is used when the molder would like to separate the part from the runner in the tool. T-series mold bases consist of an A Clamping plate, X1-plate, X2-plate, B-plate, and the ejector assembly and housing. Unlike the other mold bases, the T-series operates with two parting lines. The first parting line, which occurs between the X1 and X2 plates, separates the part from the gate prior to opening the main parting line. The main parting line then opens and the X1-plate is actuated to pull the runner from the sprue-puller pin, thereby freeing the runner and allowing it to be ejected separately from the part being produced.

See page 11 for illustrations of standard mold base types.

Choosing A Steel

Steel selection is an important aspect of specifying the right mold base. Generally there are four standard grades of steel available. See page 8 for mold and die steel descriptions.

Molding Machine Considerations

After you've picked the right style and steel for your mold base, it's time to consider variables related to the molding machine: the locating-ring style, sprue bushing, and clamp slots.

The mold maker must select the type of locating ring that will match the platens of the machine in which the mold will

be running. Locating rings are available in a wide variety of configurations to fit most injection machines, but the most common locating ring has a 3.990 in. outside diameter.

Sprue bushings must also match the machine, so be sure to determine the proper orifice and radius of the sprue bushing so it will match the machine nozzle. The most common type of sprue bushing is made from 6145 steel that has been hardened, ground, and polished for sprue release. In some applications it is desirable to use a high-conductivity copper-alloy sprue bushing.



“High-performance sprue bushings cool the sprue quickly when either the sprue weight is greater than the part weight, or a rigid target is needed for a robotic sprue picker ...”

These “high-performance” sprue bushings can cool the sprue quickly when either the sprue weight is greater than the part weight, or a rigid target is needed for a robotic sprue picker, or when scrap would result from a hot sprue coming in contact with a finished part. High-performance sprue bushings are fully interchangeable with the standard bushings.

A number of different clamp-slot styles are available. Whatever the style, make sure it's compatible with the thickness of the top clamping plate on your mold base (ACP, A-plate, or AX-plate).

Finally, the molder needs to determine the correct mold base height in relation to the maximum space available in the press. A mold base that won't run in the appropriate size of press can turn potential profit into loss. In addition, be aware of the maximum stroke required to eject the part for the mold.

Mold and Die Steels

STEEL DESCRIPTIONS

Three Steels for Structural Sections

DME NO. 1 STEEL

No. 1 Steel is a medium carbon (SAE 1030) or equivalent, silicon-killed forging quality steel with approximately 25% greater tensile strength than typical low-carbon warehouse steels. It machines easily, but is not "sticky," permitting a faster and smoother cut.

DME NO. 2 STEEL

No. 2 Steel is an AISI 4130 or equivalent type steel. It is supplied pre-heat treated to 28-34 HRC (271-321 Bhn). A high strength steel, it is ideal for cavity and core retainer plates, clamping plates and support plates in molds and dies. *(available upon request)*



DME NO. 7 STEEL

No. 7 Steel is a modified AISI 400 or equivalent series stainless steel for holder block applications. It is supplied pre-heat treated to 32-36 HRC (302-340 Bhn). This stainless steel offers corrosion-resistance and exceptional machinability but cannot be further hardened (see DME No. 6). For humid environments, corrosive plastics, "clean room" or "100% stainless" applications, it is an ideal choice for all structural (non-cavity/core) mold plates.

Three Steels for Cavities and Cores

DME NO. 3 STEEL

No. 3 Steel is a P-20 AISI 4130 (modified) type cavity steel. Exceptionally clean, it is pre-heat treated to 28-34 HRC (271-321 Bhn). It provides high hardness, good machinability and exceptional polishability for both plastics molds and die cast dies.

DME NO. 5 STEEL

No. 5 Steel is a thermal shock resistant, hotwork die steel (AISI-SAE H-13 type) or equivalent. Supplied fully annealed 13-20 HRC (approx. 200 Bhn) for easy machinability, it can be subsequently heat treated to the desired hardness with a minimum of deformation.

Mainly used for die cast dies, it is also suitable for plastics molds with exceptional hardness or polishability requirements.

DME NO. 5 Steel meets or exceeds the acceptance criteria established by the NADCA as detailed in Technical Digest Number 01-80-01D

DME NO. 6 STEEL

No. 6 Steel is T-420 type or equivalent stainless steel. It is supplied fully annealed to 8-23 HRC (179-241 Bhn), making it readily machinable. It can be used for injection, compression or transfer molds where the properties of the plastics materials or excessive condensation require a highly corrosion resistant cavity steel.

OTHER TYPES OF STEEL AVAILABLE VIA SPECIAL ORDER. CONTACT DME.

Benefits of Standard Mold Base Assemblies and Components

Seven major benefits of DME Standard Mold Base Assemblies and Components

1. Made of high quality, pre-finished mold and die steels that give you more for your money; more metallurgical consistency; more cleanliness in cavity steels; more reliability.
2. Assemblies, plates and components are pre-engineered to give you the economic and technical benefits of interchangeability.
3. Manufactured with the most advanced, precision equipment – and quality control tested to give you reliable performance.
4. Gives designers more freedom and flexibility – more time to devote to the truly creative aspects of mold, die, and product design.
5. Gives mold and die makers more time to concentrate on cavities and cores – thus increasing productivity as much as 40%.
6. Gives molders more quality parts per hour, more profitability – with production proven construction that outlasts the longest runs.
7. Readily available as you need them. The more popular assemblies are always in stock for same-day service. Our nationwide network of Service Centers means you have the products and the people near you to help you save time, money and inventory costs.




These three features have helped make DME Standard Mold Bases the most frequently specified mold base assemblies in the world:

- 1 CLAMP SLOTS that save platen space and provide maximum cavity area
- 2 TUBULAR DOWELS that provide more room for waterlines
- 3 THREE-PIECE EJECTOR HOUSING with shoulder bolts providing modular assembly

DME Standard A-Series Mold Base with Cavity Inserts

INJECTION MOLDING

Injection molding is recognized as the single most important form of plastics processing. Beginning with just a handful of standardized mold bases and components in 1942, DME now offers thousands of standardized mold base assemblies and a broad variety of mold components to satisfy the consistent need for high-quality injection molds. Primarily used for thermoplastics injection molding, most of our assemblies and components are readily adaptable for the injection molding of thermosets. Future product developments from DME will include standardized components specifically designed for the injection molding of thermoset materials.



DME Item Number System

The item number system employed by DME not only prevents the duplication of item numbers, but helps lessen the chances of error in the writing and production of orders. This is accomplished by incorporating actual dimensional data into the item numbers as indicated below.

MOLD BASES – A AND B-SERIES

The item numbers for Standard Mold Bases in the A and B-Series combine the NOMINAL Size (width and length), the Series (A or B) and the thicknesses of the A (or A-Clamping) and B-Plates.

Since all the standard mold plate thicknesses are a combination of a whole number and either $\frac{3}{8}$ or $\frac{7}{8}$, the designation 13 indicates 1 and $\frac{3}{8}$; 17 indicates 1 and $\frac{7}{8}$; 23 indicates 2 and $\frac{3}{8}$, etc.

For Example: 1016A-13-37 is the item number for a $9\frac{7}{8} \times 16$ " A-Series Mold Base with A-plate $1\frac{3}{8}$ and B-plate $3\frac{7}{8}$ thick.

MOLD BASES – X OR STRIPPER PLATE SERIES

The item numbers for the Stripper Plate Series Mold Base combine the NOMINAL Size (width and length), the letter X for Stripper Plate, the numeral 5 or 6 (plate series) and the AX-plate thickness.

Since the X-plate thickness is constant at $\frac{7}{8}$ or $1\frac{3}{8}$, and the BX-plate thickness is constant at $1\frac{3}{8}$, $1\frac{7}{8}$ or $2\frac{3}{8}$, depending on the mold base nominal size and number of plates in the assembly, these thicknesses are not represented in the item number.

For Example: 1818X-5-13 is the item number for a $17\frac{7}{8} \times 18$ ", 5-plate X-series Mold Base with a $1\frac{3}{8}$ thick AX-plate. (In this case, the X-plate is $1\frac{3}{8}$ thick, and the BX-plate is $2\frac{3}{8}$ thick).

AX AND T SERIES MOLD BASES

The item numbers for the AX-Series Mold Bases combine the NOMINAL Size (width and length), the letters AX and the thickness of the A and B-plates. The X-1-plate thickness is specified when ordering and is omitted from the item number.

For Example: 1212AX-13-37 is the item number for an $11\frac{7}{8} \times 12$ " -AX-Series Mold Base with a $1\frac{3}{8}$ thick A-plate and $3\frac{7}{8}$ thick B-plate. The X-1-plate thickness (e.g. $\frac{7}{8}$) is then specified when ordering.

The item numbers for the T-Series Mold Bases combine the NOMINAL Size (width and length), the letter T and the thickness of the X-2 and B-plates.

Since the thickness of the A-Clamping plate is constant at $1\frac{7}{8}$ or $2\frac{3}{8}$ and the X-1-plate thickness is constant at $\frac{7}{8}$ or $1\frac{3}{8}$, depending on the nominal size of the mold base, these thicknesses are not represented in the item number.

For Example: 1012T-23-17 is the item number for a $9\frac{7}{8} \times 11\frac{7}{8}$ T-Series Mold Base with a $2\frac{3}{8}$ thick X-2-plate and $1\frac{7}{8}$ thick B-plate. (In this case, the A-Clamping plate is $1\frac{7}{8}$ thick and the -X-1-plate is $\frac{7}{8}$ thick).

CAVITY RETAINER SETS

Since Cavity Retainer Sets are made up solely of an A and B-plate, the item numbers combine the NOMINAL Size, and the A and B-plate thicknesses. (The absence of the letter A, B, AX, or T distinguish these numbers from the item numbers of Standard Mold Bases).

For Example: 1215-33-47 is an $11\frac{7}{8} \times 15$ " Cavity Retainer Set with A-plate $3\frac{3}{8}$ and B-plate $4\frac{7}{8}$ thick.

MOLD PLATES


The same principle used for numbering Cavity Retainer Sets is applied to Standard Mold Plates; however, only one plate thickness is required. (Since the item numbers for retainer sets will always indicate two separate plate thicknesses, the distinction between these two items is easily identified).

For Example: 1318-47 is a $13\frac{3}{8} \times 18$ " Mold Plate, $4\frac{7}{8}$ thick.

NOTE: While an understanding of this item number system can be very helpful in identifying and referring to the various standard sizes, the DME catalog should be consulted when ordering any standard item.

Standard Mold Base Terminology


A AND REVERSE A-SERIES ASSEMBLIES




The most frequently used Standard Assembly, the A-Series Mold Base is available in 43 sizes from $7\frac{7}{8} \times 7\frac{7}{8}$ to $23\frac{3}{4} \times 35\frac{1}{2}$, or complete information.

REVERSE A-SERIES

Identical to the A-Series, with leader pins and bushings "reversed." Specify AX- and BX-plate thicknesses when ordering (rather than A and B).




B-SERIES ASSEMBLY




When cavities and cores are to be inserted into blind pockets, or machined directly into the A- and B-plates, the B-Series Assembly is used. The Top Clamping Plate and Support Plate are omitted from the assembly.

X-SERIES (STRIPPER PLATE) ASSEMBLY

Most frequently used for molds requiring stripper plate ejection, the X-Series Assembly is available with a Support Plate (6-plate series) or without a Support Plate (5-plate series).




AX-SERIES ASSEMBLY



The AX-Series Assembly is used when the mold requires a floating plate to remain with the upper or stationary half of the assembly. It is basically an A-Series Assembly with a floating plate (X-1) added.


T-SERIES ASSEMBLY



The T-Series Assembly is used for top runner molds that require two floating plates (X-1 – runner stripper plate, X-2 – cavity plate) to remain with the upper or stationary half of the assembly.


Machining of Clamp Slots

Clamp Slots facilitate clamping the mold to the platen of the press. DME mold bases offer four slot types (shown below) to ensure the best fit for the requirements of your application.



Type A


Machined when Top Clamping Plate is 0.875 or 1.375



NOTE:
When this plate is 0.875 thick, the slots
will be machined through the thickness.


Type B

Machined in plates that
are 2.375 or thicker




Type C


Machined only when
specified by a customer



Type D

Machined plates that
are 1.875 thick





Mold Base & Plates Services

Mold Bases with optional
feature-based selections

Table of Contents



Mold Base Features 20 to 23



Contour Roughing Services 28


Precision machined custom mold bases and plates with lengths up to 90"; rough milling of your complex part shapes into mold plates



Immediate price and stock information 24/7

DME Mold Base Features

**DOZENS OF
MOLD BASE FEATURES
TO CHOOSE FROM.**



Mold Base Features

Sprue Bushings & Locating Rings

Classic 2.0 Mold Bases are machined for and include a Sprue Bushing and Locating Ring. You may choose to omit either or both parts. Omitting the Machining for either makes this a non-standard mold base.

See DME Mold Component catalog for Sprue Bushing and Locating Ring options

The Sprue Bushing provides a seat at the spherical radius for the nozzle of the press. This provides a path for the material from the nozzle to the runner system.

S.A.E. 6145 Steel Sprue Bushings come in 2 stem diameters and a wide variety of lengths.



Steel Sprue Bushings

7 series

2 stem diameters

Wide variety of lengths

Multiple Orifice & Radius combinations



High Performance Sprue Bushings

2 series

2 stem diameters

Wide variety of lengths.



3D printed Conformal Cooled

Sprue Bushings


2 series

2 stem diameters

Wide variety of lengths.



The Locating Ring aligns the mold base to the stationary platen side of the press and positions the sprue bushing correctly.



Locating ring #6501 shown

DME Locating Rings

ITEM NUMBER	Ø D	DESCRIPTION
6500	2.615	
6501	3.990	STANDARD SERIES
6501LN	3.990	LN SERIES
6502	4.990	
6503	2.000	
6504	3.990	CLAMP TYPE
6505LN	5.990	LN SERIES
6510	7.995	
6511	2.990	
6520	3.990	EXTENSION NOZZLE TYPE
6521	3.990	STANDARD SERIES
6522	3.990	EXTENSION NOZZLE TYPE
6524	3.990	CLAMP TYPE
6534**	1.574	TOP AND BOTTOM RING
6535	3.541	
6536	4.331	TOP RING
6537	4.331	BOTTOM RING
6541*	3.990	STANDARD SERIES
6544*	3.990	CLAMP TYPE

* For use with high-temperature insulator sheets.

** For use with 3.5 x 3.75 Arburg Mold Bases.

See DME Mold Components catalog for dimensions of other locating rings.

Mold Base Features


Clamp Slots

Clamp Slots facilitate clamping the mold to the platen of the press. DME American Standard Mold Bases offer four slot types (shown below) to ensure the best fit for the requirements of your application.

Clamp slots come standard depending on the plate thicknesses as described below. Optional/special clamp slots are available upon request

Clamp Slot Types


Type A - Machined when Top Clamping Plate is 0.875 or 1.375




NOTE: When this plate is 0.875 thick, the slots will be machined through the thickness.

Type B - Machined in plates that are 2.375 or thicker

Type C - Machined only when specified by a customer and top clamp plate is 1.375




Type D - Machined plates that are 1.875 thick



Other/special options available:

- Omit upper clamp slot
- Omit lower clamp slot (3-piece housing supplied)
- Machine entire length
- Machine all four sides



Mold Base Features



Guided Ejection

Guided Ejection Systems hold the ejector assembly in alignment and support the weight of the ejector assembly throughout the molding cycle – greatly reducing wear on ejection components and preventing cocking of the ejector assembly. System 3 with solid bronze GE Bushings comes as standard or can be omitted on for all Classic 2.0 mold bases. Optional bushing styles available are bronze-plated or self-lubricating. System 1 & 2 can be installed as a special order.

Guided Ejection Positions


SYSTEM 3 - Standard/Optional

Pins installed in the ejector housing permit fast installation. When the ejector housing is removed from the mold base, the complete ejector assembly is removed. Maching does not extend into the Support Plate



"B" HALF OF MOLD
FOR 88 & 812 MOLD BASES ONLY

PIN DIAMETER (RECOMMENDED)	BASE SIZE	GEx	GEy
0.750	88	3.125	Center
	812	5.125	Center
	108	3.125 (Q2 ONLY)	1.125 (Q4 ONLY)
	1012	5.125	0.875
	1016	7.125	0.875
	1020	9.125	0.875
	1112	5.125	1.625
	1114	6.125	1.625
	1118	8.125	1.625
	1123	10.812	1.625
0.875	212	5.125	1.875
	1215	6.625	1.875
	1220	9.125	1.875
	1223	10.750	1.875
	1315	6.625	2.375
	1318	8.125	2.375
	1321	9.500	2.375
	1323	10.750	2.375
	1326	12.125	2.375
	1329	13.750	2.375




"B" HALF OF MOLD
FOR 108 - 2435 BASES

PIN DIAMETER (RECOMMENDED)	BASE SIZE	GEx	GEy
1.000	1518	7.938	2.375
	1524	10.875	2.375
	1529	13.750	2.375
	1616	7.000	2.250
	1620	9.000	2.250
	1623	10.750	2.250
	1626	12.000	2.250
	1629	13.750	2.250
	1635	16.750	2.250
	1724	10.875	3.125
	1729	13.750	3.125
	1818	8.000	3.250
	1820	9.000	3.250
	1823	10.750	3.250
	1826	12.000	3.250
	1829	13.750	3.250
	1835	16.750	3.250
1.250	1924	10.875	4.000
	1929	13.750	4.000
	1935	16.750	4.000
	2424	10.688	6.125
	2429	13.563	6.125
	2435	16.563	6.125


SYSTEM 1

When pins are installed in the support plate, the ejector housing can be removed from the mold without removing ejector plates. This permits easy access to service the ejector system.



SYSTEM 2

Pins installed in the ejector housing permit fast installation. When the ejector housing is removed from the mold base, the complete ejector assembly is removed.



Mold Base Features


Guide/Leader Pins & Bushings

Guide/Leader Pins and Bushings align both halves of the mold at the parting line.

Standard Guide Pin diameters and locations, appropriate to mold base sizes are provided in the chart below.

Bushings corresponding to selected plate thickness are provided to match the guide pins.

Relocation or omission of guide pins and bushings is available as a special order.



Guide Pin Bushings Types

Steel (Standard)
Bronze-Plated
Solid Bronze
Self-Lubricating




SIZE	DIA	LPxos	LPx	LPy
88	0.750	3.000	3.125	3.125
812	0.750	5.000	5.125	3.125
108	0.750	2.938	3.125	4.062
1012	0.875	4.875	5.062	4.000
1016	0.875	6.938	7.125	4.000
1020	0.875	8.938	9.125	4.000
1112	0.875	4.938	5.125	4.562
1114	0.875	5.938	6.125	4.562
1118	0.875	7.938	8.125	4.562
1123	0.875	10.688	10.875	4.562
1212	1.000	4.625	4.812	5.000
1215	1.000	6.125	6.312	5.000
1220	1.000	8.625	8.812	5.000
1223	1.000	10.375	10.562	5.000
1315	1.000	6.125	6.312	5.688
1318	1.000	7.375	7.562	5.688
1321	1.000	8.750	8.938	5.688
1323	1.000	10.125	10.312	5.688
1326	1.000	11.375	11.562	5.688
1329	1.000	13.125	13.312	5.688
1518	1.250	7.375	7.562	6.062
1524	1.250	10.250	10.438	6.062
1529	1.250	13.125	13.312	6.062
1616	1.250	6.375	6.562	6.562
1620	1.250	8.375	8.562	6.562
1623	1.250	10.125	10.312	6.562
1626	1.250	11.375	11.562	6.562
1629	1.250	13.125	13.312	6.562
1635	1.250	16.125	16.312	6.562
1724	1.250	10.250	10.438	6.812
1729	1.250	13.125	13.312	6.812
1818	1.250	7.375	7.562	7.562
1820	1.250	8.375	8.562	7.562
1823	1.250	10.125	10.312	7.562
1826	1.250	11.375	11.562	7.562
1829	1.250	13.125	13.312	7.562
1835	1.250	16.125	16.312	7.562
1924	1.250	10.250	10.438	8.312
1929	1.250	13.125	13.312	8.312
1935	1.250	16.125	16.312	8.312
2424	1.500	10.062	10.250	10.250
2429	1.500	12.938	13.125	10.250
2435	1.500	15.938	16.125	10.250

Mold Base Features

Assembly Screws

Assembly screws are used to hold the plates of the upper and lower halves of the mold together. For simplicity, the upper and lower assembly screws are generally placed in similar positions. See chart on next page for standard Assembly Screw locations. Relocation or omission of Assembly Screws is optional as a special order.



Mold Base Features

Assembly Screws

BASE SIZE	SCREW SIZE	UASy LASy	UASx1 LASx1	UASx2 LASx2	UASx3 LASx3	UASx4 LASx4	UASx5 LASx5	UASx6 LASx6	UASx7 LASx7	UASx8 LASx8	UASx9 LASx9	UASx10 LASx10	UASx11 LASx11	UASx12 LASx12
88	1/2-13	3.125	1.375	—	—	—	—	1.375	1.375	—	—	—	—	1.375
812	1/2-13	3.125	2.250	—	—	—	—	2.250	2.250	—	—	—	—	2.250
108	1/2-13	4.000	1.875	—	—	—	—	1.875	1.875	—	—	—	—	1.875
1012	1/2-13	4.000	3.250	—	—	—	—	3.250	3.250	—	—	—	—	3.250
1016	1/2-13	4.000	5.000	—	—	—	—	5.000	5.000	—	—	—	—	5.000
1020	1/2-13	4.000	6.500	—	—	1.000	—	6.500	6.500	—	1.000	—	—	6.500
1112	1/2-13	4.469	3.188	—	—	—	—	3.188	3.188	—	—	—	—	3.188
1114	1/2-13	4.469	3.188	—	—	—	—	3.188	3.188	—	—	—	—	3.188
1118	1/2-13	4.469	5.875	—	—	1.000	—	5.875	5.875	—	1.000	—	—	5.875
1123	1/2-13	4.469	8.625	—	3.188	3.188	—	8.625	8.625	—	3.188	3.188	—	8.625
1212	1/2-13	4.969	2.812	—	—	—	—	2.812	2.812	—	—	—	—	2.812
1215	1/2-13	4.969	4.500	—	—	1.000	—	4.500	4.500	—	1.000	—	—	4.500
1220	1/2-13	4.969	6.625	—	—	1.000	—	6.625	6.625	—	1.000	—	—	6.625
1223	1/2-13	4.969	8.000	—	2.750	2.750	—	8.000	8.000	—	2.750	2.750	—	8.000
1315	1/2-13	5.719	4.500	—	—	1.000	—	4.500	4.500	—	1.000	—	—	4.500
1318	1/2-13	5.719	5.438	—	—	1.000	—	5.438	5.438	—	1.000	—	—	5.438
1321	1/2-13	5.719	6.750	—	—	1.000	—	6.750	6.750	—	1.000	—	—	6.750
1323	1/2-13	5.719	8.125	—	2.750	2.750	—	8.125	8.125	—	2.750	2.750	—	8.125
1326	1/2-13	5.719	9.375	—	3.250	3.250	—	9.375	9.375	—	3.250	3.250	—	9.375
1329	1/2-13	5.719	11.125	—	3.250	3.250	—	11.125	11.125	—	3.250	3.250	—	11.125
1518	1/2-13	6.469	5.438	—	—	1.000	—	5.438	5.438	—	1.000	—	—	5.438
1524	1/2-13	6.469	7.750	—	2.750	2.750	—	7.750	7.750	—	2.750	2.750	—	7.750
1529	1/2-13	6.469	10.625	—	3.688	3.688	—	10.625	10.625	—	3.688	3.688	—	10.625
1616	1/2-13	6.969	4.250	—	—	1.000	—	4.250	4.250	—	1.000	—	—	4.250
1620	1/2-13	6.969	6.250	—	1.000	1.000	—	6.250	6.250	—	1.000	1.000	—	6.250
1623	1/2-13	6.969	8.000	—	2.750	2.750	—	8.000	8.000	—	2.750	2.750	—	8.000
1626	1/2-13	6.969	9.375	—	3.125	3.125	—	9.375	9.375	—	3.125	3.125	—	9.375
1629	1/2-13	6.969	11.000	—	3.688	3.688	—	11.000	11.000	—	3.688	3.688	—	11.000
1635	1/2-13	6.969	14.000	8.500	2.875	2.875	8.500	14.000	14.000	8.500	2.875	2.875	8.500	14.000
1724	1/2-13	7.281	7.750	—	2.750	2.750	—	7.750	7.750	—	2.750	2.750	—	7.750
1729	1/2-13	7.281	10.625	—	3.688	3.688	—	10.625	10.625	—	3.688	3.688	—	10.625
1818	1/2-13	7.969	5.438	—	—	1.000	—	5.438	5.438	—	1.000	—	—	5.438
1820	1/2-13	7.969	6.438	—	—	1.000	—	6.438	6.438	—	1.000	—	—	6.438
1823	1/2-13	7.969	8.000	—	2.750	2.750	—	8.000	8.000	—	2.750	2.750	—	8.000
1826	1/2-13	7.969	9.375	—	3.125	3.125	—	9.375	9.375	—	3.125	3.125	—	9.375
1829	1/2-13	7.969	11.125	—	3.688	3.688	—	11.125	11.125	—	3.688	3.688	—	11.125
1835	1/2-13	7.969	14.125	8.500	2.875	2.875	8.500	14.125	14.125	8.500	2.875	2.875	8.500	14.125
1924	1/2-13	8.781	7.750	—	2.750	2.750	—	7.750	7.750	—	2.750	2.750	—	7.750
1929	1/2-13	8.781	11.125	—	3.688	3.688	—	11.125	11.125	—	3.688	3.688	—	11.125
1935	1/2-13	8.781	14.125	8.500	2.875	2.875	8.500	14.125	14.125	8.500	2.875	2.875	8.500	14.125
2424	5/8-11	10.844	7.750	—	2.750	2.750	—	7.750	7.750	—	2.750	2.750	—	7.750
2429	5/8-11	10.844	10.625	—	3.688	3.688	—	10.625	10.625	—	3.688	3.688	—	10.625
2435	5/8-11	10.844	13.625	8.500	2.750	2.750	8.500	13.625	13.625	8.500	2.750	2.750	8.500	13.625

Mold Base Features

Return Pins & Stop Discs

Return Pins are used to ensure correct return of the ejector assembly to the home position. DME return pins are precision-ground from superior quality hotwork die steel. Stop Discs arrest travel – preventing excessive wear and possible housing damage Standard locations indicated in the chart below

Relocation or omission of Return Pins and Stop Discs is available as a special order.

BASE SIZE	RP DIAMETER (RECOMMENDED)	RP-y SP-y	POSITION 1		POSITION 2		SP-x1 SP-x6	SP-x2 SP-x7	SP-x3 SP-x8	SP-x4 SP-x9	SP-x5 SP-x10
			RP-xos	RP-x	RP-xos	RP-x					
88	0.500	1.500	3.250	3.375	3.125	3.250	3.250				3.250
812	0.500	1.500	5.250	5.375	5.125	5.250	5.250		On Center		5.250
108	0.625	2.250	3.250	3.375	3.125	3.250	3.250				3.250
1012	0.625	2.250	5.188	5.312	5.063	5.188	5.188		On Center		5.188
1016	0.625	2.250	7.250	7.375	7.125	7.250	7.250	2.500		2.500	7.250
1020	0.625	2.250	9.250	9.375	9.125	9.250	9.250	3.125		3.125	9.250
1112	0.625	2.812	5.250	5.375	5.125	5.250	5.250	0.750 (X2 ONLY)		0.750 (X9 ONLY)	5.250
1114	0.625	2.812	6.250	6.375	6.125	6.250	6.250	1.000 (X7 ONLY)		1.000 (X4 ONLY)	6.250
1118	0.625	2.812	8.250	8.375	8.125	8.250	8.250	4.000		4.000	8.250
1123	0.625	2.812	11.000	11.125	10.875	11.000	11.000	3.750		3.750	11.000
1212	0.750	3.188	5.250	5.375	5.063	5.188	5.188		On Center		5.188
1215	0.750	3.188	6.750	6.875	6.563	6.688	6.688	2.250		2.250	6.688
1220	0.750	3.188	9.250	9.375	9.063	9.188	9.188	3.094		3.094	9.188
1223	0.750	3.188	11.000	11.125	10.750	10.875	10.875	4.000		4.000	10.875
1315	0.750	3.812	6.750	6.875	6.563	6.688	6.688	2.250		2.250	6.688
1318	0.750	3.812	8.250	8.375	8.063	8.188	8.188	2.750		2.750	8.188
1321	0.750	3.812	9.500	9.625	9.438	9.563	9.563	4.000		4.000	9.563
1323	0.750	3.812	10.875	11.000	10.750	10.875	10.875	4.000		4.000	10.875
1326	0.750	3.812	12.125	12.250	12.063	12.188	12.188	4.000		4.000	12.188
1329	0.750	3.812	13.875	14.000	13.750	13.875	13.875	5.000		5.000	13.875
1518	0.750	3.875	8.125	8.250	7.938	8.063	8.063	2.750		2.750	8.063
1524	0.750	3.875	11.000	11.125	10.875	11.000	11.000	3.750		3.750	11.000
1529	0.750	3.875	13.875	14.000	13.750	13.875	13.875	4.688		4.688	13.875
1616	0.750	4.375	7.125	7.250	7.000	7.125	7.125	2.375		2.375	7.125
1620	0.750	4.375	9.125	9.250	9.000	9.125	9.125	3.063		3.063	9.125
1623	0.750	4.375	10.875	11.000	10.750	10.875	10.875	4.000		4.000	10.875
1626	0.750	4.375	12.125	12.250	12.000	12.125	12.125	4.000		4.000	12.125
1629	0.750	4.375	13.875	14.000	13.750	13.875	13.875	4.688		4.688	13.875
1635	0.750	4.375	16.875	17.000	16.750	16.875	16.875	8.500	On Center	8.500	16.875
1724	0.750	4.625	11.000	11.125	10.875	11.000	11.000	3.750		3.750	11.000
1729	0.750	4.625	13.875	14.000	13.750	13.875	13.875	4.688		4.688	13.875
1818	0.750	5.375	8.125	8.250	8.000	8.125	8.125	2.750		2.750	8.125
1820	0.750	5.375	9.125	9.250	9.000	9.125	9.125	3.063		3.063	9.125
1823	0.750	5.375	10.875	11.000	10.750	10.875	10.875	4.000		4.000	10.875
1826	0.750	5.375	12.125	12.250	12.000	12.125	12.125	4.000		4.000	12.125
1829	0.750	5.375	13.875	14.000	13.750	13.875	13.875	4.688		4.688	13.875
1835	0.750	5.375	16.875	17.000	16.750	16.875	16.875	8.500	On Center	8.500	16.875
1924	0.750	6.125	11.000	11.125	10.875	11.000	11.000	3.750		3.750	11.000
1929	0.750	6.125	13.875	14.000	13.750	13.875	13.875	4.688		4.688	13.875
1935	0.750	6.125	16.875	17.000	16.750	16.875	16.875	8.500	On Center	8.500	16.875
2424	0.750	7.750	11.000	11.125	10.875	11.000	11.000	3.750		3.750	11.000
2429	0.750	7.750	13.875	14.000	13.750	13.875	13.875	4.688		4.688	13.875
2435	0.750	7.750	16.875	17.000	16.750	16.875	16.875	8.438	On Center	8.438	16.875


Mold Base Features

Ejector Housings & Ejector Assembly Screws

The standard DME 3-piece Ejector is made from DME #1 or #7 steel and assembled with Socket Head Stripper Bolts.

Standard assembly screw locations are indicated in the chart below.

Assembly screw relocation is available upon special request.




BASE SIZE	SCREW SIZE	EASx	EASy
88	5/16-18	3.375	2.250
812	5/16-18	5.375	2.250
108	5/16-18	3.375	3.062
1012	5/16-18	5.312	3.062
1016	5/16-18	7.375	3.062
1020	5/16-18	9.375	3.062
1112	5/16-18	4.562	3.312
1114	5/16-18	5.562	3.312
1118	5/16-18	7.562	3.312
1123	5/16-18	10.312	3.312
1212	5/16-18	4.500	3.812
1215	5/16-18	6.000	3.812
1220	5/16-18	8.500	3.812
1223	5/16-18	10.250	3.812
1315	3/8-16	5.812	4.250
1318	3/8-16	7.312	4.250
1321	3/8-16	8.688	4.250
1323	3/8-16	10.062	4.250
1326	3/8-16	11.312	4.250
1329	3/8-16	13.062	4.250
1518	3/8-16	8.312	5.000
1524	3/8-16	11.250	5.000

BASE SIZE	SCREW SIZE	EASx	EASy
1529	3/8-16	14.125	5.000
1616	3/8-16	7.375	5.438
1620	3/8-16	9.375	5.438
1623	3/8-16	11.125	5.438
1626	3/8-16	12.375	5.438
1629	3/8-16	14.125	5.438
1635	3/8-16	17.125	5.438
1724	3/8-16	11.250	5.750
1729	3/8-16	14.125	5.750
1818	3/8-16	8.375	6.500
1820	3/8-16	9.375	6.438
1823	3/8-16	11.125	6.438
1826	3/8-16	12.375	6.438
1829	3/8-16	14.125	6.438
1835	3/8-16	17.125	6.438
1924	1/2-13	11.250	7.250
1929	1/2-13	14.125	7.250
1935	1/2-13	17.125	7.250
2424	1/2-13	11.250	8.875
2429	1/2-13	14.125	8.875
2435	1/2-13	17.125	8.875

Leader Pin Vents

Leader Pin Vents, which allow trapped air to escape from the mold, are designed into all 15-inch-and-wider series molds.

When desired, they can be specified on smaller molds.





Mold Base Features

Pry Slots

Pry slots provide handling ease when opening and/or disassembling a mold.

DME Classic 2.0 mold bases come standard with pry slots on the A-plate or A-clamping plates & Support plate parting lines. Additional pry slots can be machined via special request.




Lifting Holes

Lifting Holes are used to install hoist rings for easy handling. Mold bases come standard with lift holes in the Top Clamp/A-clamping plate, B-plate, Support plate and Ejector plate. Mold base can be configured only with Lifting Holes which are appropriate for the specific mold base size. Refer to the DME Mold Components catalog for a comprehensive selection of hoist rings.

BASE SIZE	PLATE THICKNESS	
	0.875	1.375
88-1118	1/2-13 UNC	1/2-13 UNC
1123-1524	5/8-11 UNC	5/8-11 UNC
1529-1829	5/8-11 UNC	3/4-10 UNC
1835-2429	5/8-11 UNC	1"-8 UNC
2435	N/A	1"-8 UNC

Lifting Holes

THREAD SIZE	S	T MAX.
1/2-13	1.00	1.38
5/8-11	1.25	1.75
3/4-10	1.50	2.00
1"-8	2.00	2.62



Custom Mold Base Features

Pockets

Per customer specifications, any type of cavity and core pockets can be machined. Blind or Through, Rough or Finished. Please provide prints for quoting.



Corner Radius - .50 min. / 1.00 max

Pocket Tolerances:

Rough - .062 per side

Finished - +/- .001



Contour Roughing Services

At the request of moldmakers, DME contour roughing services are available to rough mill complex part shapes into mold plates, even for milling that requires large and deep cavities.

- » The Contour Roughing Service begins with complex core and cavity CAD files from customers
- » Industry-leading CAM software enables the programming of contour roughing tool paths, leaving consistent machining allowance throughout the surface of the cavity block
- » 3D cavity roughing tool paths to generate a rough milled surface, allowing machining stock for finishing by the customer.



Key Advantages of Contour Roughing

Moldmakers can use this service to extend their in-house capacity, reduce lead time and focus on other high-value machining

Consistent machining allowance throughout the surface of the cavity block provides even finishing without areas of heavy stock

DME Contour Roughing Services from DME can provide customers with the CAM program to continue the work where we left off, saving time and programming expense



Contour roughing can be bundled with the option to stress-relieve cavity blocks and a custom mold base

For more details on the Contour Roughing Service, contact your DME representative today.

Spring Pockets

Machining for Spring Pockets can be done upon request.

See DME Mold Components catalog for spring free lengths and hole dimensions.



Mold Base Features

Mold Strap Holes

Machined holes will be for mounting mold straps. Please provide desired positions and quantity (minimum 2).

- Ideal for securing mold assembly stack-ups during transport or storage
- Offered as pairs in three sizes
- Constructed of cast metal for strength and durability
- Yellow-powder coating provides corrosion resistance and high visibility

ITEM NO	SHCS	CAPACITY	TORQUE
MLDST088	1/4" - 20 UNC x 3/8" LONG	930 LBS	13 FT LBS
MLDST150	5/16" - 18 UNC x 3/4" LONG	1220 LBS	27 FT LBS
MLDST200	1/2" - 13 UNC x 1" LONG	1740 LBS	130 FT LBS



Mold Interlocks

DME Interlocks are precision toleranced and precision manufactured to provide off-the-shelf interchangeability and accurate alignment of mold halves. Interlock machining available upon request.


See Mold Component catalog for information on the complete line of DME Mold Interlocks



Leader Pin Bushings

Standard steel leader pin bushings can be replaced with Self-lubricating, Bronze-Plated or Solid Bronze bushings. These bushing come with a shoulder or straight.

See DME Mold Components catalog for optional leader pin bushing selection.




Mold Base Features

Support Pillars

Support Pillars greatly increase the capacity of the mold to support the projected area of the cavities, runner and sprue. By providing additional support, they prevent deflection of the mold. Support Pillars are universally adaptable for cap screw, threaded locating pin, or socket set screw application.

Support Pillar information can be found in the Mold Component catalog




High Temperature Insulator Sheets

DME High Temperature Insulator Sheets are used on molds and dies between the top clamping plate and the stationary platen, and between the bottom of the ejector housing and the movable platen. Available 1/4" or 1/2" thick ready to install.

- Asbestos-free material
- High compression strength
- Machinable with high-speed cutting tools

General Data

COMPRESSIVE STRENGTH	(ASTM D-229)	49,400 PSI AT 75°F 27,200 PSI AT 300°F 18,000 PSI AT 400°F 17,100 PSI AT 500°F 15,000 PSI AT 550°F
MODULUS OF ELASTICITY IN COMPRESSION	(ASTM D-229)	1.8×10^6 PSI AT 75°F 2.9×10^6 PSI AT 425°F
WATER ABSORPTION	(ASTM D-229)	0.2%
THERMAL CONDUCTIVITY (K FACTOR), (BTU/HR/FT ² /IN/°F)	(ASTM C-177)	1.9 AT 75°F 2.1 AT 425°F
FLAME RESISTANCE	(UL SUBJECT 94)	94V-0
EXPANSION ACROSS THICKNESS EXPANSION ACROSS SURFACE		6.43×10^{-5} IN/IN/°F 1.24×10^{-5} IN/IN/°F
MAXIMUM RECOMMENDED SERVICE TEMPERATURE		550°F



ENERGY SAVINGS


1/4 THICK = 27,508 BTU/HR

1/2 THICK = 31,004 BTU/HR


Mold Base Features

Three-Plate Extension Bushings

Three-Plate Extension Bushings can save material, reduce cycle time and help prevent runner hang-ups in 3-plate molds.



**Runner Stripper Plate
Bushing TEB-0001**



NOTES:

1. Stripper plate bushing TEB-0001 is used with all small and large extension nozzle bushings.
2. Appropriate S.H.C.S. are included with all bushings (TEB-0001 thru TEB-0009).
3. Select small or large bushing based on "A" clamping plate (A.C.P.) thickness, X-1 stripper plate thickness, machine nozzle spherical radius and machine nozzle clearance requirements.

ITEM NUMBER	R SPH. RAD	Ø A	Ø B	Ø C	E	F	G	H	J	K	L
TEB-0002	1/2	4.490	2.375	3.120	.375	2.265	1.377	1.875	2.640	#10-24 x 7/8 LONG (2) INCLUDED	1.781
TEB-0003	3/4							1.812			
TEB-0004	1/2							2.375			
TEB-0005	3/4							2.312			
TEB-0006	1/2	5.490	3.250	3.932	.750	2.765	1.877	2.375	3.140	5/16-18 X 7/8 LONG (2) INCLUDED	2.312
TEB-0007	3/4							2.312			
TEB-0008	1/2							2.875			
TEB-0009	3/4							2.812			


Waterlines

DME will provide waterlines and plugs per customer specifications. Diameter, plates to be machined for waterlines, and total length of waterlines in each plate.

Jiffy-Tite® Plugs (JP)

Male Plug Mounting Information

ITEM NUMBER	NPT	HEX SIZE	A	B	C	H
JP-250	1/16	7/16	11/16	11/16	1"	5/8
JP-251	1/8	7/16	11/16	11/16	1"	5/8
JP-252-(SV)	1/4	9/16	27/32	15/16	13/16	7/8
JP-253-(SV)	3/8	11/16	1.000	15/16	1 1/4	29/32
JP-351	1/8	9/16	1.000	15/16	1 1/4	7/8
JP-352-(SV)	1/4	9/16	1.000	13/32	17/16	1 1/32
JP-353-(SV)	3/8	11/16	1.000	1 1/8	17/16	1 1/16
JP-354-(SV)	1/2	7/8	1 3/16	1 1/4	1 9/16	1 3/16
JP-553	3/8	7/8	1 1/4	1 3/16	1 5/8	1 1/8
JP-554	1/2	7/8	1 1/4	1 1/2	1 13/16	1 7/16
JP-556	3/4	1 1/8	1 1/2	1 9/16	1 7/8	1 1/2





DME American Standard Mold Bases

**Mold Bases with optional
feature-based selections**

Table of Contents



A-Series Mold Bases.....31

Available in 43 sizes from 7.875 x 7.875 to 23.75 x 35.5, the DME A-Series Mold Base is the most frequently used standard assembly

B-Series Mold Bases.....122



X, AX, T-Series 123-146

When you need a floating plate or two or stripper plate ejection, DME mold base assemblies to get the job done



Small & Shuttle Mold Bases..... 150-159

Lower your mold costs with Small Mold Base Adapter Plates and Shuttle Mold Bases



Immediate price and stock information 24/7

DME Classic 2.0 A-Series Mold Bases

OVER 75 TRILLION POSSIBLE
MOLD BASE CONFIGURATIONS



A-Series Mold Bases

Table of Contents

88A	36-37	1318A	66-67	1729A	96-97
812A	38-39	1321A	68-69	1818A	98-99
108A	40-41	1323A	70-71	1820A	100-101
1012A	42-43	326A	72-73	1823A	102-103
1016A	44-45	1329A	74-75	1826A	104-105
1020A	46-47	518A	76-77	1829A	106-107
1112A	48-49	1524A	78-79	1835A	108-109
1114A	50-51	1529A	80-81	1924A	110-111
1118A	52-53	1616A	82-83	1929A	112-113
1123A	54-55	1620A	84-85	1935A	114-115
1212A	56-57	1623A	86-87	2424A	116-117
1215A	58-59	1626A	88-89	2429A	118-119
1220A	60-61	1629A	90-91	2435A	120-121
1223A	62-63	1635A	92-93	B-Series Mold Bases.....	122
1315A	64-65	724A	94-95		

Mold Base Key Features

Nobody delivers like the DME American Standard Mold Base. With an infinite number of possible configurations. Some key features and options include:

How to use this catalog

The following pages detail the choices available. If you have questions contact us and one of our knowledgeable representatives will assist you.

43 Nominal Sizes

9 Plate Thicknesses

3 Steel Types

Guided Ejection (optional)

Pry Slots

Lifting Holes

Leader Pin Vents

Feature Positions

Feature Omissions

3-Piece Housings


Clamp Slots

Mixed Steel

Stop Discs




American Classic 2.0 Standard Mold Base Selections




A-Series

The most frequently used Standard Assembly, the A-Series Mold Base is available in 43 sizes from 7.875 x 7.875 to 23.75 x 35.5.




B-Series

When cavities and cores are to be inserted into blind pockets, or machined directly into the A- and B-plates, the B-Series Assembly is used. The Top Clamping Plate and Support Plate are omitted from the assembly.




AX-Series

The AX-Series Assembly is used when the mold requires a floating plate to remain with the upper or stationary half of the assembly. It is basically an A-Series Assembly with a floating plate (X-1) added.



T-Series

The T-Series Assembly is used for top runner molds that require two floating plates (X-1 – runner stripper plate, X-2 – cavity plate) to remain with the upper or stationary half of the assembly.



X-Series (5 Plate)

Most frequently used for molds requiring stripper plate ejection, the X-Series Assembly is available with a Support Plate (6-plate series) or without a Support Plate (5-plate series).

X-Series (6 Plate)

NOTE: Location and diameter of standard components are identical for all mold base series.

DME American Standard Steel Types

Synonymous with mold making are the DME American Standard Steel Types. Our experience in selecting mold steel ensures the cleanliness, durability and machinability appropriate to your application.

Steels for Structural and Holder Block Applications

DME #1 Steel is a medium carbon quality steel with greater tensile strength than typical plain carbon warehouse steels. It machines easily, but is not "sticky", permitting a faster and smoother cut. International comparisons: DIN 1.1178 (CK 30) and 1.1730 (C 45 W); JIS S 30 CM, S50C, S55C; ISO 683-1 C30E4.

DME #2 Steel is a medium alloy steel specified for durability in structural applications. It is supplied pre-heat treated to 28-34 HRC (271-321 Bhn). A high strength steel, it is ideal for cavity and core retainer plates, clamping plates and support plates in molds. International comparisons: DIN 1.2312 (40CrMnMoS 8 6), 1.7218 (25CrMo4) and 1.2331 (41CrMoS4); JIS SCM 430; ISO 683-2 Type 1. *(Available upon request)*

DME #7 Steel is a modified AISI 400 series stainless steel for holder block applications. It is supplied pre-heat treated to 32-36 HRC (302-340 Bhn). This stainless steel offers corrosion-resistance and exceptional machinability but cannot be further hardened (see DME #6). For humid environments, corrosive plastics, "clean room" or "100% stainless" applications, it is an ideal choice for all structural mold plates. International comparisons: none.

Steels for Cavity & Core Applications

DME #3 Steel is a P-20 AISI 4130 type cavity steel. Exceptionally clean, it is pre-heat treated to 28-34 HRC (271-321 Bhn). It provides good machinability, the ability to heat treat to higher hardness, and exceptional polishability. International comparisons: DIN 1.2311 G40CrMnMo7; JIS none; ISO none.

DME #5 Steel is an AISI/SAE H-13 type thermal shock resistant, hotwork die steel. Supplied fully annealed (approximately 200 Bhn; 13-20 HRC) for easy machinability, it can be subsequently heat treated to the desired hardness with a minimum of deformation. Mainly used for die cast dies, it is also suitable for plastic molds with exceptional hardness or polishability requirements. DME #5 Steel meets or exceeds the acceptance criteria established by the NADCA as detailed in Technical Digest Number 01-80-01D. International comparisons: DIN 1.2344 (X40CrMoV5-1); JIS SKD 61; ISO 4955 H13.



DME #6 Steel is a modified AISI 420 type stainless steel. It is supplied fully annealed to 179-241 Bhn (8-23 HRC), making it readily machinable. Unlike DME #7 steel, DME #6 steel is a cavity-grade material that can be subsequently heat treated to the desired hardness and has excellent polishability. International comparisons: DIN 1.4028 (X30Cr13); JIS SUS 420 J 2; ISO none.





Typical Steel Types Configurations

A-Series Mold Bases are available in over 40 standard sizes, 7-7/8 x 7-7/8 to 23-3/4 x 35-1/2. Each size offers a wide variety of standard cavity plate thickness combinations, plus your choice of DME No. 1, No. 3 or No. 7 steel.



No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Steel Selections: Available in 43 Nominal Sizes

MOLD PLATE	STEEL TYPES					
	#1	#2	#3	#7	#5	#6
TOP CLAMP PLATE			⚡	⚡		
AC PLATE			⚡	⚡		
A PLATE	⚡		⚡	⚡*		
B PLATE	⚡		⚡	⚡*		
AX, BX PLATES			⚡	⚡		
XP, X-1 AND X-2 PLATES			⚡	⚡		
SUPPORT PLATE			⚡	⚡		
EJECTOR RETAINER PLATE	⚡			⚡		
EJECTOR BAR PLATE	⚡			⚡		
EJECTOR HOUSING - THREE PIECE	⚡			⚡		

DME mold base assemblies are regularly comprised of mixed steel types to deliver plates configured to your application requirements. You can select steel types for each plate, as available from the table at left, in any combination for your mold base.



= Standard



= Not available as standard.
Contact DME for quote. DME
Customer Service can quote up to
5.875 thickness plates on all plates.


*Up to 2.375 thickness

NOTE: AC plates are not recommended.

The American Classic 2.0 Mold Base is available in 43 nominal sizes to match the mold space requirements for your application.

As the creator of the American mold base standard, we have the largest selection of mold base sizes.

NOTE: Drilled complete replacement plates available .




NOTE: Approximate mold base weight can be estimated with the following formula:
WEIGHT = WIDTH x LENGTH x HEIGHT x .283 x 90%

NOMINAL SIZE	WIDTH (IN)	LENGTH (IN)	WEIGHT RANGE (LBS)	
			MIN	MAX
88	7.875	7.875	116	305
812	7.875	11.875	175	460
108	9.875	8.000	156	393
1012	9.875	11.875	235	592
1016	9.875	16.000	316	798
1020	9.875	20.000	395	997
1112	10.875	12.000	261	659
1114	10.875	14.000	305	769
1118	10.875	18.000	392	988
1123	10.875	23.500	511	1290
1212	11.875	12.000	285	719
1215	11.875	15.000	379	899
1220	11.875	20.000	505	1199
1223	11.875	23.500	594	1409
1315	13.375	15.000	427	1038
1318	13.375	18.000	512	1246
1321	13.375	20.750	590	1436
1323	13.375	23.500	669	1627
1326	13.375	26.000	740	1800
1329	13.375	29.500	839	2042
1518	14.875	17.875	599	1410
1524	14.875	23.750	796	1873
1529	14.875	29.500	989	2327
1616	15.875	16.000	573	1347
1620	15.875	20.000	716	1683
1623	15.875	23.500	841	1978
1626	15.875	26.000	930	2189
1629	15.875	29.500	1056	2483
1635	15.875	35.500	1270	2988
1724	16.500	23.750	883	2078
1729	16.500	29.500	1097	2581
1818	17.875	18.000	725	1706
1820	17.875	20.000	806	1896
1823	17.875	23.500	947	2227
1826	17.875	26.000	1048	2464
1829	17.875	29.500	1189	2796
1835	17.875	35.500	1430	3365
1924	19.500	23.750	1044	2456
1929	19.500	29.500	1297	3050
1935	19.500	35.500	1648	3758
2424	23.750	23.750	1343	3062
2429	23.750	29.500	1668	3804
2435	23.750	35.500	2008	4578


7/8 x 7/8 A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

7/8 x 7/8 A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.375	88A-7-7	111
	1.375	2.500	7.875	88A-7-13	120
	1.875	2.500	8.375	88A-7-17	129
	2.375	2.500	8.875	88A-7-23	138
	2.875	3.000	9.875	88A-7-27	149
	3.375	3.500	10.875	88A-7-33	161
	3.875	3.500	11.375	88A-7-37	170
	4.875	4.500	13.375	88A-7-47	193
	5.875	4.500	14.375	88A-7-57	211

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	2.500	8.875	88A-23-7	138
	1.375	2.500	9.375	88A-23-13	147
	1.875	2.500	9.875	88A-23-17	155
	2.375	3.000	10.875	88A-23-23	167
	2.875	3.500	11.875	88A-23-27	179
	3.375	4.000	12.875	88A-23-33	190
	3.875	4.000	13.375	88A-23-37	199
	4.875	4.500	14.875	88A-23-47	219
	5.875	4.500	15.875	88A-23-57	237

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	10.875	88A-37-7	167
	1.375	3.500	11.875	88A-37-13	179
	1.875	3.500	12.375	88A-37-17	187
	2.375	4.000	13.375	88A-37-23	199
	2.875	4.000	13.875	88A-37-27	208
	3.375	4.000	14.375	88A-37-33	217
	3.875	4.500	15.375	88A-37-37	228
	4.875	4.500	16.375	88A-37-47	246
	5.875	4.500	17.375	88A-37-57	263

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	7.875	88A-13-7	120
	1.375	2.500	8.375	88A-13-13	129
	1.875	2.500	8.875	88A-13-17	138
	2.375	3.000	9.875	88A-13-23	149
	2.875	3.000	10.375	88A-13-27	158
	3.375	3.500	11.375	88A-13-33	170
	3.875	4.000	12.375	88A-13-37	181
	4.875	4.500	13.875	88A-13-47	202
	5.875	4.500	14.875	88A-13-57	219

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	9.875	88A-27-7	149
	1.375	3.000	10.375	88A-27-13	158
	1.875	3.500	11.375	88A-27-17	170
	2.375	3.500	11.875	88A-27-23	179
	2.875	4.000	12.875	88A-27-27	190
	3.375	4.000	13.375	88A-27-33	199
	3.875	4.000	13.875	88A-27-37	208
	4.875	4.500	15.375	88A-27-47	228
	5.875	4.500	16.375	88A-27-57	246

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.375	88A-47-7	187
	1.375	3.500	12.875	88A-47-13	196
	1.875	4.000	13.875	88A-47-17	208
	2.375	4.000	14.375	88A-47-23	217
	2.875	4.000	14.875	88A-47-27	225
	3.375	4.500	15.875	88A-47-33	237
	3.875	4.500	16.375	88A-47-37	246
	4.875	4.500	17.375	88A-47-47	263
	5.875	4.500	18.375	88A-47-57	281

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.375	88A-17-7	129
	1.375	2.500	8.875	88A-17-13	138
	1.875	2.500	9.375	88A-17-17	147
	2.375	3.000	10.375	88A-17-23	158
	2.875	3.500	11.375	88A-17-27	170
	3.375	3.500	11.875	88A-17-33	179
	3.875	4.000	12.875	88A-17-37	190
	4.875	4.500	14.375	88A-17-47	211
	5.875	4.500	15.375	88A-17-57	228

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.375	88A-33-7	158
	1.375	3.500	11.375	88A-33-13	170
	1.875	3.500	11.875	88A-33-17	182
	2.375	4.000	12.875	88A-33-23	190
	2.875	4.000	13.375	88A-33-27	199
	3.375	4.000	13.875	88A-33-33	208
	3.875	4.500	14.875	88A-33-37	219
	4.875	4.500	15.875	88A-33-47	237
	5.875	4.500	16.875	88A-33-57	255

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.375	88A-57-7	205
	1.375	3.500	13.875	88A-57-13	214
	1.875	4.000	14.875	88A-57-17	225
	2.375	4.000	15.375	88A-57-23	234
	2.875	4.000	15.875	88A-57-27	243
	3.375	4.500	16.875	88A-57-33	255
	3.875	4.500	17.375	88A-57-37	263
	4.875	4.500	18.375	88A-57-47	281
	5.875	4.500	19.375	88A-57-57	298

Other plate thickness, riser height and ejector bar length options available


CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.

C RISER			EB EJECTOR BAR	
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR	E LENGTH NOM.	EJECTOR BAR LENGTH NO.
2.500	25	0.813	7.85	8
3.000	30	1.313	11.85	12
3.500	35	1.813	15.97	16
4.000	40	2.313	19.97	20
4.500	45	2.813		
5.000	50	3.313		
5.500	55	3.813		
6.000	60	4.313		

See Item 6 below.

See Item 8 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., U, UV, UR, *B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218 or .281
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed (Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Other features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


7/8 x 11 7/8 A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)


B-Series Assembly




Steel Configurations available in:

Steel


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

7/8 x 11 7/8 A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.375	812A-7-7	174
	1.375	3.000	8.375	812A-7-13	191
	1.875	3.000	8.875	812A-7-17	205
	2.375	3.500	9.875	812A-7-23	222
	2.875	3.500	10.375	812A-7-27	235
	3.375	4.000	11.375	812A-7-33	253
	3.875	4.000	11.875	812A-7-37	266
	4.875	4.500	13.375	812A-7-47	297
	5.875	4.500	14.375	812A-7-57	323

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.375	812A-23-7	218
	1.375	3.000	9.875	812A-23-13	231
	1.875	3.500	10.875	812A-23-17	249
	2.375	3.500	11.375	812A-23-23	262
	2.875	4.000	12.375	812A-23-27	279
	3.375	4.000	12.875	812A-23-33	293
	3.875	4.000	13.375	812A-23-37	306
	4.875	4.500	14.875	812A-23-47	336
	5.875	4.500	15.875	812A-23-57	363

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	10.875	812A-37-7	258
	1.375	3.500	11.875	812A-37-13	275
	1.875	3.500	12.375	812A-37-17	288
	2.375	4.000	13.375	812A-37-23	306
	2.875	4.000	13.875	812A-37-27	319
	3.375	4.000	14.375	812A-37-33	332
	3.875	4.500	15.375	812A-37-37	350
	4.875	4.500	16.375	812A-37-47	376
	5.875	4.500	17.375	812A-37-57	403

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	7.875	812A-13-7	187
	1.375	3.000	8.875	812A-13-13	205
	1.875	3.000	9.375	812A-13-17	218
	2.375	3.500	10.375	812A-13-23	235
	2.875	3.500	10.875	812A-13-27	249
	3.375	4.000	11.875	812A-13-33	266
	3.875	4.000	12.375	812A-13-37	279
	4.875	4.500	13.875	812A-13-47	310
	5.875	4.500	14.875	812A-13-57	336

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	9.875	812A-27-7	231
	1.375	3.000	10.375	812A-27-13	244
	1.875	3.500	11.375	812A-27-17	262
	2.375	3.500	11.875	812A-27-23	275
	2.875	4.000	12.875	812A-27-27	293
	3.375	4.000	13.375	812A-27-33	306
	3.875	4.000	13.875	812A-27-37	319
	4.875	4.500	15.375	812A-27-47	350
	5.875	4.500	16.375	812A-27-57	376

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.375	812A-47-7	288
	1.375	3.500	12.875	812A-47-13	302
	1.875	4.000	13.875	812A-47-17	319
	2.375	4.000	14.375	812A-47-23	332
	2.875	4.000	14.875	812A-47-27	346
	3.375	4.500	15.875	812A-47-33	363
	3.875	4.500	16.375	812A-47-37	376
	4.875	4.500	17.375	812A-47-47	403
	5.875	4.500	18.375	812A-47-57	429

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.375	812A-17-7	200
	1.375	3.000	9.375	812A-17-13	218
	1.875	3.500	10.375	812A-17-17	235
	2.375	3.500	10.875	812A-17-23	249
	2.875	4.000	11.875	812A-17-27	266
	3.375	4.000	12.375	812A-17-33	279
	3.875	4.000	12.875	812A-17-37	293
	4.875	4.500	14.375	812A-17-47	323
	5.875	4.500	15.375	812A-17-57	350

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.375	812A-33-7	244
	1.375	3.500	11.375	812A-33-13	262
	1.875	3.500	11.875	812A-33-17	275
	2.375	4.000	12.875	812A-33-23	293
	2.875	4.000	13.375	812A-33-27	306
	3.375	4.000	13.875	812A-33-33	319
	3.875	4.500	14.875	812A-33-37	336
	4.875	4.500	15.875	812A-33-47	363
	5.875	4.500	16.875	812A-33-57	389

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.375	812A-57-7	315
	1.375	3.500	13.875	812A-57-13	328
	1.875	4.000	14.875	812A-57-17	346
	2.375	4.000	15.375	812A-57-23	359
	2.875	4.000	15.875	812A-57-27	372
	3.375	4.500	16.875	812A-57-33	389
	3.875	4.500	17.375	812A-57-37	403
	4.875	4.500	18.375	812A-57-47	429
	5.875	4.500	19.375	812A-57-57	456


Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
11.85	12
15.97	16
19.97	20

See Item 6 below.



See Items 7 & 8 below.


See Item 8 below.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., U, UV, UR, *B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218 or .281
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Other features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


9 7/8 x 8" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)


B-Series Assembly




Steel Configurations available in:

Steel


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

9 7/8 x 8" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.875	108A-7-7	158
	1.375	2.500	8.375	108A-7-13	169
	1.875	2.500	8.875	108A-7-17	181
	2.375	3.000	9.875	108A-7-23	195
	2.875	3.500	10.875	108A-7-27	209
	3.375	4.000	11.875	108A-7-33	224
	3.875	4.000	12.375	108A-7-37	236
	4.875	4.500	13.875	108A-7-47	261
	5.875	4.500	14.875	108A-7-57	284

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	108A-23-7	195
	1.375	3.000	10.375	108A-23-13	206
	1.875	3.500	11.375	108A-23-17	221
	2.375	3.500	11.875	108A-23-23	232
	2.875	4.000	12.875	108A-23-27	246
	3.375	4.000	13.375	108A-23-33	257
	3.875	4.000	13.875	108A-23-37	269
	4.875	4.500	15.375	108A-23-47	294
	5.875	4.500	16.375	108A-23-57	317

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	11.375	108A-37-7	229
	1.375	3.500	12.375	108A-37-13	243
	1.875	3.500	12.875	108A-37-17	254
	2.375	4.000	13.875	108A-37-23	269
	2.875	4.000	14.375	108A-37-27	280
	3.375	4.000	14.875	108A-37-33	291
	3.875	4.500	15.875	108A-37-37	306
	4.875	4.500	16.875	108A-37-47	328
	5.875	4.500	17.875	108A-37-57	350

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	8.375	108A-13-7	169
	1.375	2.500	8.875	108A-13-13	181
	1.875	3.000	9.875	108A-13-17	196
	2.375	3.500	10.875	108A-13-23	209
	2.875	3.500	11.375	108A-13-27	221
	3.375	4.000	12.375	108A-13-33	235
	3.875	4.000	12.875	108A-13-37	246
	4.875	4.500	14.375	108A-13-47	272
	5.875	4.500	15.375	108A-13-57	294

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	108A-27-7	206
	1.375	3.000	10.875	108A-27-13	217
	1.875	3.500	11.875	108A-27-17	232
	2.375	3.500	12.375	108A-27-23	244
	2.875	4.000	13.375	108A-27-27	257
	3.375	4.000	13.875	108A-27-33	269
	3.875	4.000	14.375	108A-27-37	280
	4.875	4.500	15.875	108A-27-47	306
	5.875	4.500	16.875	108A-27-57	328

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	108A-47-7	254
	1.375	3.500	13.375	108A-47-13	265
	1.875	4.000	14.375	108A-47-17	280
	2.375	4.000	14.875	108A-47-23	291
	2.875	4.000	15.375	108A-47-27	302
	3.375	4.500	16.375	108A-47-33	317
	3.875	4.500	16.875	108A-47-37	328
	4.875	4.500	17.875	108A-47-47	350
	5.875	4.500	18.875	108A-47-57	373

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.875	108A-17-7	181
	1.375	3.000	9.875	108A-17-13	195
	1.875	3.500	10.875	108A-17-17	209
	2.375	3.500	11.375	108A-17-23	221
	2.875	4.000	12.375	108A-17-27	235
	3.375	4.000	12.875	108A-17-33	246
	3.875	4.000	13.375	108A-17-37	257
	4.875	4.500	14.875	108A-17-47	283
	5.875	4.500	15.875	108A-17-57	306

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.875	108A-33-7	217
	1.375	3.500	11.875	108A-33-13	232
	1.875	3.500	12.375	108A-33-17	243
	2.375	4.000	13.375	108A-33-23	257
	2.875	4.000	13.875	108A-33-27	269
	3.375	4.000	14.375	108A-33-33	280
	3.875	4.500	15.375	108A-33-37	294
	4.875	4.500	16.375	108A-33-47	317
	5.875	4.500	17.375	108A-33-57	339

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	108A-57-7	277
	1.375	3.500	14.375	108A-57-13	288
	1.875	4.000	15.375	108A-57-17	302
	2.375	4.000	15.875	108A-57-23	313
	2.875	4.000	16.375	108A-57-27	325
	3.375	4.500	17.375	108A-57-33	339
	3.875	4.500	17.875	108A-57-37	350
	4.875	4.500	18.875	108A-57-47	373
	5.875	4.500	19.875	108A-57-57	395

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
7.97	8
11.85	12
15.97	16
19.97	20
23.47	23
29.47	29

See Item 6 below.
Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Other features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


9⁷/₈ x 11⁷/₈ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

9 7/8 x 11 7/8 A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.875	1012A-7-7	235
	1.375	3.000	8.875	1012A-7-13	256
	1.875	3.000	9.375	1012A-7-17	273
	2.375	3.500	10.375	1012A-7-23	294
	2.875	3.500	10.875	1012A-7-27	311
	3.375	4.000	11.875	1012A-7-33	332
	3.875	4.000	12.375	1012A-7-37	349
	4.875	4.500	13.875	1012A-7-47	387
	5.875	4.500	14.875	1012A-7-57	420

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1012A-23-7	289
	1.375	3.000	10.375	1012A-23-13	306
	1.875	3.500	11.375	1012A-23-17	327
	2.375	3.500	11.875	1012A-23-23	344
	2.875	4.000	12.875	1012A-23-27	365
	3.375	4.000	13.375	1012A-23-33	382
	3.875	4.000	13.875	1012A-23-37	399
	4.875	4.500	15.375	1012A-23-47	437
	5.875	4.500	16.375	1012A-23-57	470

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	11.375	1012A-37-7	339
	1.375	3.500	12.375	1012A-37-13	361
	1.875	3.500	12.875	1012A-37-17	377
	2.375	4.000	13.875	1012A-37-23	399
	2.875	4.000	14.375	1012A-37-27	415
	3.375	4.000	14.875	1012A-37-33	432
	3.875	4.500	15.875	1012A-37-37	453
	4.875	4.500	16.875	1012A-37-47	486
	5.875	4.500	17.875	1012A-37-57	520

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	8.375	1012A-13-7	251
	1.375	3.000	9.375	1012A-13-13	273
	1.875	3.000	9.875	1012A-13-17	289
	2.375	3.500	10.875	1012A-13-23	311
	2.875	3.500	11.375	1012A-13-27	327
	3.375	4.000	12.375	1012A-13-33	349
	3.875	4.000	12.875	1012A-13-37	365
	4.875	4.500	14.375	1012A-13-47	403
	5.875	4.500	15.375	1012A-13-57	437

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1012A-27-7	306
	1.375	3.000	10.875	1012A-27-13	322
	1.875	3.500	11.875	1012A-27-17	344
	2.375	3.500	12.375	1012A-27-23	361
	2.875	4.000	13.375	1012A-27-27	382
	3.375	4.000	13.875	1012A-27-33	399
	3.875	4.000	14.375	1012A-27-37	415
	4.875	4.500	15.875	1012A-27-47	453
	5.875	4.500	16.875	1012A-27-57	486

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1012A-47-7	377
	1.375	3.500	13.375	1012A-47-13	394
	1.875	4.000	14.375	1012A-47-17	415
	2.375	4.000	14.875	1012A-47-23	432
	2.875	4.000	15.375	1012A-47-27	448
	3.375	4.500	16.375	1012A-47-33	470
	3.875	4.500	16.875	1012A-47-37	486
	4.875	4.500	17.875	1012A-47-47	520
	5.875	4.500	18.875	1012A-47-57	553

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.875	1012A-17-7	268
	1.375	3.000	9.875	1012A-17-13	289
	1.875	3.500	10.875	1012A-17-17	311
	2.375	3.500	11.375	1012A-17-23	327
	2.875	4.000	12.375	1012A-17-27	349
	3.375	4.000	12.875	1012A-17-33	365
	3.875	4.000	13.375	1012A-17-37	382
	4.875	4.500	14.875	1012A-17-47	420
	5.875	4.500	15.875	1012A-17-57	453

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.875	1012A-33-7	322
	1.375	3.500	11.875	1012A-33-13	344
	1.875	3.500	12.375	1012A-33-17	361
	2.375	4.000	13.375	1012A-33-23	382
	2.875	4.000	13.875	1012A-33-27	399
	3.375	4.000	14.375	1012A-33-33	415
	3.875	4.500	15.375	1012A-33-37	437
	4.875	4.500	16.375	1012A-33-47	470
	5.875	4.500	17.375	1012A-33-57	503

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1012A-57-7	410
	1.375	3.500	14.375	1012A-57-13	427
	1.875	4.000	15.375	1012A-57-17	448
	2.375	4.000	15.875	1012A-57-23	465
	2.875	4.000	16.375	1012A-57-27	482
	3.375	4.500	17.375	1012A-57-33	503
	3.875	4.500	17.875	1012A-57-37	520
	4.875	4.500	18.875	1012A-57-47	553
	5.875	4.500	19.875	1012A-57-57	586

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
11.85	12
15.97	16
19.97	20
23.47	23
29.47	29

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For "B" Series, replace "A" with "B")
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Other features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


9⁷/₈ x 16" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

9⁷/₈ x 16" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.875	1016A-7-7	316
	1.375	3.000	8.875	1016A-7-13	345
	1.875	3.000	9.375	1016A-7-17	367
	2.375	3.500	10.375	1016A-7-23	396
	2.875	3.500	10.875	1016A-7-27	418
	3.375	4.000	11.875	1016A-7-33	447
	3.875	4.000	12.375	1016A-7-37	470
	4.875	4.500	13.875	1016A-7-47	521
	5.875	4.500	14.875	1016A-7-57	566

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1016A-23-7	389
	1.375	3.000	10.375	1016A-23-13	412
	1.875	3.500	11.375	1016A-23-17	441
	2.375	3.500	11.875	1016A-23-23	463
	2.875	4.000	12.875	1016A-23-27	492
	3.375	4.000	13.375	1016A-23-33	514
	3.875	4.000	13.875	1016A-23-37	537
	4.875	4.500	15.375	1016A-23-47	588
	5.875	4.500	16.375	1016A-23-57	633

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	11.375	1016A-37-7	457
	1.375	3.500	12.375	1016A-37-13	485
	1.875	3.500	12.875	1016A-37-17	508
	2.375	4.000	13.875	1016A-37-23	537
	2.875	4.000	14.375	1016A-37-27	559
	3.375	4.000	14.875	1016A-37-33	582
	3.875	4.500	15.875	1016A-37-37	610
	4.875	4.500	16.875	1016A-37-47	655
	5.875	4.500	17.875	1016A-37-57	700

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	8.375	1016A-13-7	338
	1.375	3.000	9.375	1016A-13-13	367
	1.875	3.000	9.875	1016A-13-17	389
	2.375	3.500	10.875	1016A-13-23	418
	2.875	3.500	11.375	1016A-13-27	441
	3.375	4.000	12.375	1016A-13-33	470
	3.875	4.000	12.875	1016A-13-37	492
	4.875	4.500	14.375	1016A-13-47	543
	5.875	4.500	15.375	1016A-13-57	588

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1016A-27-7	412
	1.375	3.000	10.875	1016A-27-13	434
	1.875	3.500	11.875	1016A-27-17	463
	2.375	3.500	12.375	1016A-27-23	485
	2.875	4.000	13.375	1016A-27-27	514
	3.375	4.000	13.875	1016A-27-33	537
	3.875	4.000	14.375	1016A-27-37	559
	4.875	4.500	15.875	1016A-27-47	610
	5.875	4.500	16.875	1016A-27-57	655

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1016A-47-7	508
	1.375	3.500	13.375	1016A-47-13	530
	1.875	4.000	14.375	1016A-47-17	559
	2.375	4.000	14.875	1016A-47-23	582
	2.875	4.000	15.375	1016A-47-27	604
	3.375	4.500	16.375	1016A-47-33	633
	3.875	4.500	16.875	1016A-47-37	655
	4.875	4.500	17.875	1016A-47-47	700
	5.875	4.500	18.875	1016A-47-57	745

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.875	1016A-17-7	361
	1.375	3.000	9.875	1016A-17-13	389
	1.875	3.500	10.875	1016A-17-17	418
	2.375	3.500	11.375	1016A-17-23	441
	2.875	4.000	12.375	1016A-17-27	470
	3.375	4.000	12.875	1016A-17-33	492
	3.875	4.000	13.375	1016A-17-37	514
	4.875	4.500	14.875	1016A-17-47	566
	5.875	4.500	15.875	1016A-17-57	610

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.875	1016A-33-7	434
	1.375	3.500	11.875	1016A-33-13	463
	1.875	3.500	12.375	1016A-33-17	485
	2.375	4.000	13.375	1016A-33-23	514
	2.875	4.000	13.875	1016A-33-27	537
	3.375	4.000	14.375	1016A-33-33	559
	3.875	4.500	15.375	1016A-33-37	588
	4.875	4.500	16.375	1016A-33-47	633
	5.875	4.500	17.375	1016A-33-57	678

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1016A-57-7	553
	1.375	3.500	14.375	1016A-57-13	575
	1.875	4.000	15.375	1016A-57-17	604
	2.375	4.000	15.875	1016A-57-23	626
	2.875	4.000	16.375	1016A-57-27	649
	3.375	4.500	17.375	1016A-57-33	678
	3.875	4.500	17.875	1016A-57-37	700
	4.875	4.500	18.875	1016A-57-47	745
	5.875	4.500	19.875	1016A-57-57	789

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
15.97	16
19.97	20
23.47	23
29.47	29

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

9⁷/₈ x 20" A-Series Mold Bases


See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.



To reinforce Support Plate, use Support Pillars.


Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

9 7/8 x 20" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.875	1020A-7-7	395
	1.375	3.000	8.875	1020A-7-13	431
	1.875	3.000	9.375	1020A-7-17	459
	2.375	3.500	10.375	1020A-7-23	495
	2.875	3.500	10.875	1020A-7-27	523
	3.375	4.000	11.875	1020A-7-33	559
	3.875	4.000	12.375	1020A-7-37	587
	4.875	4.500	13.875	1020A-7-47	651
	5.875	4.500	14.875	1020A-7-57	707

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1020A-23-7	487
	1.375	3.000	10.375	1020A-23-13	515
	1.875	3.500	11.375	1020A-23-17	551
	2.375	3.500	11.875	1020A-23-23	579
	2.875	4.000	12.875	1020A-23-27	615
	3.375	4.000	13.375	1020A-23-33	643
	3.875	4.000	13.875	1020A-23-37	671
	4.875	4.500	15.375	1020A-23-47	735
	5.875	4.500	16.375	1020A-23-57	791

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	11.375	1020A-37-7	571
	1.375	3.500	12.375	1020A-37-13	607
	1.875	3.500	12.875	1020A-37-17	635
	2.375	4.000	13.875	1020A-37-23	671
	2.875	4.000	14.375	1020A-37-27	699
	3.375	4.000	14.875	1020A-37-33	727
	3.875	4.500	15.875	1020A-37-37	763
	4.875	4.500	16.875	1020A-37-47	819
	5.875	4.500	17.875	1020A-37-57	875

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	8.375	1020A-13-7	423
	1.375	3.000	9.375	1020A-13-13	459
	1.875	3.000	9.875	1020A-13-17	487
	2.375	3.500	10.875	1020A-13-23	523
	2.875	3.500	11.375	1020A-13-27	551
	3.375	4.000	12.375	1020A-13-33	587
	3.875	4.000	12.875	1020A-13-37	615
	4.875	4.500	14.375	1020A-13-47	679
	5.875	4.500	15.375	1020A-13-57	735

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1020A-27-7	515
	1.375	3.000	10.875	1020A-27-13	543
	1.875	3.500	11.875	1020A-27-17	579
	2.375	3.500	12.375	1020A-27-23	607
	2.875	4.000	13.375	1020A-27-27	643
	3.375	4.000	13.875	1020A-27-33	671
	3.875	4.000	14.375	1020A-27-37	699
	4.875	4.500	15.875	1020A-27-47	763
	5.875	4.500	16.875	1020A-27-57	819

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1020A-47-7	635
	1.375	3.500	13.375	1020A-47-13	663
	1.875	4.000	14.375	1020A-47-17	699
	2.375	4.000	14.875	1020A-47-23	727
	2.875	4.000	15.375	1020A-47-27	755
	3.375	4.500	16.375	1020A-47-33	791
	3.875	4.500	16.875	1020A-47-37	819
	4.875	4.500	17.875	1020A-47-47	875
	5.875	4.500	18.875	1020A-47-57	931

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.875	1020A-17-7	451
	1.375	3.000	9.875	1020A-17-13	487
	1.875	3.500	10.875	1020A-17-17	523
	2.375	3.500	11.375	1020A-17-23	551
	2.875	4.000	12.375	1020A-17-27	587
	3.375	4.000	12.875	1020A-17-33	615
	3.875	4.000	13.375	1020A-17-37	643
	4.875	4.500	14.875	1020A-17-47	707
	5.875	4.500	15.875	1020A-17-57	763

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.875	1020A-33-7	543
	1.375	3.500	11.875	1020A-33-13	579
	1.875	3.500	12.375	1020A-33-17	607
	2.375	4.000	13.375	1020A-33-23	643
	2.875	4.000	13.875	1020A-33-27	671
	3.375	4.000	14.375	1020A-33-33	699
	3.875	4.500	15.375	1020A-33-37	735
	4.875	4.500	16.375	1020A-33-47	791
	5.875	4.500	17.375	1020A-33-57	847

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1020A-57-7	691
	1.375	3.500	14.375	1020A-57-13	719
	1.875	4.000	15.375	1020A-57-17	755
	2.375	4.000	15.875	1020A-57-23	783
	2.875	4.000	16.375	1020A-57-27	811
	3.375	4.500	17.375	1020A-57-33	847
	3.875	4.500	17.875	1020A-57-37	875
	4.875	4.500	18.875	1020A-57-47	931
	5.875	4.500	19.875	1020A-57-57	987

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
19.97	20
23.47	23
29.47	29

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


10⁷/₈ x 12" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

10⁷/₈ x 12" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.875	1112A-7-7	262
	1.375	3.000	8.875	1112A-7-13	286
	1.875	3.000	9.375	1112A-7-17	305
	2.375	3.500	10.375	1112A-7-23	329
	2.875	3.500	10.875	1112A-7-27	347
	3.375	4.000	11.875	1112A-7-33	372
	3.875	4.000	12.375	1112A-7-37	390
	4.875	4.500	13.875	1112A-7-47	433
	5.875	4.500	14.875	1112A-7-57	470

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1112A-23-7	323
	1.375	3.000	10.375	1112A-23-13	342
	1.875	3.500	11.375	1112A-23-17	366
	2.375	3.500	11.875	1112A-23-23	384
	2.875	4.000	12.875	1112A-23-27	409
	3.375	4.000	13.375	1112A-23-33	427
	3.875	4.000	13.875	1112A-23-37	446
	4.875	4.500	15.375	1112A-23-47	488
	5.875	4.500	16.375	1112A-23-57	525

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	11.375	1112A-37-7	379
	1.375	3.500	12.375	1112A-37-13	403
	1.875	3.500	12.875	1112A-37-17	421
	2.375	4.000	13.875	1112A-37-23	446
	2.875	4.000	14.375	1112A-37-27	464
	3.375	4.000	14.875	1112A-37-33	483
	3.875	4.500	15.875	1112A-37-37	507
	4.875	4.500	16.875	1112A-37-47	544
	5.875	4.500	17.875	1112A-37-57	581

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	8.375	1112A-13-7	281
	1.375	3.000	9.375	1112A-13-13	305
	1.875	3.000	9.875	1112A-13-17	323
	2.375	3.500	10.875	1112A-13-23	347
	2.875	3.500	11.375	1112A-13-27	366
	3.375	4.000	12.375	1112A-13-33	390
	3.875	4.000	12.875	1112A-13-37	409
	4.875	4.500	14.375	1112A-13-47	451
	5.875	4.500	15.375	1112A-13-57	488

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1112A-27-7	342
	1.375	3.000	10.875	1112A-27-13	361
	1.875	3.500	11.875	1112A-27-17	384
	2.375	3.500	12.375	1112A-27-23	403
	2.875	4.000	13.375	1112A-27-27	427
	3.375	4.000	13.875	1112A-27-33	446
	3.875	4.000	14.375	1112A-27-37	464
	4.875	4.500	15.875	1112A-27-47	507
	5.875	4.500	16.875	1112A-27-57	544

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1112A-47-7	421
	1.375	3.500	13.375	1112A-47-13	440
	1.875	4.000	14.375	1112A-47-17	464
	2.375	4.000	14.875	1112A-47-23	483
	2.875	4.000	15.375	1112A-47-27	501
	3.375	4.500	16.375	1112A-47-33	525
	3.875	4.500	16.875	1112A-47-37	544
	4.875	4.500	17.875	1112A-47-47	581
	5.875	4.500	18.875	1112A-47-57	618

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.875	1112A-17-7	299
	1.375	3.000	9.875	1112A-17-13	323
	1.875	3.500	10.875	1112A-17-17	347
	2.375	3.500	11.375	1112A-17-23	366
	2.875	4.000	12.375	1112A-17-27	390
	3.375	4.000	12.875	1112A-17-33	409
	3.875	4.000	13.375	1112A-17-37	427
	4.875	4.500	14.875	1112A-17-47	470
	5.875	4.500	15.875	1112A-17-57	507

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.875	1112A-33-7	360
	1.375	3.500	11.875	1112A-33-13	384
	1.875	3.500	12.375	1112A-33-17	403
	2.375	4.000	13.375	1112A-33-23	427
	2.875	4.000	13.875	1112A-33-27	446
	3.375	4.000	14.375	1112A-33-33	464
	3.875	4.500	15.375	1112A-33-37	488
	4.875	4.500	16.375	1112A-33-47	525
	5.875	4.500	17.375	1112A-33-57	563

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1112A-57-7	458
	1.375	3.500	14.375	1112A-57-13	477
	1.875	4.000	15.375	1112A-57-17	501
	2.375	4.000	15.875	1112A-57-23	520
	2.875	4.000	16.375	1112A-57-27	538
	3.375	4.500	17.375	1112A-57-33	562
	3.875	4.500	17.875	1112A-57-37	581
	4.875	4.500	18.875	1112A-57-47	618
	5.875	4.500	19.875	1112A-57-57	655

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
11.97	12
13.97	14
17.97	18
23.47	23
29.47	29

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed (Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


10⁷/₈ x 14" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

10⁷/₈ x 14" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.875	1114A-7-7	306
	1.375	3.000	8.875	1114A-7-13	334
	1.875	3.000	9.375	1114A-7-17	355
	2.375	3.500	10.375	1114A-7-23	384
	2.875	3.500	10.875	1114A-7-27	405
	3.375	4.000	11.875	1114A-7-33	434
	3.875	4.000	12.375	1114A-7-37	455
	4.875	4.500	13.875	1114A-7-47	505
	5.875	4.500	14.875	1114A-7-57	548

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1114A-23-7	377
	1.375	3.000	10.375	1114A-23-13	399
	1.875	3.500	11.375	1114A-23-17	427
	2.375	3.500	11.875	1114A-23-23	448
	2.875	4.000	12.875	1114A-23-27	477
	3.375	4.000	13.375	1114A-23-33	498
	3.875	4.000	13.875	1114A-23-37	520
	4.875	4.500	15.375	1114A-23-47	570
	5.875	4.500	16.375	1114A-23-57	613

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	11.375	1114A-37-7	442
	1.375	3.500	12.375	1114A-37-13	470
	1.875	3.500	12.875	1114A-37-17	492
	2.375	4.000	13.875	1114A-37-23	520
	2.875	4.000	14.375	1114A-37-27	541
	3.375	4.000	14.875	1114A-37-33	563
	3.875	4.500	15.875	1114A-37-37	591
	4.875	4.500	16.875	1114A-37-47	634
	5.875	4.500	17.875	1114A-37-57	678

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	8.375	1114A-13-7	327
	1.375	3.000	9.375	1114A-13-13	355
	1.875	3.000	9.875	1114A-13-17	377
	2.375	3.500	10.875	1114A-13-23	405
	2.875	3.500	11.375	1114A-13-27	427
	3.375	4.000	12.375	1114A-13-33	455
	3.875	4.000	12.875	1114A-13-37	477
	4.875	4.500	14.375	1114A-13-47	527
	5.875	4.500	15.375	1114A-13-57	570

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1114A-27-7	399
	1.375	3.000	10.875	1114A-27-13	420
	1.875	3.500	11.875	1114A-27-17	448
	2.375	3.500	12.375	1114A-27-23	470
	2.875	4.000	13.375	1114A-27-27	498
	3.375	4.000	13.875	1114A-27-33	520
	3.875	4.000	14.375	1114A-27-37	541
	4.875	4.500	15.875	1114A-27-47	591
	5.875	4.500	16.875	1114A-27-57	634

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1114A-47-7	492
	1.375	3.500	13.375	1114A-47-13	513
	1.875	4.000	14.375	1114A-47-17	541
	2.375	4.000	14.875	1114A-47-23	563
	2.875	4.000	15.375	1114A-47-27	585
	3.375	4.500	16.375	1114A-47-33	613
	3.875	4.500	16.875	1114A-47-37	634
	4.875	4.500	17.875	1114A-47-47	678
	5.875	4.500	18.875	1114A-47-57	721

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.875	1114A-17-7	349
	1.375	3.000	9.875	1114A-17-13	377
	1.875	3.500	10.875	1114A-17-17	405
	2.375	3.500	11.375	1114A-17-23	427
	2.875	4.000	12.375	1114A-17-27	455
	3.375	4.000	12.875	1114A-17-33	477
	3.875	4.000	13.375	1114A-17-37	498
	4.875	4.500	14.875	1114A-17-47	548
	5.875	4.500	15.875	1114A-17-57	591

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.875	1114A-33-7	420
	1.375	3.500	11.875	1114A-33-13	448
	1.875	3.500	12.375	1114A-33-17	470
	2.375	4.000	13.375	1114A-33-23	498
	2.875	4.000	13.875	1114A-33-27	520
	3.375	4.000	14.375	1114A-33-33	542
	3.875	4.500	15.375	1114A-33-37	570
	4.875	4.500	16.375	1114A-33-47	613
	5.875	4.500	17.375	1114A-33-57	656

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1114A-57-7	535
	1.375	3.500	14.375	1114A-57-13	556
	1.875	4.000	15.375	1114A-57-17	585
	2.375	4.000	15.875	1114A-57-23	606
	2.875	4.000	16.375	1114A-57-27	628
	3.375	4.500	17.375	1114A-57-33	656
	3.875	4.500	17.875	1114A-57-37	678
	4.875	4.500	18.875	1114A-57-47	721
	5.875	4.500	19.875	1114A-57-57	764

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
13.97	14
17.97	18
23.47	23
29.47	29

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


10⁷/₈ x 18" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

10⁷/₈ x 18" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	2.500	7.875	1118A-7-7	393
	1.375	3.000	8.875	1118A-7-13	429
	1.875	3.000	9.375	1118A-7-17	457
	2.375	3.500	10.375	1118A-7-23	493
	2.875	3.500	10.875	1118A-7-27	521
	3.375	4.000	11.875	1118A-7-33	557
	3.875	4.000	12.375	1118A-7-37	585
	4.875	4.500	13.875	1118A-7-47	649
	5.875	4.500	14.875	1118A-7-57	705

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1118A-23-7	485
	1.375	3.000	10.375	1118A-23-13	513
	1.875	3.500	11.375	1118A-23-17	549
	2.375	3.500	11.875	1118A-23-23	576
	2.875	4.000	12.875	1118A-23-27	613
	3.375	4.000	13.375	1118A-23-33	641
	3.875	4.000	13.875	1118A-23-37	668
	4.875	4.500	15.375	1118A-23-47	732
	5.875	4.500	16.375	1118A-23-57	788

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.000	11.375	1118A-37-7	568
	1.375	3.500	12.375	1118A-37-13	604
	1.875	3.500	12.875	1118A-37-17	632
	2.375	4.000	13.875	1118A-37-23	668
	2.875	4.000	14.375	1118A-37-27	696
	3.375	4.000	14.875	1118A-37-33	724
	3.875	4.500	15.875	1118A-37-37	760
	4.875	4.500	16.875	1118A-37-47	816
	5.875	4.500	17.875	1118A-37-57	871

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	2.500	8.375	1118A-13-7	421
	1.375	3.000	9.375	1118A-13-13	457
	1.875	3.000	9.875	1118A-13-17	485
	2.375	3.500	10.875	1118A-13-23	521
	2.875	3.500	11.375	1118A-13-27	549
	3.375	4.000	12.375	1118A-13-33	585
	3.875	4.000	12.875	1118A-13-37	613
	4.875	4.500	14.375	1118A-13-47	677
	5.875	4.500	15.375	1118A-13-57	732

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1118A-27-7	512
	1.375	3.000	10.875	1118A-27-13	540
	1.875	3.500	11.875	1118A-27-17	576
	2.375	3.500	12.375	1118A-27-23	604
	2.875	4.000	13.375	1118A-27-27	641
	3.375	4.000	13.875	1118A-27-33	668
	3.875	4.000	14.375	1118A-27-37	696
	4.875	4.500	15.875	1118A-27-47	760
	5.875	4.500	16.875	1118A-27-57	816

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1118A-47-7	632
	1.375	3.500	13.375	1118A-47-13	660
	1.875	4.000	14.375	1118A-47-17	696
	2.375	4.000	14.875	1118A-47-23	724
	2.875	4.000	15.375	1118A-47-27	751
	3.375	4.500	16.375	1118A-47-33	788
	3.875	4.500	16.875	1118A-47-37	816
	4.875	4.500	17.875	1118A-47-47	871
	5.875	4.500	18.875	1118A-47-57	926

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	2.500	8.875	1118A-17-7	448
	1.375	3.000	9.875	1118A-17-13	485
	1.875	3.500	10.875	1118A-17-17	521
	2.375	3.500	11.375	1118A-17-23	549
	2.875	4.000	12.375	1118A-17-27	585
	3.375	4.000	12.875	1118A-17-33	613
	3.875	4.000	13.375	1118A-17-37	641
	4.875	4.500	14.875	1118A-17-47	705
	5.875	4.500	15.875	1118A-17-57	760

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.000	10.875	1118A-33-7	540
	1.375	3.500	11.875	1118A-33-13	576
	1.875	3.500	12.375	1118A-33-17	604
	2.375	4.000	13.375	1118A-33-23	641
	2.875	4.000	13.875	1118A-33-27	668
	3.375	4.000	14.375	1118A-33-33	696
	3.875	4.500	15.375	1118A-33-37	732
	4.875	4.500	16.375	1118A-33-47	788
	5.875	4.500	17.375	1118A-33-57	843

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1118A-57-7	687
	1.375	3.500	14.375	1118A-57-13	715
	1.875	4.000	15.375	1118A-57-17	751
	2.375	4.000	15.875	1118A-57-23	779
	2.875	4.000	16.375	1118A-57-27	807
	3.375	4.500	17.375	1118A-57-33	843
	3.875	4.500	17.875	1118A-57-37	871
	4.875	4.500	18.875	1118A-57-47	926
	5.875	4.500	19.875	1118A-57-57	982

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
2.500	25	0.813
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
17.97	18
23.47	23
29.47	29

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


10⁷/₈ x 23¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

10⁷/₈ x 23¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	9.375	1123A-13-13	596
	1.875	3.000	9.875	1123A-13-17	633
	2.375	3.500	10.875	1123A-13-23	680
	2.875	3.500	11.375	1123A-13-27	716
	3.375	4.000	12.375	1123A-13-33	764
	3.875	4.000	12.875	1123A-13-37	800
	4.875	4.500	14.375	1123A-13-47	883
	5.875	4.500	15.375	1123A-13-57	956

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.000	10.875	1123A-27-13	705
	1.875	3.500	11.875	1123A-27-17	752
	2.375	3.500	12.375	1123A-27-23	789
	2.875	4.000	13.375	1123A-27-27	836
	3.375	4.000	13.875	1123A-27-33	872
	3.875	4.000	14.375	1123A-27-37	908
	4.875	4.500	15.875	1123A-27-47	992
	5.875	4.500	16.875	1123A-27-57	1063

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	3.500	13.375	1123A-47-13	861
	1.875	4.000	14.375	1123A-47-17	908
	2.375	4.000	14.875	1123A-47-23	945
	2.875	4.000	15.375	1123A-47-27	981
	3.375	4.500	16.375	1123A-47-33	1028
	3.875	4.500	16.875	1123A-47-37	1064
	4.875	4.500	17.875	1123A-47-47	1137
	5.875	4.500	18.875	1123A-47-57	1209

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	9.875	1123A-17-13	633
	1.875	3.500	10.875	1123A-17-17	680
	2.375	3.500	11.375	1123A-17-23	716
	2.875	4.000	12.375	1123A-17-27	764
	3.375	4.000	12.875	1123A-17-33	800
	3.875	4.000	13.375	1123A-17-37	836
	4.875	4.500	14.875	1123A-17-47	920
	5.875	4.500	15.875	1123A-17-57	992

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	3.500	11.875	1123A-33-13	752
	1.875	3.500	12.375	1123A-33-17	789
	2.375	4.000	13.375	1123A-33-23	836
	2.875	4.000	13.875	1123A-33-27	872
	3.375	4.000	14.375	1123A-33-33	908
	3.875	4.500	15.375	1123A-33-37	956
	4.875	4.500	16.375	1123A-33-47	1028
	5.875	4.500	17.375	1123A-33-57	1101

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	3.500	14.375	1123A-57-13	933
	1.875	4.000	15.375	1123A-57-17	981
	2.375	4.000	15.875	1123A-57-23	1017
	2.875	4.000	16.375	1123A-57-27	1053
	3.375	4.500	17.375	1123A-57-33	1101
	3.875	4.500	17.875	1123A-57-37	1137
	4.875	4.500	18.875	1123A-57-47	1209
	5.875	4.500	19.875	1123A-57-57	1282

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.000	10.375	1123A-23-13	669
	1.875	3.500	11.375	1123A-23-17	716
	2.375	3.500	11.875	1123A-23-23	752
	2.875	4.000	12.875	1123A-23-27	800
	3.375	4.000	13.375	1123A-23-33	836
	3.875	4.000	13.875	1123A-23-37	872
	4.875	4.500	15.375	1123A-23-47	956
	5.875	4.500	16.375	1123A-23-57	1028

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	3.500	12.375	1123A-37-13	789
	1.875	3.500	12.875	1123A-37-17	825
	2.375	4.000	13.875	1123A-37-23	872
	2.875	4.000	14.375	1123A-37-27	908
	3.375	4.000	14.875	1123A-37-33	945
	3.875	4.500	15.875	1123A-37-37	992
	4.875	4.500	16.875	1123A-37-47	1064
	5.875	4.500	17.875	1123A-37-57	1137

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.313
3.500	35	1.813
4.000	40	2.313
4.500	45	2.813
5.000	50	3.313
5.500	55	3.813
6.000	60	4.313

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.47	23
29.47	29

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

11⁷/₈ x 12" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series
and T-Series Mold Bases, see pages 173-198.)

**Steel
Configurations
available in:**



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

11⁷/₈ x 12" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	8.375	1212A-7-7	295
	1.375	3.000	8.875	1212A-7-13	315
	1.875	3.000	9.375	1212A-7-17	335
	2.375	3.500	10.375	1212A-7-23	361
	2.875	3.500	10.875	1212A-7-27	381
	3.375	4.000	11.875	1212A-7-33	407
	3.875	4.000	12.375	1212A-7-37	427
	4.875	4.500	13.875	1212A-7-47	473
	5.875	4.500	14.875	1212A-7-57	514

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1212A-23-7	355
	1.375	3.500	10.875	1212A-23-13	381
	1.875	3.500	11.375	1212A-23-17	401
	2.375	3.500	11.875	1212A-23-23	422
	2.875	4.000	12.875	1212A-23-27	448
	3.375	4.000	13.375	1212A-23-33	468
	3.875	4.000	13.875	1212A-23-37	488
	4.875	4.500	15.375	1212A-23-47	534
	5.875	4.500	16.375	1212A-23-57	574

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	11.875	1212A-37-7	422
	1.375	3.500	12.375	1212A-37-13	442
	1.875	4.000	13.375	1212A-37-17	468
	2.375	4.500	14.375	1212A-37-23	494
	2.875	4.500	14.875	1212A-37-27	514
	3.375	4.500	15.375	1212A-37-33	534
	3.875	4.500	15.875	1212A-37-37	554
	4.875	4.500	16.875	1212A-37-47	595
	5.875	4.500	17.875	1212A-37-57	635

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	8.875	1212A-13-7	315
	1.375	3.000	9.375	1212A-13-13	335
	1.875	3.000	9.875	1212A-13-17	355
	2.375	3.500	10.875	1212A-13-23	381
	2.875	3.500	11.375	1212A-13-27	401
	3.375	4.000	12.375	1212A-13-33	427
	3.875	4.000	12.875	1212A-13-37	448
	4.875	4.500	14.375	1212A-13-47	494
	5.875	4.500	15.375	1212A-13-57	534

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1212A-27-7	375
	1.375	3.500	11.375	1212A-27-13	401
	1.875	3.500	11.875	1212A-27-17	422
	2.375	3.500	12.375	1212A-27-23	442
	2.875	4.000	13.375	1212A-27-27	468
	3.375	4.000	13.875	1212A-27-33	488
	3.875	4.000	14.375	1212A-27-37	508
	4.875	4.500	15.875	1212A-27-47	554
	5.875	4.500	16.875	1212A-27-57	595

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1212A-47-7	462
	1.375	3.500	13.375	1212A-47-13	482
	1.875	4.000	14.375	1212A-47-17	508
	2.375	4.500	15.375	1212A-47-23	534
	2.875	4.500	15.875	1212A-47-27	554
	3.375	4.500	16.375	1212A-47-33	574
	3.875	4.500	16.875	1212A-47-37	595
	4.875	4.500	17.875	1212A-47-47	635
	5.875	4.500	18.875	1212A-47-57	675

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	9.375	1212A-17-7	335
	1.375	3.000	9.875	1212A-17-13	355
	1.875	3.000	10.375	1212A-17-17	375
	2.375	3.500	11.375	1212A-17-23	401
	2.875	3.500	11.875	1212A-17-27	422
	3.375	4.000	12.875	1212A-17-33	448
	3.875	4.000	13.375	1212A-17-37	468
	4.875	4.500	14.875	1212A-17-47	514
	5.875	4.500	15.875	1212A-17-57	554

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	11.375	1212A-33-7	401
	1.375	3.500	11.875	1212A-33-13	422
	1.875	3.500	12.375	1212A-33-17	442
	2.375	4.000	13.375	1212A-33-23	468
	2.875	4.000	13.875	1212A-33-27	488
	3.375	4.500	14.875	1212A-33-33	514
	3.875	4.500	15.375	1212A-33-37	534
	4.875	4.500	16.375	1212A-33-47	574
	5.875	4.500	17.375	1212A-33-57	615

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1212A-57-7	502
	1.375	4.000	14.875	1212A-57-13	528
	1.875	4.500	15.875	1212A-57-17	554
	2.375	4.500	16.375	1212A-57-23	574
	2.875	4.500	16.875	1212A-57-27	595
	3.375	4.500	17.375	1212A-57-33	615
	3.875	4.500	17.875	1212A-57-37	635
	4.875	4.500	18.875	1212A-57-47	675
	5.875	4.500	19.875	1212A-57-57	716

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.188
3.500	35	1.688
4.000	40	2.188
4.500	45	2.688
5.000	50	3.188
5.500	55	3.688
6.000	60	4.188

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
11.97	12
14.97	15
19.97	20
23.47	23
29.47	29

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.




WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

11⁷/₈ x 15" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




All dimensions are "Nominal" unless a tolerance is specified.



To reinforce Support Plate, use Support Pillars.


Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

11⁷/₈ x 15" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	8.375	1215A-7-7	368
	1.375	3.000	8.875	1215A-7-13	393
	1.875	3.000	9.375	1215A-7-17	419
	2.375	3.500	10.375	1215A-7-23	451
	2.875	3.500	10.875	1215A-7-27	476
	3.375	4.000	11.875	1215A-7-33	509
	3.875	4.000	12.375	1215A-7-37	534
	4.875	4.500	13.875	1215A-7-47	592
	5.875	4.500	14.875	1215A-7-57	642

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1215A-23-7	444
	1.375	3.500	10.875	1215A-23-13	476
	1.875	3.500	11.375	1215A-23-17	502
	2.375	3.500	11.875	1215A-23-23	527
	2.875	4.000	12.875	1215A-23-27	559
	3.375	4.000	13.375	1215A-23-33	584
	3.875	4.000	13.875	1215A-23-37	610
	4.875	4.500	15.375	1215A-23-47	667
	5.875	4.500	16.375	1215A-23-57	718

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	11.875	1215A-37-7	527
	1.375	3.500	12.375	1215A-37-13	552
	1.875	4.000	13.375	1215A-37-17	584
	2.375	4.500	14.375	1215A-37-23	617
	2.875	4.500	14.875	1215A-37-27	642
	3.375	4.500	15.375	1215A-37-33	667
	3.875	4.500	15.875	1215A-37-37	692
	4.875	4.500	16.875	1215A-37-47	743
	5.875	4.500	17.875	1215A-37-57	793

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	8.875	1215A-13-7	393
	1.375	3.000	9.375	1215A-13-13	419
	1.875	3.000	9.875	1215A-13-17	444
	2.375	3.500	10.875	1215A-13-23	476
	2.875	3.500	11.375	1215A-13-27	502
	3.375	4.000	12.375	1215A-13-33	534
	3.875	4.000	12.875	1215A-13-37	559
	4.875	4.500	14.375	1215A-13-47	617
	5.875	4.500	15.375	1215A-13-57	667

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1215A-27-7	469
	1.375	3.500	11.375	1215A-27-13	502
	1.875	3.500	11.875	1215A-27-17	527
	2.375	3.500	12.375	1215A-27-23	552
	2.875	4.000	13.375	1215A-27-27	584
	3.375	4.000	13.875	1215A-27-33	610
	3.875	4.000	14.375	1215A-27-37	635
	4.875	4.500	15.875	1215A-27-47	692
	5.875	4.500	16.875	1215A-27-57	743

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1215A-47-7	577
	1.375	3.500	13.375	1215A-47-13	602
	1.875	4.000	14.375	1215A-47-17	635
	2.375	4.500	15.375	1215A-47-23	667
	2.875	4.500	15.875	1215A-47-27	692
	3.375	4.500	16.375	1215A-47-33	718
	3.875	4.500	16.875	1215A-47-37	743
	4.875	4.500	17.875	1215A-47-47	793
	5.875	4.500	18.875	1215A-47-57	844

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	9.375	1215A-17-7	419
	1.375	3.000	9.875	1215A-17-13	444
	1.875	3.000	10.375	1215A-17-17	469
	2.375	3.500	11.375	1215A-17-23	502
	2.875	3.500	11.875	1215A-17-27	527
	3.375	4.000	12.875	1215A-17-33	559
	3.875	4.000	13.375	1215A-17-37	584
	4.875	4.500	14.875	1215A-17-47	642
	5.875	4.500	15.875	1215A-17-57	692

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	11.375	1215A-33-7	502
	1.375	3.500	11.875	1215A-33-13	527
	1.875	3.500	12.375	1215A-33-17	552
	2.375	4.000	13.375	1215A-33-23	584
	2.875	4.000	13.875	1215A-33-27	610
	3.375	4.500	14.875	1215A-33-33	642
	3.875	4.500	15.375	1215A-33-37	667
	4.875	4.500	16.375	1215A-33-47	718
	5.875	4.500	17.375	1215A-33-57	768

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1215A-57-7	628
	1.375	4.000	14.875	1215A-57-13	660
	1.875	4.500	15.875	1215A-57-17	692
	2.375	4.500	16.375	1215A-57-23	718
	2.875	4.500	16.875	1215A-57-27	743
	3.375	4.500	17.375	1215A-57-33	768
	3.875	4.500	17.875	1215A-57-37	793
	4.875	4.500	18.875	1215A-57-47	844
	5.875	4.500	19.875	1215A-57-57	894

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.188
3.500	35	1.688
4.000	40	2.188
4.500	45	2.688
5.000	50	3.188
5.500	55	3.688
6.000	60	4.188

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
14.97	15
19.97	20
23.47	23
29.47	29

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


11⁷/₈ x 20" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

11⁷/₈ x 20" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	8.375	1220A-7-7	491
	1.375	3.000	8.875	1220A-7-13	525
	1.875	3.000	9.375	1220A-7-17	558
	2.375	3.500	10.375	1220A-7-23	601
	2.875	3.500	10.875	1220A-7-27	635
	3.375	4.000	11.875	1220A-7-33	678
	3.875	4.000	12.375	1220A-7-37	712
	4.875	4.500	13.875	1220A-7-47	788
	5.875	4.500	14.875	1220A-7-57	856

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	9.875	1220A-23-7	592
	1.375	3.500	10.875	1220A-23-13	635
	1.875	3.500	11.375	1220A-23-17	669
	2.375	3.500	11.875	1220A-23-23	702
	2.875	4.000	12.875	1220A-23-27	746
	3.375	4.000	13.375	1220A-23-33	779
	3.875	4.000	13.875	1220A-23-37	813
	4.875	4.500	15.375	1220A-23-47	890
	5.875	4.500	16.375	1220A-23-57	957

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	11.875	1220A-37-7	702
	1.375	3.500	12.375	1220A-37-13	736
	1.875	4.000	13.375	1220A-37-17	779
	2.375	4.500	14.375	1220A-37-23	822
	2.875	4.500	14.875	1220A-37-27	856
	3.375	4.500	15.375	1220A-37-33	890
	3.875	4.500	15.875	1220A-37-37	923
	4.875	4.500	16.875	1220A-37-47	991
	5.875	4.500	17.875	1220A-37-57	1058

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	8.875	1220A-13-7	525
	1.375	3.000	9.375	1220A-13-13	558
	1.875	3.000	9.875	1220A-13-17	592
	2.375	3.500	10.875	1220A-13-23	635
	2.875	3.500	11.375	1220A-13-27	669
	3.375	4.000	12.375	1220A-13-33	712
	3.875	4.000	12.875	1220A-13-37	746
	4.875	4.500	14.375	1220A-13-47	822
	5.875	4.500	15.375	1220A-13-57	890

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.375	1220A-27-7	625
	1.375	3.500	11.375	1220A-27-13	669
	1.875	3.500	11.875	1220A-27-17	702
	2.375	3.500	12.375	1220A-27-23	736
	2.875	4.000	13.375	1220A-27-27	779
	3.375	4.000	13.875	1220A-27-33	813
	3.875	4.000	14.375	1220A-27-37	846
	4.875	4.500	15.875	1220A-27-47	923
	5.875	4.500	16.875	1220A-27-57	991

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	12.875	1220A-47-7	770
	1.375	3.500	13.375	1220A-47-13	803
	1.875	4.000	14.375	1220A-47-17	846
	2.375	4.500	15.375	1220A-47-23	890
	2.875	4.500	15.875	1220A-47-27	923
	3.375	4.500	16.375	1220A-47-33	957
	3.875	4.500	16.875	1220A-47-37	991
	4.875	4.500	17.875	1220A-47-47	1058
	5.875	4.500	18.875	1220A-47-57	1125

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	9.375	1220A-17-7	558
	1.375	3.000	9.875	1220A-17-13	592
	1.875	3.000	10.375	1220A-17-17	625
	2.375	3.500	11.375	1220A-17-23	669
	2.875	3.500	11.875	1220A-17-27	702
	3.375	4.000	12.875	1220A-17-33	746
	3.875	4.000	13.375	1220A-17-37	779
	4.875	4.500	14.875	1220A-17-47	856
	5.875	4.500	15.875	1220A-17-57	923

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	11.375	1220A-33-7	669
	1.375	3.500	11.875	1220A-33-13	702
	1.875	3.500	12.375	1220A-33-17	736
	2.375	4.000	13.375	1220A-33-23	779
	2.875	4.000	13.875	1220A-33-27	813
	3.375	4.500	14.875	1220A-33-33	856
	3.875	4.500	15.375	1220A-33-37	890
	4.875	4.500	16.375	1220A-33-47	957
	5.875	4.500	17.375	1220A-33-57	1024

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	13.875	1220A-57-7	837
	1.375	4.000	14.875	1220A-57-13	880
	1.875	4.500	15.875	1220A-57-17	923
	2.375	4.500	16.375	1220A-57-23	957
	2.875	4.500	16.875	1220A-57-27	991
	3.375	4.500	17.375	1220A-57-33	1024
	3.875	4.500	17.875	1220A-57-37	1058
	4.875	4.500	18.875	1220A-57-47	1125
	5.875	4.500	19.875	1220A-57-57	1192

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.188
3.500	35	1.688
4.000	40	2.188
4.500	45	2.688
5.000	50	3.188
5.500	55	3.688
6.000	60	4.188

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
19.97	20
23.47	23
29.47	29

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

11⁷/₈ x 23¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

11⁷/₈ x 23¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	9.375	1223A-13-13	656
	1.875	3.000	9.875	1223A-13-17	695
	2.375	3.500	10.875	1223A-13-23	746
	2.875	3.500	11.375	1223A-13-27	786
	3.375	4.000	12.375	1223A-13-33	836
	3.875	4.000	12.875	1223A-13-37	876
	4.875	4.500	14.375	1223A-13-47	966
	5.875	4.500	15.375	1223A-13-57	1045

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	11.375	1223A-27-13	786
	1.875	3.500	11.875	1223A-27-17	825
	2.375	3.500	12.375	1223A-27-23	865
	2.875	4.000	13.375	1223A-27-27	915
	3.375	4.000	13.875	1223A-27-33	955
	3.875	4.000	14.375	1223A-27-37	994
	4.875	4.500	15.875	1223A-27-47	1085
	5.875	4.500	16.875	1223A-27-57	1164

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	3.500	13.375	1223A-47-13	944
	1.875	4.000	14.375	1223A-47-17	994
	2.375	4.500	15.375	1223A-47-23	1045
	2.875	4.500	15.875	1223A-47-27	1085
	3.375	4.500	16.375	1223A-47-33	1124
	3.875	4.500	16.875	1223A-47-37	1164
	4.875	4.500	17.875	1223A-47-47	1243
	5.875	4.500	18.875	1223A-47-57	1322

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	9.875	1223A-17-13	696
	1.875	3.000	10.375	1223A-17-17	735
	2.375	3.500	11.375	1223A-17-23	786
	2.875	3.500	11.875	1223A-17-27	825
	3.375	4.000	12.875	1223A-17-33	876
	3.875	4.000	13.375	1223A-17-37	915
	4.875	4.500	14.875	1223A-17-47	1006
	5.875	4.500	15.875	1223A-17-57	1085

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	3.500	11.875	1223A-33-13	825
	1.875	3.500	12.375	1223A-33-17	865
	2.375	4.000	13.375	1223A-33-23	915
	2.875	4.000	13.875	1223A-33-27	955
	3.375	4.500	14.875	1223A-33-33	1006
	3.875	4.500	15.375	1223A-33-37	1045
	4.875	4.500	16.375	1223A-33-47	1124
	5.875	4.500	17.375	1223A-33-57	1203

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	14.875	1223A-57-13	1034
	1.875	4.500	15.875	1223A-57-17	1085
	2.375	4.500	16.375	1223A-57-23	1124
	2.875	4.500	16.875	1223A-57-27	1164
	3.375	4.500	17.375	1223A-57-33	1203
	3.875	4.500	17.875	1223A-57-37	1243
	4.875	4.500	18.875	1223A-57-47	1322
	5.875	4.500	19.875	1223A-57-57	1401

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	10.875	1223A-23-13	746
	1.875	3.500	11.375	1223A-23-17	786
	2.375	3.500	11.875	1223A-23-23	825
	2.875	4.000	12.875	1223A-23-27	876
	3.375	4.000	13.375	1223A-23-33	915
	3.875	4.000	13.875	1223A-23-37	955
	4.875	4.500	15.375	1223A-23-47	1045
	5.875	4.500	16.375	1223A-23-57	1124

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	3.500	12.375	1223A-37-13	865
	1.875	4.000	13.375	1223A-37-17	915
	2.375	4.500	14.375	1223A-37-23	966
	2.875	4.500	14.875	1223A-37-27	1006
	3.375	4.500	15.375	1223A-37-33	1045
	3.875	4.500	15.875	1223A-37-37	1085
	4.875	4.500	16.875	1223A-37-47	1164
	5.875	4.500	17.875	1223A-37-57	1243

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.188
3.500	35	1.688
4.000	40	2.188
4.500	45	2.688
5.000	50	3.188
5.500	55	3.688
6.000	60	4.188

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.47	23
29.47	29

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


13³/₈ x 15" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

13³/₈ x 15" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	8.875	1315A-7-7	449
	1.375	3.000	9.375	1315A-7-13	477
	1.875	3.000	9.875	1315A-7-17	505
	2.375	3.500	10.875	1315A-7-23	542
	2.875	3.500	11.375	1315A-7-27	570
	3.375	4.000	12.375	1315A-7-33	607
	3.875	4.000	12.875	1315A-7-37	635
	4.875	4.500	14.375	1315A-7-47	700
	5.875	4.500	15.375	1315A-7-57	757

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	10.375	1315A-23-7	534
	1.375	3.500	11.375	1315A-23-13	570
	1.875	3.500	11.875	1315A-23-17	599
	2.375	3.500	12.375	1315A-23-23	627
	2.875	4.000	13.375	1315A-23-27	663
	3.375	4.000	13.875	1315A-23-33	692
	3.875	4.000	14.375	1315A-23-37	720
	4.875	4.500	15.875	1315A-23-47	785
	5.875	4.500	16.875	1315A-23-57	842

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	12.375	1315A-37-7	627
	1.375	3.500	12.875	1315A-37-13	655
	1.875	4.000	13.875	1315A-37-17	692
	2.375	4.500	14.875	1315A-37-23	728
	2.875	4.500	15.375	1315A-37-27	757
	3.375	4.500	15.875	1315A-37-33	785
	3.875	4.500	16.375	1315A-37-37	813
	4.875	4.500	17.375	1315A-37-47	870
	5.875	4.500	18.375	1315A-37-57	927

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	9.375	1315A-13-7	477
	1.375	3.000	9.875	1315A-13-13	505
	1.875	3.000	10.375	1315A-13-17	534
	2.375	3.500	11.375	1315A-13-23	570
	2.875	3.500	11.875	1315A-13-27	599
	3.375	4.000	12.875	1315A-13-33	635
	3.875	4.000	13.375	1315A-13-37	663
	4.875	4.500	14.875	1315A-13-47	728
	5.875	4.500	15.875	1315A-13-57	785

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.875	1315A-27-7	562
	1.375	3.500	11.875	1315A-27-13	599
	1.875	3.500	12.375	1315A-27-17	627
	2.375	3.500	12.875	1315A-27-23	655
	2.875	4.000	13.875	1315A-27-27	692
	3.375	4.000	14.375	1315A-27-33	720
	3.875	4.000	14.875	1315A-27-37	749
	4.875	4.500	16.375	1315A-27-47	813
	5.875	4.500	17.375	1315A-27-57	870

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	13.375	1315A-47-7	684
	1.375	3.500	13.875	1315A-47-13	712
	1.875	4.000	14.875	1315A-47-17	749
	2.375	4.500	15.875	1315A-47-23	785
	2.875	4.500	16.375	1315A-47-27	813
	3.375	4.500	16.875	1315A-47-33	842
	3.875	4.500	17.375	1315A-47-37	870
	4.875	4.500	18.375	1315A-47-47	927
	5.875	4.500	19.375	1315A-47-57	984

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	9.875	1315A-17-7	505
	1.375	3.000	10.375	1315A-17-13	534
	1.875	3.000	10.875	1315A-17-17	562
	2.375	3.500	11.875	1315A-17-23	599
	2.875	3.500	12.375	1315A-17-27	627
	3.375	4.000	13.375	1315A-17-33	663
	3.875	4.000	13.875	1315A-17-37	692
	4.875	4.500	15.375	1315A-17-47	757
	5.875	4.500	16.375	1315A-17-57	813

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	11.875	1315A-33-7	599
	1.375	3.500	12.375	1315A-33-13	627
	1.875	3.500	12.875	1315A-33-17	655
	2.375	4.000	13.875	1315A-33-23	692
	2.875	4.000	14.375	1315A-33-27	720
	3.375	4.500	15.375	1315A-33-33	757
	3.875	4.500	15.875	1315A-33-37	785
	4.875	4.500	16.875	1315A-33-47	842
	5.875	4.500	17.875	1315A-33-57	899

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	14.375	1315A-57-7	741
	1.375	4.000	15.375	1315A-57-13	777
	1.875	4.500	16.375	1315A-57-17	813
	2.375	4.500	16.875	1315A-57-23	842
	2.875	4.500	17.375	1315A-57-27	870
	3.375	4.500	17.875	1315A-57-33	899
	3.875	4.500	18.375	1315A-57-37	927
	4.875	4.500	19.375	1315A-57-47	984
	5.875	4.500	20.375	1315A-57-57	1041

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER			EB EJECTOR BAR	
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR	E LENGTH NOM.	EJECTOR BAR LENGTH NO.
3.000	30	1.063	14.97	15
3.500	35	1.563	17.97	18
4.000	40	2.063	20.72	21
4.500	45	2.563	23.47	23
5.000	50	3.063	25.97	26
5.500	55	3.563	29.47	29
6.000	60	4.063	35.47	35

See Item 8 below.

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


13³/₈ x 18" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

13³/₈ x 18" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	8.875	1318A-7-7	538
	1.375	3.000	9.375	1318A-7-13	572
	1.875	3.000	9.875	1318A-7-17	606
	2.375	3.500	10.875	1318A-7-23	650
	2.875	3.500	11.375	1318A-7-27	684
	3.375	4.000	12.375	1318A-7-33	728
	3.875	4.000	12.875	1318A-7-37	762
	4.875	4.500	14.375	1318A-7-47	840
	5.875	4.500	15.375	1318A-7-57	908

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	10.375	1318A-23-7	640
	1.375	3.500	11.375	1318A-23-13	684
	1.875	3.500	11.875	1318A-23-17	718
	2.375	3.500	12.375	1318A-23-23	752
	2.875	4.000	13.375	1318A-23-27	796
	3.375	4.000	13.875	1318A-23-33	830
	3.875	4.000	14.375	1318A-23-37	864
	4.875	4.500	15.875	1318A-23-47	942
	5.875	4.500	16.875	1318A-23-57	1010

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	12.375	1318A-37-7	752
	1.375	3.500	12.875	1318A-37-13	786
	1.875	4.000	13.875	1318A-37-17	830
	2.375	4.500	14.875	1318A-37-23	874
	2.875	4.500	15.375	1318A-37-27	908
	3.375	4.500	15.875	1318A-37-33	942
	3.875	4.500	16.375	1318A-37-37	976
	4.875	4.500	17.375	1318A-37-47	1044
	5.875	4.500	18.375	1318A-37-57	1112

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	9.375	1318A-13-7	572
	1.375	3.000	9.875	1318A-13-13	606
	1.875	3.000	10.375	1318A-13-17	640
	2.375	3.500	11.375	1318A-13-23	684
	2.875	3.500	11.875	1318A-13-27	718
	3.375	4.000	12.875	1318A-13-33	762
	3.875	4.000	13.375	1318A-13-37	796
	4.875	4.500	14.875	1318A-13-47	874
	5.875	4.500	15.875	1318A-13-57	942

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.875	1318A-27-7	675
	1.375	3.500	11.875	1318A-27-13	718
	1.875	3.500	12.375	1318A-27-17	752
	2.375	3.500	12.875	1318A-27-23	786
	2.875	4.000	13.875	1318A-27-27	830
	3.375	4.000	14.375	1318A-27-33	864
	3.875	4.000	14.875	1318A-27-37	898
	4.875	4.500	16.375	1318A-27-47	976
	5.875	4.500	17.375	1318A-27-57	1044

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	13.375	1318A-47-7	821
	1.375	3.500	13.875	1318A-47-13	855
	1.875	4.000	14.875	1318A-47-17	898
	2.375	4.500	15.875	1318A-47-23	942
	2.875	4.500	16.375	1318A-47-27	976
	3.375	4.500	16.875	1318A-47-33	1010
	3.875	4.500	17.375	1318A-47-37	1044
	4.875	4.500	18.375	1318A-47-47	1112
	5.875	4.500	19.375	1318A-47-57	1181

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	9.875	1318A-17-7	606
	1.375	3.000	10.375	1318A-17-13	640
	1.875	3.000	10.875	1318A-17-17	675
	2.375	3.500	11.875	1318A-17-23	718
	2.875	3.500	12.375	1318A-17-27	752
	3.375	4.000	13.375	1318A-17-33	796
	3.875	4.000	13.875	1318A-17-37	830
	4.875	4.500	15.375	1318A-17-47	908
	5.875	4.500	16.375	1318A-17-57	976

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	11.875	1318A-33-7	718
	1.375	3.500	12.375	1318A-33-13	752
	1.875	3.500	12.875	1318A-33-17	786
	2.375	4.000	13.875	1318A-33-23	830
	2.875	4.000	14.375	1318A-33-27	864
	3.375	4.500	15.375	1318A-33-33	908
	3.875	4.500	15.875	1318A-33-37	942
	4.875	4.500	16.875	1318A-33-47	1010
	5.875	4.500	17.875	1318A-33-57	1078

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	14.375	1318A-57-7	889
	1.375	4.000	15.375	1318A-57-13	932
	1.875	4.500	16.375	1318A-57-17	976
	2.375	4.500	16.875	1318A-57-23	1010
	2.875	4.500	17.375	1318A-57-27	1044
	3.375	4.500	17.875	1318A-57-33	1078
	3.875	4.500	18.375	1318A-57-37	1112
	4.875	4.500	19.375	1318A-57-47	1181
	5.875	4.500	20.375	1318A-57-57	1249

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
17.97	18
20.72	21
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.





WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed (Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

13³/₈ x 20³/₄ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

13³/₈ x 20³/₄ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	8.875	1321A-7-7	620
	1.375	3.000	9.375	1321A-7-13	660
	1.875	3.000	9.875	1321A-7-17	699
	2.375	3.500	10.875	1321A-7-23	749
	2.875	3.500	11.375	1321A-7-27	789
	3.375	4.000	12.375	1321A-7-33	839
	3.875	4.000	12.875	1321A-7-37	878
	4.875	4.500	14.375	1321A-7-47	968
	5.875	4.500	15.375	1321A-7-57	1046

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	10.375	1321A-23-7	738
	1.375	3.500	11.375	1321A-23-13	789
	1.875	3.500	11.875	1321A-23-17	828
	2.375	3.500	12.375	1321A-23-23	867
	2.875	4.000	13.375	1321A-23-27	917
	3.375	4.000	13.875	1321A-23-33	957
	3.875	4.000	14.375	1321A-23-37	996
	4.875	4.500	15.875	1321A-23-47	1086
	5.875	4.500	16.875	1321A-23-57	1164

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	12.375	1321A-37-7	867
	1.375	3.500	12.875	1321A-37-13	906
	1.875	4.000	13.875	1321A-37-17	957
	2.375	4.500	14.875	1321A-37-23	1007
	2.875	4.500	15.375	1321A-37-27	1046
	3.375	4.500	15.875	1321A-37-33	1086
	3.875	4.500	16.375	1321A-37-37	1125
	4.875	4.500	17.375	1321A-37-47	1204
	5.875	4.500	18.375	1321A-37-57	1282

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	9.375	1321A-13-7	660
	1.375	3.000	9.875	1321A-13-13	699
	1.875	3.000	10.375	1321A-13-17	738
	2.375	3.500	11.375	1321A-13-23	789
	2.875	3.500	11.875	1321A-13-27	828
	3.375	4.000	12.875	1321A-13-33	878
	3.875	4.000	13.375	1321A-13-37	917
	4.875	4.500	14.875	1321A-13-47	1007
	5.875	4.500	15.875	1321A-13-57	1086

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	10.875	1321A-27-7	777
	1.375	3.500	11.875	1321A-27-13	828
	1.875	3.500	12.375	1321A-27-17	867
	2.375	3.500	12.875	1321A-27-23	906
	2.875	4.000	13.875	1321A-27-27	957
	3.375	4.000	14.375	1321A-27-33	996
	3.875	4.000	14.875	1321A-27-37	1035
	4.875	4.500	16.375	1321A-27-47	1125
	5.875	4.500	17.375	1321A-27-57	1204

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	13.375	1321A-47-7	946
	1.375	3.500	13.875	1321A-47-13	985
	1.875	4.000	14.875	1321A-47-17	1035
	2.375	4.500	15.875	1321A-47-23	1086
	2.875	4.500	16.375	1321A-47-27	1125
	3.375	4.500	16.875	1321A-47-33	1164
	3.875	4.500	17.375	1321A-47-37	1204
	4.875	4.500	18.375	1321A-47-47	1282
	5.875	4.500	19.375	1321A-47-57	1361

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	9.875	1321A-17-7	699
	1.375	3.000	10.375	1321A-17-13	738
	1.875	3.000	10.875	1321A-17-17	777
	2.375	3.500	11.875	1321A-17-23	828
	2.875	3.500	12.375	1321A-17-27	867
	3.375	4.000	13.375	1321A-17-33	917
	3.875	4.000	13.875	1321A-17-37	957
	4.875	4.500	15.375	1321A-17-47	1046
	5.875	4.500	16.375	1321A-17-57	1125

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	11.875	1321A-33-7	828
	1.375	3.500	12.375	1321A-33-13	867
	1.875	3.500	12.875	1321A-33-17	906
	2.375	4.000	13.875	1321A-33-23	957
	2.875	4.000	14.375	1321A-33-27	996
	3.375	4.500	15.375	1321A-33-33	1046
	3.875	4.500	15.875	1321A-33-37	1086
	4.875	4.500	16.875	1321A-33-47	1164
	5.875	4.500	17.875	1321A-33-57	1243

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	3.500	14.375	1321A-57-7	1024
	1.375	4.000	15.375	1321A-57-13	1075
	1.875	4.500	16.375	1321A-57-17	1125
	2.375	4.500	16.875	1321A-57-23	1164
	2.875	4.500	17.375	1321A-57-27	1204
	3.375	4.500	17.875	1321A-57-33	1243
	3.875	4.500	18.375	1321A-57-37	1282
	4.875	4.500	19.375	1321A-57-47	1361
	5.875	4.500	20.375	1321A-57-57	1440

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.062
3.500	35	1.562
4.000	40	2.062
4.500	45	2.562
5.000	50	3.062
5.500	55	3.562
6.000	60	4.062

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
20.72	21
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


13³/₈ x 23¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

13³/₈ x 23¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	9.875	1323A-13-13	791
	1.875	3.000	10.375	1323A-13-17	836
	2.375	3.500	11.375	1323A-13-23	893
	2.875	3.500	11.875	1323A-13-27	938
	3.375	4.000	12.875	1323A-13-33	995
	3.875	4.000	13.375	1323A-13-37	1039
	4.875	4.500	14.875	1323A-13-47	1141
	5.875	4.500	15.875	1323A-13-57	1230

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	11.875	1323A-27-13	938
	1.875	3.500	12.375	1323A-27-17	982
	2.375	3.500	12.875	1323A-27-23	1027
	2.875	4.000	13.875	1323A-27-27	1084
	3.375	4.000	14.375	1323A-27-33	1128
	3.875	4.000	14.875	1323A-27-37	1173
	4.875	4.500	16.375	1323A-27-47	1274
	5.875	4.500	17.375	1323A-27-57	1363

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	3.500	13.875	1323A-47-13	1116
	1.875	4.000	14.875	1323A-47-17	1173
	2.375	4.500	15.875	1323A-47-23	1230
	2.875	4.500	16.375	1323A-47-27	1274
	3.375	4.500	16.875	1323A-47-33	1319
	3.875	4.500	17.375	1323A-47-37	1363
	4.875	4.500	18.375	1323A-47-47	1452
	5.875	4.500	19.375	1323A-47-57	1541

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.375	1323A-17-13	836
	1.875	3.000	10.875	1323A-17-17	881
	2.375	3.500	11.875	1323A-17-23	938
	2.875	3.500	12.375	1323A-17-27	982
	3.375	4.000	13.375	1323A-17-33	1039
	3.875	4.000	13.875	1323A-17-37	1084
	4.875	4.500	15.375	1323A-17-47	1185
	5.875	4.500	16.375	1323A-17-57	1274

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	3.500	12.375	1323A-33-13	982
	1.875	3.500	12.875	1323A-33-17	1027
	2.375	4.000	13.875	1323A-33-23	1084
	2.875	4.000	14.375	1323A-33-27	1128
	3.375	4.500	15.375	1323A-33-33	1185
	3.875	4.500	15.875	1323A-33-37	1230
	4.875	4.500	16.875	1323A-33-47	1319
	5.875	4.500	17.875	1323A-33-57	1408

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.375	1323A-57-13	1217
	1.875	4.500	16.375	1323A-57-17	1274
	2.375	4.500	16.875	1323A-57-23	1319
	2.875	4.500	17.375	1323A-57-27	1363
	3.375	4.500	17.875	1323A-57-33	1408
	3.875	4.500	18.375	1323A-57-37	1452
	4.875	4.500	19.375	1323A-57-47	1541
	5.875	4.500	20.375	1323A-57-57	1630

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.375	1323A-23-13	893
	1.875	3.500	11.875	1323A-23-17	938
	2.375	3.500	12.375	1323A-23-23	982
	2.875	4.000	13.375	1323A-23-27	1039
	3.375	4.000	13.875	1323A-23-33	1084
	3.875	4.000	14.375	1323A-23-37	1128
	4.875	4.500	15.875	1323A-23-47	1230
	5.875	4.500	16.875	1323A-23-57	1319

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	3.500	12.875	1323A-37-13	1027
	1.875	4.000	13.875	1323A-37-17	1084
	2.375	4.500	14.875	1323A-37-23	1141
	2.875	4.500	15.375	1323A-37-27	1185
	3.375	4.500	15.875	1323A-37-33	1230
	3.875	4.500	16.375	1323A-37-37	1274
	4.875	4.500	17.375	1323A-37-47	1363
	5.875	4.500	18.375	1323A-37-57	1452

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

13³/₈ x 26" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series
and T-Series Mold Bases, see pages 173-198.)

**Steel
Configurations
available in:**



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

13³/₈ x 26" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	9.875	1326A-13-13	876
	1.875	3.000	10.375	1326A-13-17	925
	2.375	3.500	11.375	1326A-13-23	988
	2.875	3.500	11.875	1326A-13-27	1037
	3.375	4.000	12.875	1326A-13-33	1100
	3.875	4.000	13.375	1326A-13-37	1150
	4.875	4.500	14.875	1326A-13-47	1262
	5.875	4.500	15.875	1326A-13-57	1360

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	11.875	1326A-27-13	1037
	1.875	3.500	12.375	1326A-27-17	1086
	2.375	3.500	12.875	1326A-27-23	1136
	2.875	4.000	13.875	1326A-27-27	1199
	3.375	4.000	14.375	1326A-27-33	1248
	3.875	4.000	14.875	1326A-27-37	1297
	4.875	4.500	16.375	1326A-27-47	1410
	5.875	4.500	17.375	1326A-27-57	1508

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	3.500	13.875	1326A-47-13	1234
	1.875	4.000	14.875	1326A-47-17	1297
	2.375	4.500	15.875	1326A-47-23	1360
	2.875	4.500	16.375	1326A-47-27	1410
	3.375	4.500	16.875	1326A-47-33	1459
	3.875	4.500	17.375	1326A-47-37	1508
	4.875	4.500	18.375	1326A-47-47	1607
	5.875	4.500	19.375	1326A-47-57	1705

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.375	1326A-17-13	925
	1.875	3.000	10.875	1326A-17-17	974
	2.375	3.500	11.875	1326A-17-23	1037
	2.875	3.500	12.375	1326A-17-27	1086
	3.375	4.000	13.375	1326A-17-33	1150
	3.875	4.000	13.875	1326A-17-37	1199
	4.875	4.500	15.375	1326A-17-47	1311
	5.875	4.500	16.375	1326A-17-57	1410

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	3.500	12.375	1326A-33-13	1086
	1.875	3.500	12.875	1326A-33-17	1136
	2.375	4.000	13.875	1326A-33-23	1199
	2.875	4.000	14.375	1326A-33-27	1248
	3.375	4.500	15.375	1326A-33-33	1311
	3.875	4.500	15.875	1326A-33-37	1360
	4.875	4.500	16.875	1326A-33-47	1459
	5.875	4.500	17.875	1326A-33-57	1557

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.375	1326A-57-13	1347
	1.875	4.500	16.375	1326A-57-17	1410
	2.375	4.500	16.875	1326A-57-23	1459
	2.875	4.500	17.375	1326A-57-27	1508
	3.375	4.500	17.875	1326A-57-33	1557
	3.875	4.500	18.375	1326A-57-37	1607
	4.875	4.500	19.375	1326A-57-47	1705
	5.875	4.500	20.375	1326A-57-57	1804

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.375	1326A-23-13	988
	1.875	3.500	11.875	1326A-23-17	1037
	2.375	3.500	12.375	1326A-23-23	1086
	2.875	4.000	13.375	1326A-23-27	1150
	3.375	4.000	13.875	1326A-23-33	1199
	3.875	4.000	14.375	1326A-23-37	1248
	4.875	4.500	15.875	1326A-23-47	1360
	5.875	4.500	16.875	1326A-23-57	1459

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	3.500	12.875	1326A-37-13	1136
	1.875	4.000	13.875	1326A-37-17	1199
	2.375	4.500	14.875	1326A-37-23	1262
	2.875	4.500	15.375	1326A-37-27	1311
	3.375	4.500	15.875	1326A-37-33	1360
	3.875	4.500	16.375	1326A-37-37	1410
	4.875	4.500	17.375	1326A-37-47	1508
	5.875	4.500	18.375	1326A-37-57	1607

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
25.97	26
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


13³/₈ x 29¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

13³/₈ x 29¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	9.875	1329A-13-13	993
	1.875	3.000	10.375	1329A-13-17	1049
	2.375	3.500	11.375	1329A-13-23	1121
	2.875	3.500	11.875	1329A-13-27	1177
	3.375	4.000	12.875	1329A-13-33	1248
	3.875	4.000	13.375	1329A-13-37	1304
	4.875	4.500	14.875	1329A-13-47	1432
	5.875	4.500	15.875	1329A-13-57	1543

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	11.875	1329A-27-13	1177
	1.875	3.500	12.375	1329A-27-17	1233
	2.375	3.500	12.875	1329A-27-23	1288
	2.875	4.000	13.875	1329A-27-27	1360
	3.375	4.000	14.375	1329A-27-33	1416
	3.875	4.000	14.875	1329A-27-37	1472
	4.875	4.500	16.375	1329A-27-47	1599
	5.875	4.500	17.375	1329A-27-57	1711

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	3.500	13.875	1329A-47-13	1400
	1.875	4.000	14.875	1329A-47-17	1472
	2.375	4.500	15.875	1329A-47-23	1543
	2.875	4.500	16.375	1329A-47-27	1599
	3.375	4.500	16.875	1329A-47-33	1655
	3.875	4.500	17.375	1329A-47-37	1711
	4.875	4.500	18.375	1329A-47-47	1823
	5.875	4.500	19.375	1329A-47-57	1935

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.375	1329A-17-13	1049
	1.875	3.000	10.875	1329A-17-17	1105
	2.375	3.500	11.875	1329A-17-23	1177
	2.875	3.500	12.375	1329A-17-27	1233
	3.375	4.000	13.375	1329A-17-33	1304
	3.875	4.000	13.875	1329A-17-37	1360
	4.875	4.500	15.375	1329A-17-47	1488
	5.875	4.500	16.375	1329A-17-57	1599

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	3.500	12.375	1329A-33-13	1233
	1.875	3.500	12.875	1329A-33-17	1288
	2.375	4.000	13.875	1329A-33-23	1360
	2.875	4.000	14.375	1329A-33-27	1416
	3.375	4.500	15.375	1329A-33-33	1488
	3.875	4.500	15.875	1329A-33-37	1543
	4.875	4.500	16.875	1329A-33-47	1655
	5.875	4.500	17.875	1329A-33-57	1767

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.375	1329A-57-13	1528
	1.875	4.500	16.375	1329A-57-17	1599
	2.375	4.500	16.875	1329A-57-23	1655
	2.875	4.500	17.375	1329A-57-27	1711
	3.375	4.500	17.875	1329A-57-33	1767
	3.875	4.500	18.375	1329A-57-37	1823
	4.875	4.500	19.375	1329A-57-47	1935
	5.875	4.500	20.375	1329A-57-57	2046

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.375	1329A-23-13	1121
	1.875	3.500	11.875	1329A-23-17	1177
	2.375	3.500	12.375	1329A-23-23	1233
	2.875	4.000	13.375	1329A-23-27	1304
	3.375	4.000	13.875	1329A-23-33	1360
	3.875	4.000	14.375	1329A-23-37	1416
	4.875	4.500	15.875	1329A-23-47	1546
	5.875	4.500	16.875	1329A-23-57	1655

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	3.500	12.875	1329A-37-13	1288
	1.875	4.000	13.875	1329A-37-17	1360
	2.375	4.500	14.875	1329A-37-23	1432
	2.875	4.500	15.375	1329A-37-27	1488
	3.375	4.500	15.875	1329A-37-33	1543
	3.875	4.500	16.375	1329A-37-37	1599
	4.875	4.500	17.375	1329A-37-47	1711
	5.875	4.500	18.375	1329A-37-57	1823

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
29.47	29
35.47	35

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


14⁷/₈ x 17⁷/₈ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

14⁷/₈ x 17⁷/₈ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	9.375	1518A-7-7	630
	1.375	3.000	9.875	1518A-7-13	668
	1.875	3.000	10.375	1518A-7-17	705
	2.375	3.500	11.375	1518A-7-23	752
	2.875	3.500	11.875	1518A-7-27	790
	3.375	4.000	12.875	1518A-7-33	837
	3.875	4.000	13.375	1518A-7-37	875
	4.875	4.500	14.875	1518A-7-47	960
	5.875	4.500	15.875	1518A-7-57	1035

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	10.875	1518A-23-7	743
	1.375	3.500	11.875	1518A-23-13	790
	1.875	3.500	12.375	1518A-23-17	828
	2.375	3.500	12.875	1518A-23-23	865
	2.875	4.000	13.875	1518A-23-27	913
	3.375	4.000	14.375	1518A-23-33	950
	3.875	4.000	14.875	1518A-23-37	988
	4.875	4.500	16.375	1518A-23-47	1073
	5.875	4.500	17.375	1518A-23-57	1148

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	12.875	1518A-37-7	865
	1.375	4.000	13.875	1518A-37-13	913
	1.875	4.000	14.375	1518A-37-17	950
	2.375	4.500	15.375	1518A-37-23	997
	2.875	4.500	15.875	1518A-37-27	1035
	3.375	4.500	16.375	1518A-37-33	1073
	3.875	4.500	16.875	1518A-37-37	1110
	4.875	4.500	17.875	1518A-37-47	1185
	5.875	4.500	18.875	1518A-37-57	1261

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	9.875	1518A-13-7	668
	1.375	3.000	10.375	1518A-13-13	705
	1.875	3.000	10.875	1518A-13-17	743
	2.375	3.500	11.875	1518A-13-23	790
	2.875	3.500	12.375	1518A-13-27	828
	3.375	4.000	13.375	1518A-13-33	875
	3.875	4.000	13.875	1518A-13-37	913
	4.875	4.500	15.375	1518A-13-47	997
	5.875	4.500	16.375	1518A-13-57	1073

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	11.375	1518A-27-7	781
	1.375	3.500	12.375	1518A-27-13	828
	1.875	3.500	12.875	1518A-27-17	865
	2.375	3.500	13.375	1518A-27-23	903
	2.875	4.000	14.375	1518A-27-27	950
	3.375	4.000	14.875	1518A-27-33	988
	3.875	4.000	15.375	1518A-27-37	1026
	4.875	4.500	16.875	1518A-27-47	1110
	5.875	4.500	17.875	1518A-27-57	1186

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	13.875	1518A-47-7	941
	1.375	4.000	14.875	1518A-47-13	988
	1.875	4.000	15.375	1518A-47-17	1026
	2.375	4.500	16.375	1518A-47-23	1073
	2.875	4.500	16.875	1518A-47-27	1110
	3.375	4.500	17.375	1518A-47-33	1148
	3.875	4.500	17.875	1518A-47-37	1186
	4.875	4.500	18.875	1518A-47-47	1261
	5.875	4.500	19.875	1518A-47-57	1336

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	10.375	1518A-17-7	705
	1.375	3.000	10.875	1518A-17-13	743
	1.875	3.500	11.875	1518A-17-17	790
	2.375	3.500	12.375	1518A-17-23	828
	2.875	4.000	13.375	1518A-17-27	875
	3.375	4.000	13.875	1518A-17-33	913
	3.875	4.000	14.375	1518A-17-37	950
	4.875	4.500	15.875	1518A-17-47	1035
	5.875	4.500	16.875	1518A-17-57	1110

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	12.375	1518A-33-7	828
	1.375	4.000	13.375	1518A-33-13	875
	1.875	4.000	13.875	1518A-33-17	913
	2.375	4.000	14.375	1518A-33-23	950
	2.875	4.500	15.375	1518A-33-27	997
	3.375	4.500	15.875	1518A-33-33	1035
	3.875	4.500	16.375	1518A-33-37	1073
	4.875	4.500	17.375	1518A-33-47	1148
	5.875	4.500	18.375	1518A-33-57	1223

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	4.000	15.375	1518A-57-7	1026
	1.375	4.000	15.875	1518A-57-13	1063
	1.875	4.500	16.875	1518A-57-17	1110
	2.375	4.500	17.375	1518A-57-23	1148
	2.875	4.500	17.875	1518A-57-27	1186
	3.375	4.500	18.375	1518A-57-33	1223
	3.875	4.500	18.875	1518A-57-37	1261
	4.875	4.500	19.875	1518A-57-47	1336
	5.875	4.500	20.875	1518A-57-57	1412

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
17.85	18
23.72	23
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


14⁷/₈ x 23³/₄ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

14⁷/₈ x 23³/₄ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1524A-13-13	937
	1.875	3.000	10.875	1524A-13-17	987
	2.375	3.500	11.875	1524A-13-23	1050
	2.875	3.500	12.375	1524A-13-27	1100
	3.375	4.000	13.375	1524A-13-33	1162
	3.875	4.000	13.875	1524A-13-37	1212
	4.875	4.500	15.375	1524A-13-47	1325
	5.875	4.500	16.375	1524A-13-57	1425

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1524A-27-13	1100
	1.875	3.500	12.875	1524A-27-17	1150
	2.375	3.500	13.375	1524A-27-23	1200
	2.875	4.000	14.375	1524A-27-27	1262
	3.375	4.000	14.875	1524A-27-33	1312
	3.875	4.000	15.375	1524A-27-37	1363
	4.875	4.500	16.875	1524A-27-47	1475
	5.875	4.500	17.875	1524A-27-57	1575

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1524A-47-13	1312
	1.875	4.000	15.375	1524A-47-17	1363
	2.375	4.500	16.375	1524A-47-23	1425
	2.875	4.500	16.875	1524A-47-27	1475
	3.375	4.500	17.375	1524A-47-33	1525
	3.875	4.500	17.875	1524A-47-37	1575
	4.875	4.500	18.875	1524A-47-47	1675
	5.875	4.500	19.875	1524A-47-57	1775

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1524A-17-13	987
	1.875	3.500	11.875	1524A-17-17	1050
	2.375	3.500	12.375	1524A-17-23	1100
	2.875	4.000	13.375	1524A-17-27	1162
	3.375	4.000	13.875	1524A-17-33	1212
	3.875	4.000	14.375	1524A-17-37	1262
	4.875	4.500	15.875	1524A-17-47	1375
	5.875	4.500	16.875	1524A-17-57	1475

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1524A-33-13	1162
	1.875	4.000	13.875	1524A-33-17	1212
	2.375	4.000	14.375	1524A-33-23	1262
	2.875	4.500	15.375	1524A-33-27	1325
	3.375	4.500	15.875	1524A-33-33	1375
	3.875	4.500	16.375	1524A-33-37	1425
	4.875	4.500	17.375	1524A-33-47	1525
	5.875	4.500	18.375	1524A-33-57	1625

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1524A-57-13	1413
	1.875	4.500	16.875	1524A-57-17	1475
	2.375	4.500	17.375	1524A-57-23	1525
	2.875	4.500	17.875	1524A-57-27	1575
	3.375	4.500	18.375	1524A-57-33	1625
	3.875	4.500	18.875	1524A-57-37	1675
	4.875	4.500	19.875	1524A-57-47	1775
	5.875	4.500	20.875	1524A-57-57	1876

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1524A-23-13	1050
	1.875	3.500	12.375	1524A-23-17	1100
	2.375	3.500	12.875	1524A-23-23	1150
	2.875	4.000	13.875	1524A-23-27	1212
	3.375	4.000	14.375	1524A-23-33	1262
	3.875	4.000	14.875	1524A-23-37	1312
	4.875	4.500	16.375	1524A-23-47	1425
	5.875	4.500	17.375	1524A-23-57	1525

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1524A-37-13	1212
	1.875	4.000	14.375	1524A-37-17	1262
	2.375	4.500	15.375	1524A-37-23	1325
	2.875	4.500	15.875	1524A-37-27	1375
	3.375	4.500	16.375	1524A-37-33	1425
	3.875	4.500	16.875	1524A-37-37	1475
	4.875	4.500	17.875	1524A-37-47	1575
	5.875	4.500	18.875	1524A-37-57	1675

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.72	24
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


14⁷/₈ x 29¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

14⁷/₈ x 29¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1529A-13-13	1164
	1.875	3.000	10.875	1529A-13-17	1226
	2.375	3.500	11.875	1529A-13-23	1304
	2.875	3.500	12.375	1529A-13-27	1366
	3.375	4.000	13.375	1529A-13-33	1444
	3.875	4.000	13.875	1529A-13-37	1506
	4.875	4.500	15.375	1529A-13-47	1646
	5.875	4.500	16.375	1529A-13-57	1770

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1529A-27-13	1366
	1.875	3.500	12.875	1529A-27-17	1428
	2.375	3.500	13.375	1529A-27-23	1490
	2.875	4.000	14.375	1529A-27-27	1568
	3.375	4.000	14.875	1529A-27-33	1630
	3.875	4.000	15.375	1529A-27-37	1692
	4.875	4.500	16.875	1529A-27-47	1832
	5.875	4.500	17.875	1529A-27-57	1957

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1529A-47-13	1630
	1.875	4.000	15.375	1529A-47-17	1692
	2.375	4.500	16.375	1529A-47-23	1770
	2.875	4.500	16.875	1529A-47-27	1832
	3.375	4.500	17.375	1529A-47-33	1894
	3.875	4.500	17.875	1529A-47-37	1957
	4.875	4.500	18.875	1529A-47-47	2081
	5.875	4.500	19.875	1529A-47-57	2205

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1529A-17-13	1226
	1.875	3.500	11.875	1529A-17-17	1304
	2.375	3.500	12.375	1529A-17-23	1366
	2.875	4.000	13.375	1529A-17-27	1444
	3.375	4.000	13.875	1529A-17-33	1506
	3.875	4.000	14.375	1529A-17-37	1568
	4.875	4.500	15.875	1529A-17-47	1708
	5.875	4.500	16.875	1529A-17-57	1832

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1529A-33-13	1444
	1.875	4.000	13.875	1529A-33-17	1506
	2.375	4.000	14.375	1529A-33-23	1568
	2.875	4.500	15.375	1529A-33-27	1646
	3.375	4.500	15.875	1529A-33-33	1708
	3.875	4.500	16.375	1529A-33-37	1770
	4.875	4.500	17.375	1529A-33-47	1894
	5.875	4.500	18.375	1529A-33-57	2019

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1529A-57-13	1755
	1.875	4.500	16.875	1529A-57-17	1832
	2.375	4.500	17.375	1529A-57-23	1894
	2.875	4.500	17.875	1529A-57-27	1957
	3.375	4.500	18.375	1529A-57-33	2019
	3.875	4.500	18.875	1529A-57-37	2081
	4.875	4.500	19.875	1529A-57-47	2205
	5.875	4.500	20.875	1529A-57-57	2330

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1529A-23-13	1304
	1.875	3.500	12.375	1529A-23-17	1366
	2.375	3.500	12.875	1529A-23-23	1428
	2.875	4.000	13.875	1529A-23-27	1506
	3.375	4.000	14.375	1529A-23-33	1568
	3.875	4.000	14.875	1529A-23-37	1630
	4.875	4.500	16.375	1529A-23-47	1770
	5.875	4.500	17.375	1529A-23-57	1894

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1529A-37-13	1506
	1.875	4.000	14.375	1529A-37-17	1568
	2.375	4.500	15.375	1529A-37-23	1646
	2.875	4.500	15.875	1529A-37-27	1708
	3.375	4.500	16.375	1529A-37-33	1770
	3.875	4.500	16.875	1529A-37-37	1832
	4.875	4.500	17.875	1529A-37-47	1957
	5.875	4.500	18.875	1529A-37-57	2081

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
29.47	29
35.47	35

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


15⁷/₈ x 16" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

15⁷/₈ x 16" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	9.375	1616A-7-7	601
	1.375	3.000	9.875	1616A-7-13	637
	1.875	3.000	10.375	1616A-7-17	673
	2.375	3.500	11.375	1616A-7-23	717
	2.875	3.500	11.875	1616A-7-27	753
	3.375	4.000	12.875	1616A-7-33	798
	3.875	4.000	13.375	1616A-7-37	834
	4.875	4.500	14.875	1616A-7-47	914
	5.875	4.500	15.875	1616A-7-57	986

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	10.875	1616A-23-7	709
	1.375	3.500	11.875	1616A-23-13	753
	1.875	3.500	12.375	1616A-23-17	789
	2.375	3.500	12.875	1616A-23-23	825
	2.875	4.000	13.875	1616A-23-27	870
	3.375	4.000	14.375	1616A-23-33	906
	3.875	4.000	14.875	1616A-23-37	942
	4.875	4.500	16.375	1616A-23-47	1022
	5.875	4.500	17.375	1616A-23-57	1094

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	12.875	1616A-37-7	825
	1.375	4.000	13.875	1616A-37-13	870
	1.875	4.000	14.375	1616A-37-17	906
	2.375	4.500	15.375	1616A-37-23	950
	2.875	4.500	15.875	1616A-37-27	986
	3.375	4.500	16.375	1616A-37-33	1022
	3.875	4.500	16.875	1616A-37-37	1058
	4.875	4.500	17.875	1616A-37-47	1130
	5.875	4.500	18.875	1616A-37-57	1202

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	9.875	1616A-13-7	637
	1.375	3.000	10.375	1616A-13-13	673
	1.875	3.000	10.875	1616A-13-17	709
	2.375	3.500	11.875	1616A-13-23	753
	2.875	3.500	12.375	1616A-13-27	789
	3.375	4.000	13.375	1616A-13-33	834
	3.875	4.000	13.875	1616A-13-37	870
	4.875	4.500	15.375	1616A-13-47	950
	5.875	4.500	16.375	1616A-13-57	1022

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	11.375	1616A-27-7	745
	1.375	3.500	12.375	1616A-27-13	789
	1.875	3.500	12.875	1616A-27-17	825
	2.375	3.500	13.375	1616A-27-23	861
	2.875	4.000	14.375	1616A-27-27	906
	3.375	4.000	14.875	1616A-27-33	942
	3.875	4.000	15.375	1616A-27-37	978
	4.875	4.500	16.875	1616A-27-47	1058
	5.875	4.500	17.875	1616A-27-57	1130

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	13.875	1616A-47-7	897
	1.375	4.000	14.875	1616A-47-13	942
	1.875	4.000	15.375	1616A-47-17	978
	2.375	4.500	16.375	1616A-47-23	1022
	2.875	4.500	16.875	1616A-47-27	1058
	3.375	4.500	17.375	1616A-47-33	1094
	3.875	4.500	17.875	1616A-47-37	1130
	4.875	4.500	18.875	1616A-47-47	1202
	5.875	4.500	19.875	1616A-47-57	1274

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	10.375	1616A-17-7	673
	1.375	3.000	10.875	1616A-17-13	709
	1.875	3.500	11.875	1616A-17-17	753
	2.375	3.500	12.375	1616A-17-23	789
	2.875	4.000	13.375	1616A-17-27	834
	3.375	4.000	13.875	1616A-17-33	870
	3.875	4.000	14.375	1616A-17-37	906
	4.875	4.500	15.875	1616A-17-47	986
	5.875	4.500	16.875	1616A-17-57	1058

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	12.375	1616A-33-7	789
	1.375	4.000	13.375	1616A-33-13	834
	1.875	4.000	13.875	1616A-33-17	870
	2.375	4.000	14.375	1616A-33-23	906
	2.875	4.500	15.375	1616A-33-27	950
	3.375	4.500	15.875	1616A-33-33	986
	3.875	4.500	16.375	1616A-33-37	1022
	4.875	4.500	17.375	1616A-33-47	1094
	5.875	4.500	18.375	1616A-33-57	1166

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	4.000	15.375	1616A-57-7	978
	1.375	4.000	15.875	1616A-57-13	1014
	1.875	4.500	16.875	1616A-57-17	1058
	2.375	4.500	17.375	1616A-57-23	1094
	2.875	4.500	17.875	1616A-57-27	1130
	3.375	4.500	18.375	1616A-57-33	1166
	3.875	4.500	18.875	1616A-57-37	1202
	4.875	4.500	19.875	1616A-57-47	1274
	5.875	4.500	20.875	1616A-57-57	1346

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
15.97	16
19.97	20
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.




WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

15⁷/₈ x 20" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

15⁷/₈ x 20" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
.875 (7/8)	0.875	3.000	9.375	1620A-7-7	751
	1.375	3.000	9.875	1620A-7-13	796
	1.875	3.000	10.375	1620A-7-17	841
	2.375	3.500	11.375	1620A-7-23	896
	2.875	3.500	11.875	1620A-7-27	941
	3.375	4.000	12.875	1620A-7-33	997
	3.875	4.000	13.375	1620A-7-37	1042
	4.875	4.500	14.875	1620A-7-47	1143
	5.875	4.500	15.875	1620A-7-57	1232

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	0.875	3.000	10.875	1620A-23-7	886
	1.375	3.500	11.875	1620A-23-13	941
	1.875	3.500	12.375	1620A-23-17	986
	2.375	3.500	12.875	1620A-23-23	1031
	2.875	4.000	13.875	1620A-23-27	1087
	3.375	4.000	14.375	1620A-23-33	1132
	3.875	4.000	14.875	1620A-23-37	1177
	4.875	4.500	16.375	1620A-23-47	1277
	5.875	4.500	17.375	1620A-23-57	1367

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	0.875	3.500	12.875	1620A-37-7	1031
	1.375	4.000	13.875	1620A-37-13	1087
	1.875	4.000	14.375	1620A-37-17	1132
	2.375	4.500	15.375	1620A-37-23	1187
	2.875	4.500	15.875	1620A-37-27	1232
	3.375	4.500	16.375	1620A-37-33	1277
	3.875	4.500	16.875	1620A-37-37	1322
	4.875	4.500	17.875	1620A-37-47	1412
	5.875	4.500	18.875	1620A-37-57	1502

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	0.875	3.000	9.875	1620A-13-7	796
	1.375	3.000	10.375	1620A-13-13	841
	1.875	3.000	10.875	1620A-13-17	886
	2.375	3.500	11.875	1620A-13-23	941
	2.875	3.500	12.375	1620A-13-27	986
	3.375	4.000	13.375	1620A-13-33	1042
	3.875	4.000	13.875	1620A-13-37	1087
	4.875	4.500	15.375	1620A-13-47	1187
	5.875	4.500	16.375	1620A-13-57	1277

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	0.875	3.000	11.375	1620A-27-7	931
	1.375	3.500	12.375	1620A-27-13	986
	1.875	3.500	12.875	1620A-27-17	1031
	2.375	3.500	13.375	1620A-27-23	1076
	2.875	4.000	14.375	1620A-27-27	1132
	3.375	4.000	14.875	1620A-27-33	1177
	3.875	4.000	15.375	1620A-27-37	1222
	4.875	4.500	16.875	1620A-27-47	1322
	5.875	4.500	17.875	1620A-27-57	1412

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	0.875	3.500	13.875	1620A-47-7	1121
	1.375	4.000	14.875	1620A-47-13	1177
	1.875	4.000	15.375	1620A-47-17	1222
	2.375	4.500	16.375	1620A-47-23	1277
	2.875	4.500	16.875	1620A-47-27	1322
	3.375	4.500	17.375	1620A-47-33	1367
	3.875	4.500	17.875	1620A-47-37	1412
	4.875	4.500	18.875	1620A-47-47	1502
	5.875	4.500	19.875	1620A-47-57	1592

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	0.875	3.000	10.375	1620A-17-7	841
	1.375	3.000	10.875	1620A-17-13	886
	1.875	3.500	11.875	1620A-17-17	941
	2.375	3.500	12.375	1620A-17-23	986
	2.875	4.000	13.375	1620A-17-27	1042
	3.375	4.000	13.875	1620A-17-33	1087
	3.875	4.000	14.375	1620A-17-37	1132
	4.875	4.500	15.875	1620A-17-47	1232
	5.875	4.500	16.875	1620A-17-57	1322

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	0.875	3.500	12.375	1620A-33-7	986
	1.375	4.000	13.375	1620A-33-13	1042
	1.875	4.000	13.875	1620A-33-17	1087
	2.375	4.000	14.375	1620A-33-23	1132
	2.875	4.500	15.375	1620A-33-27	1187
	3.375	4.500	15.875	1620A-33-33	1232
	3.875	4.500	16.375	1620A-33-37	1277
	4.875	4.500	17.375	1620A-33-47	1367
	5.875	4.500	18.375	1620A-33-57	1457

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	0.875	4.000	15.375	1620A-57-7	1222
	1.375	4.000	15.875	1620A-57-13	1267
	1.875	4.500	16.875	1620A-57-17	1322
	2.375	4.500	17.375	1620A-57-23	1367
	2.875	4.500	17.875	1620A-57-27	1412
	3.375	4.500	18.375	1620A-57-33	1457
	3.875	4.500	18.875	1620A-57-37	1502
	4.875	4.500	19.875	1620A-57-47	1592
	5.875	4.500	20.875	1620A-57-57	1682

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
19.97	20
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed (Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


15⁷/₈ x 23¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

15⁷/₈ x 23¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1%)	1.375	3.000	10.375	1623A-13-13	988
	1.875	3.000	10.875	1623A-13-17	1041
	2.375	3.500	11.875	1623A-13-23	1106
	2.875	3.500	12.375	1623A-13-27	1159
	3.375	4.000	13.375	1623A-13-33	1224
	3.875	4.000	13.875	1623A-13-37	1277
	4.875	4.500	15.375	1623A-13-47	1395
	5.875	4.500	16.375	1623A-13-57	1501

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2%)	1.375	3.500	12.375	1623A-27-13	1159
	1.875	3.500	12.875	1623A-27-17	1212
	2.375	3.500	13.375	1623A-27-23	1265
	2.875	4.000	14.375	1623A-27-27	1330
	3.375	4.000	14.875	1623A-27-33	1383
	3.875	4.000	15.375	1623A-27-37	1436
	4.875	4.500	16.875	1623A-27-47	1554
	5.875	4.500	17.875	1623A-27-57	1659

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4%)	1.375	4.000	14.875	1623A-47-13	1383
	1.875	4.000	15.375	1623A-47-17	1436
	2.375	4.500	16.375	1623A-47-23	1501
	2.875	4.500	16.875	1623A-47-27	1554
	3.375	4.500	17.375	1623A-47-33	1607
	3.875	4.500	17.875	1623A-47-37	1659
	4.875	4.500	18.875	1623A-47-47	1765
	5.875	4.500	19.875	1623A-47-57	1871

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1%)	1.375	3.000	10.875	1623A-17-13	1041
	1.875	3.000	11.375	1623A-17-17	1106
	2.375	3.500	12.375	1623A-17-23	1159
	2.875	3.500	12.875	1623A-17-27	1224
	3.375	4.000	13.875	1623A-17-33	1277
	3.875	4.000	14.375	1623A-17-37	1330
	4.875	4.500	15.875	1623A-17-47	1448
	5.875	4.500	16.875	1623A-17-57	1554

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3%)	1.375	4.000	13.375	1623A-33-13	1224
	1.875	4.000	13.875	1623A-33-17	1277
	2.375	4.000	14.375	1623A-33-23	1330
	2.875	4.500	15.375	1623A-33-27	1395
	3.375	4.500	15.875	1623A-33-33	1448
	3.875	4.500	16.375	1623A-33-37	1501
	4.875	4.500	17.375	1623A-33-47	1607
	5.875	4.500	18.375	1623A-33-57	1712

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5%)	1.375	4.000	15.875	1623A-57-13	1488
	1.875	4.500	16.875	1623A-57-17	1554
	2.375	4.500	17.375	1623A-57-23	1607
	2.875	4.500	17.875	1623A-57-27	1659
	3.375	4.500	18.375	1623A-57-33	1712
	3.875	4.500	18.875	1623A-57-37	1765
	4.875	4.500	19.875	1623A-57-47	1871
	5.875	4.500	20.875	1623A-57-57	1976

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2%)	1.375	3.500	11.875	1623A-23-13	1106
	1.875	3.500	12.375	1623A-23-17	1159
	2.375	3.500	12.875	1623A-23-23	1212
	2.875	4.000	13.875	1623A-23-27	1277
	3.375	4.000	14.375	1623A-23-33	1330
	3.875	4.000	14.875	1623A-23-37	1383
	4.875	4.500	16.375	1623A-23-47	1501
	5.875	4.500	17.375	1623A-23-57	1607

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3%)	1.375	4.000	13.875	1623A-37-13	1277
	1.875	4.000	14.375	1623A-37-17	1330
	2.375	4.500	15.375	1623A-37-23	1395
	2.875	4.500	15.875	1623A-37-27	1448
	3.375	4.500	16.375	1623A-37-33	1501
	3.875	4.500	16.875	1623A-37-37	1554
	4.875	4.500	17.875	1623A-37-47	1659
	5.875	4.500	18.875	1623A-37-57	1765

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


15⁷/₈ x 26" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

15⁷/₈ x 26" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1626A-13-13	1093
	1.875	3.000	10.875	1626A-13-17	1151
	2.375	3.500	11.875	1626A-13-23	1224
	2.875	3.500	12.375	1626A-13-27	1282
	3.375	4.000	13.375	1626A-13-33	1354
	3.875	4.000	13.875	1626A-13-37	1413
	4.875	4.500	15.375	1626A-13-47	1544
	5.875	4.500	16.375	1626A-13-57	1661

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1626A-27-13	1282
	1.875	3.500	12.875	1626A-27-17	1341
	2.375	3.500	13.375	1626A-27-23	1399
	2.875	4.000	14.375	1626A-27-27	1471
	3.375	4.000	14.875	1626A-27-33	1530
	3.875	4.000	15.375	1626A-27-37	1588
	4.875	4.500	16.875	1626A-27-47	1719
	5.875	4.500	17.875	1626A-27-57	1836

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1626A-47-13	1530
	1.875	4.000	15.375	1626A-47-17	1588
	2.375	4.500	16.375	1626A-47-23	1661
	2.875	4.500	16.875	1626A-47-27	1719
	3.375	4.500	17.375	1626A-47-33	1778
	3.875	4.500	17.875	1626A-47-37	1836
	4.875	4.500	18.875	1626A-47-47	1953
	5.875	4.500	19.875	1626A-47-57	2070

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1626A-17-13	1151
	1.875	3.000	11.375	1626A-17-17	1224
	2.375	3.500	12.375	1626A-17-23	1282
	2.875	3.500	12.875	1626A-17-27	1354
	3.375	4.000	13.875	1626A-17-33	1413
	3.875	4.000	14.375	1626A-17-37	1471
	4.875	4.500	15.875	1626A-17-47	1602
	5.875	4.500	16.875	1626A-17-57	1719

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1626A-33-13	1354
	1.875	4.000	13.875	1626A-33-17	1413
	2.375	4.000	14.375	1626A-33-23	1471
	2.875	4.500	15.375	1626A-33-27	1544
	3.375	4.500	15.875	1626A-33-33	1602
	3.875	4.500	16.375	1626A-33-37	1661
	4.875	4.500	17.375	1626A-33-47	1778
	5.875	4.500	18.375	1626A-33-57	1894

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1626A-57-13	1647
	1.875	4.500	16.875	1626A-57-17	1719
	2.375	4.500	17.375	1626A-57-23	1778
	2.875	4.500	17.875	1626A-57-27	1836
	3.375	4.500	18.375	1626A-57-33	1894
	3.875	4.500	18.875	1626A-57-37	1953
	4.875	4.500	19.875	1626A-57-47	2070
	5.875	4.500	20.875	1626A-57-57	2187

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1626A-23-13	1224
	1.875	3.500	12.375	1626A-23-17	1282
	2.375	3.500	12.875	1626A-23-23	1341
	2.875	4.000	13.875	1626A-23-27	1413
	3.375	4.000	14.375	1626A-23-33	1471
	3.875	4.000	14.875	1626A-23-37	1530
	4.875	4.500	16.375	1626A-23-47	1661
	5.875	4.500	17.375	1626A-23-57	1778

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1626A-37-13	1413
	1.875	4.000	14.375	1626A-37-17	1471
	2.375	4.500	15.375	1626A-37-23	1544
	2.875	4.500	15.875	1626A-37-27	1602
	3.375	4.500	16.375	1626A-37-33	1661
	3.875	4.500	16.875	1626A-37-37	1719
	4.875	4.500	17.875	1626A-37-47	1836
	5.875	4.500	18.875	1626A-37-57	1953

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
25.97	26
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


15⁷/₈ x 29¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

15⁷/₈ x 29¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1629A-13-13	1240
	1.875	3.000	10.875	1629A-13-17	1306
	2.375	3.500	11.875	1629A-13-23	1388
	2.875	3.500	12.375	1629A-13-27	1455
	3.375	4.000	13.375	1629A-13-33	1537
	3.875	4.000	13.875	1629A-13-37	1603
	4.875	4.500	15.375	1629A-13-47	1751
	5.875	4.500	16.375	1629A-13-57	1884

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1629A-27-13	1455
	1.875	3.500	12.875	1629A-27-17	1521
	2.375	3.500	13.375	1629A-27-23	1587
	2.875	4.000	14.375	1629A-27-27	1669
	3.375	4.000	14.875	1629A-27-33	1736
	3.875	4.000	15.375	1629A-27-37	1802
	4.875	4.500	16.875	1629A-27-47	1950
	5.875	4.500	17.875	1629A-27-57	2083

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1629A-47-13	1736
	1.875	4.000	15.375	1629A-47-17	1802
	2.375	4.500	16.375	1629A-47-23	1884
	2.875	4.500	16.875	1629A-47-27	1950
	3.375	4.500	17.375	1629A-47-33	2017
	3.875	4.500	17.875	1629A-47-37	2083
	4.875	4.500	18.875	1629A-47-47	2216
	5.875	4.500	19.875	1629A-47-57	2348

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1629A-17-13	1306
	1.875	3.000	11.375	1629A-17-17	1388
	2.375	3.500	12.375	1629A-17-23	1455
	2.875	3.500	12.875	1629A-17-27	1537
	3.375	4.000	13.875	1629A-17-33	1603
	3.875	4.000	14.375	1629A-17-37	1669
	4.875	4.500	15.875	1629A-17-47	1818
	5.875	4.500	16.875	1629A-17-57	1950

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1629A-33-13	1537
	1.875	4.000	13.875	1629A-33-17	1603
	2.375	4.000	14.375	1629A-33-23	1669
	2.875	4.500	15.375	1629A-33-27	1751
	3.375	4.500	15.875	1629A-33-33	1818
	3.875	4.500	16.375	1629A-33-37	1884
	4.875	4.500	17.375	1629A-33-47	2017
	5.875	4.500	18.375	1629A-33-57	2149

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1629A-57-13	1868
	1.875	4.500	16.875	1629A-57-17	1950
	2.375	4.500	17.375	1629A-57-23	2017
	2.875	4.500	17.875	1629A-57-27	2083
	3.375	4.500	18.375	1629A-57-33	2149
	3.875	4.500	18.875	1629A-57-37	2216
	4.875	4.500	19.875	1629A-57-47	2348
	5.875	4.500	20.875	1629A-57-57	2481

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1629A-23-13	1388
	1.875	3.500	12.375	1629A-23-17	1455
	2.375	3.500	12.875	1629A-23-23	1521
	2.875	4.000	13.875	1629A-23-27	1603
	3.375	4.000	14.375	1629A-23-33	1669
	3.875	4.000	14.875	1629A-23-37	1736
	4.875	4.500	16.375	1629A-23-47	1884
	5.875	4.500	17.375	1629A-23-57	2017

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1629A-37-13	1603
	1.875	4.000	14.375	1629A-37-17	1669
	2.375	4.500	15.375	1629A-37-23	1751
	2.875	4.500	15.875	1629A-37-27	1818
	3.375	4.500	16.375	1629A-37-33	1884
	3.875	4.500	16.875	1629A-37-37	1950
	4.875	4.500	17.875	1629A-37-47	2-93
	5.875	4.500	18.875	1629A-37-57	2216

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


15⁷/₈ x 35¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

15⁷/₈ x 35¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1635A-13-13	1492
	1.875	3.000	10.875	1635A-13-17	1572
	2.375	3.500	11.875	1635A-13-23	1671
	2.875	3.500	12.375	1635A-13-27	1750
	3.375	4.000	13.375	1635A-13-33	1849
	3.875	4.000	13.875	1635A-13-37	1929
	4.875	4.500	15.375	1635A-13-47	2107
	5.875	4.500	16.375	1635A-13-57	2267

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1635A-27-13	1750
	1.875	3.500	12.875	1635A-27-17	1830
	2.375	3.500	13.375	1635A-27-23	1910
	2.875	4.000	14.375	1635A-27-27	2009
	3.375	4.000	14.875	1635A-27-33	2089
	3.875	4.000	15.375	1635A-27-37	2168
	4.875	4.500	16.875	1635A-27-47	2347
	5.875	4.500	17.875	1635A-27-57	2507

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1635A-47-13	2089
	1.875	4.000	15.375	1635A-47-17	2168
	2.375	4.500	16.375	1635A-47-23	2267
	2.875	4.500	16.875	1635A-47-27	2347
	3.375	4.500	17.375	1635A-47-33	2427
	3.875	4.500	17.875	1635A-47-37	2507
	4.875	4.500	18.875	1635A-47-47	2666
	5.875	4.500	19.875	1635A-47-57	2826

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1635A-17-13	1572
	1.875	3.000	11.375	1635A-17-17	1671
	2.375	3.500	12.375	1635A-17-23	1750
	2.875	3.500	12.875	1635A-17-27	1849
	3.375	4.000	13.875	1635A-17-33	1929
	3.875	4.000	14.375	1635A-17-37	2009
	4.875	4.500	15.875	1635A-17-47	2187
	5.875	4.500	16.875	1635A-17-57	2347

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1635A-33-13	1849
	1.875	4.000	13.875	1635A-33-17	1929
	2.375	4.000	14.375	1635A-33-23	2009
	2.875	4.500	15.375	1635A-33-27	2107
	3.375	4.500	15.875	1635A-33-33	2187
	3.875	4.500	16.375	1635A-33-37	2267
	4.875	4.500	17.375	1635A-33-47	2427
	5.875	4.500	18.375	1635A-33-57	2586

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1635A-57-13	2248
	1.875	4.500	16.875	1635A-57-17	2347
	2.375	4.500	17.375	1635A-57-23	2427
	2.875	4.500	17.875	1635A-57-27	2507
	3.375	4.500	18.375	1635A-57-33	2586
	3.875	4.500	18.875	1635A-57-37	2666
	4.875	4.500	19.875	1635A-57-47	2826
	5.875	4.500	20.875	1635A-57-57	2987

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1635A-23-13	1671
	1.875	3.500	12.375	1635A-23-17	1750
	2.375	3.500	12.875	1635A-23-23	1830
	2.875	4.000	13.875	1635A-23-27	1929
	3.375	4.000	14.375	1635A-23-33	2009
	3.875	4.000	14.875	1635A-23-37	2089
	4.875	4.500	16.375	1635A-23-47	2267
	5.875	4.500	17.375	1635A-23-57	2427

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1635A-37-13	1929
	1.875	4.000	14.375	1635A-37-17	2009
	2.375	4.500	15.375	1635A-37-23	2107
	2.875	4.500	15.875	1635A-37-27	2187
	3.375	4.500	16.375	1635A-37-33	2267
	3.875	4.500	16.875	1635A-37-37	2347
	4.875	4.500	17.875	1635A-37-47	2507
	5.875	4.500	18.875	1635A-37-57	2666

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


16¹/₂ x 23³/₄ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

16¹/₂ x 23³/₄ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1724A-13-13	1037
	1.875	3.000	10.875	1724A-13-17	1092
	2.375	3.500	11.875	1724A-13-23	1160
	2.875	3.500	12.375	1724A-13-27	1216
	3.375	4.000	13.375	1724A-13-33	1284
	3.875	4.000	13.875	1724A-13-37	1340
	4.875	4.500	15.375	1724A-13-47	1463
	5.875	4.500	16.375	1724A-13-57	1574

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1724A-27-13	1216
	1.875	3.500	12.875	1724A-27-17	1271
	2.375	3.500	13.375	1724A-27-23	1327
	2.875	4.000	14.375	1724A-27-27	1395
	3.375	4.000	14.875	1724A-27-33	1451
	3.875	4.000	15.375	1724A-27-37	1506
	4.875	4.500	16.875	1724A-27-47	1630
	5.875	4.500	17.875	1724A-27-57	1741

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1724A-47-13	1451
	1.875	4.000	15.375	1724A-47-17	1506
	2.375	4.500	16.375	1724A-47-23	1574
	2.875	4.500	16.875	1724A-47-27	1630
	3.375	4.500	17.375	1724A-47-33	1685
	3.875	4.500	17.875	1724A-47-37	1741
	4.875	4.500	18.875	1724A-47-47	1852
	5.875	4.500	19.875	1724A-47-57	1963

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1724A-17-13	1092
	1.875	3.000	11.375	1724A-17-17	1160
	2.375	3.500	12.375	1724A-17-23	1216
	2.875	3.500	12.875	1724A-17-27	1284
	3.375	4.000	13.875	1724A-17-33	1340
	3.875	4.000	14.375	1724A-17-37	1395
	4.875	4.500	15.875	1724A-17-47	1519
	5.875	4.500	16.875	1724A-17-57	1630

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1724A-33-13	1284
	1.875	4.000	13.875	1724A-33-17	1340
	2.375	4.000	14.375	1724A-33-23	1395
	2.875	4.500	15.375	1724A-33-27	1463
	3.375	4.500	15.875	1724A-33-33	1519
	3.875	4.500	16.375	1724A-33-37	1574
	4.875	4.500	17.375	1724A-33-47	1685
	5.875	4.500	18.375	1724A-33-57	1796

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1724A-57-13	1562
	1.875	4.500	16.875	1724A-57-17	1630
	2.375	4.500	17.375	1724A-57-23	1685
	2.875	4.500	17.875	1724A-57-27	1741
	3.375	4.500	18.375	1724A-57-33	1796
	3.875	4.500	18.875	1724A-57-37	1852
	4.875	4.500	19.875	1724A-57-47	1963
	5.875	4.500	20.875	1724A-57-57	2074

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1724A-23-13	1160
	1.875	3.500	12.375	1724A-23-17	1216
	2.375	3.500	12.875	1724A-23-23	1271
	2.875	4.000	13.875	1724A-23-27	1340
	3.375	4.000	14.375	1724A-23-33	1395
	3.875	4.000	14.875	1724A-23-37	1451
	4.875	4.500	16.375	1724A-23-47	1574
	5.875	4.500	17.375	1724A-23-57	1685

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1724A-37-13	1340
	1.875	4.000	14.375	1724A-37-17	1395
	2.375	4.500	15.375	1724A-37-23	1463
	2.875	4.500	15.875	1724A-37-27	1519
	3.375	4.500	16.375	1724A-37-33	1574
	3.875	4.500	16.875	1724A-37-37	1630
	4.875	4.500	17.875	1724A-37-47	1741
	5.875	4.500	18.875	1724A-37-57	1852

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.72	24
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

16¹/₂ x 29¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

16¹/₂ x 29¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1729A-13-13	1288
	1.875	3.000	10.875	1729A-13-17	1357
	2.375	3.500	11.875	1729A-13-23	1441
	2.875	3.500	12.375	1729A-13-27	1510
	3.375	4.000	13.375	1729A-13-33	1595
	3.875	4.000	13.875	1729A-13-37	1664
	4.875	4.500	15.375	1729A-13-47	1817
	5.875	4.500	16.375	1729A-13-57	1955

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1729A-27-13	1510
	1.875	3.500	12.875	1729A-27-17	1579
	2.375	3.500	13.375	1729A-27-23	1648
	2.875	4.000	14.375	1729A-27-27	1733
	3.375	4.000	14.875	1729A-27-33	1802
	3.875	4.000	15.375	1729A-27-37	1871
	4.875	4.500	16.875	1729A-27-47	2024
	5.875	4.500	17.875	1729A-27-57	2162

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1729A-47-13	1802
	1.875	4.000	15.375	1729A-47-17	1871
	2.375	4.500	16.375	1729A-47-23	1955
	2.875	4.500	16.875	1729A-47-27	2024
	3.375	4.500	17.375	1729A-47-33	2093
	3.875	4.500	17.875	1729A-47-37	2162
	4.875	4.500	18.875	1729A-47-47	2300
	5.875	4.500	19.875	1729A-47-57	2438

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1729A-17-13	1357
	1.875	3.000	11.375	1729A-17-17	1441
	2.375	3.500	12.375	1729A-17-23	1510
	2.875	3.500	12.875	1729A-17-27	1595
	3.375	4.000	13.875	1729A-17-33	1664
	3.875	4.000	14.375	1729A-17-37	1733
	4.875	4.500	15.875	1729A-17-47	1886
	5.875	4.500	16.875	1729A-17-57	2024

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1729A-33-13	1595
	1.875	4.000	13.875	1729A-33-17	1664
	2.375	4.000	14.375	1729A-33-23	1733
	2.875	4.500	15.375	1729A-33-27	1817
	3.375	4.500	15.875	1729A-33-33	1886
	3.875	4.500	16.375	1729A-33-37	1955
	4.875	4.500	17.375	1729A-33-47	2093
	5.875	4.500	18.375	1729A-33-57	2231

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1729A-57-13	1940
	1.875	4.500	16.875	1729A-57-17	2024
	2.375	4.500	17.375	1729A-57-23	2093
	2.875	4.500	17.875	1729A-57-27	2162
	3.375	4.500	18.375	1729A-57-33	2231
	3.875	4.500	18.875	1729A-57-37	2300
	4.875	4.500	19.875	1729A-57-47	2438
	5.875	4.500	20.875	1729A-57-57	2576

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1729A-23-13	1441
	1.875	3.500	12.375	1729A-23-17	1510
	2.375	3.500	12.875	1729A-23-23	1579
	2.875	4.000	13.875	1729A-23-27	1664
	3.375	4.000	14.375	1729A-23-33	1733
	3.875	4.000	14.875	1729A-23-37	1802
	4.875	4.500	16.375	1729A-23-47	1955
	5.875	4.500	17.375	1729A-23-57	2093

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1729A-37-13	1664
	1.875	4.000	14.375	1729A-37-17	1733
	2.375	4.500	15.375	1729A-37-23	1817
	2.875	4.500	15.875	1729A-37-27	1886
	3.375	4.500	16.375	1729A-37-33	1955
	3.875	4.500	16.875	1729A-37-37	2024
	4.875	4.500	17.875	1729A-37-47	2162
	5.875	4.500	18.875	1729A-37-57	2300

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
29.47	29
35.47	35

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


17⁷/₈ x 18" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

17⁷/₈ x 18" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1818A-13-13	850
	1.875	3.000	10.875	1818A-13-17	985
	2.375	3.500	11.875	1818A-13-23	951
	2.875	3.500	12.375	1818A-13-27	996
	3.375	4.000	13.375	1818A-13-33	1051
	3.875	4.000	13.875	1818A-13-37	1097
	4.875	4.500	15.375	1818A-13-47	1198
	5.875	4.500	16.375	1818A-13-57	1289

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1818A-27-13	996
	1.875	3.500	12.875	1818A-27-17	1042
	2.375	3.500	13.375	1818A-27-23	107
	2.875	4.000	14.375	1818A-27-27	1142
	3.375	4.000	14.875	1818A-27-33	1188
	3.875	4.000	15.375	1818A-27-37	1234
	4.875	4.500	16.875	1818A-27-47	1334
	5.875	4.500	17.875	1818A-27-57	1426

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1818A-47-13	1188
	1.875	4.000	15.375	1818A-47-17	1234
	2.375	4.500	16.375	1818A-47-23	1289
	2.875	4.500	16.875	1818A-47-27	1334
	3.375	4.500	17.375	1818A-47-33	1380
	3.875	4.500	17.875	1818A-47-37	1426
	4.875	4.500	18.875	1818A-47-47	1517
	5.875	4.500	19.875	1818A-47-57	1608

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1818A-17-13	895
	1.875	3.000	11.375	1818A-17-17	941
	2.375	3.500	12.375	1818A-17-23	996
	2.875	3.500	12.875	1818A-17-27	1042
	3.375	4.000	13.875	1818A-17-33	1097
	3.875	4.000	14.375	1818A-17-37	1142
	4.875	4.500	15.875	1818A-17-47	1243
	5.875	4.500	16.875	1818A-17-57	1334

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1818A-33-13	1051
	1.875	4.000	13.875	1818A-33-17	1097
	2.375	4.000	14.375	1818A-33-23	1142
	2.875	4.500	15.375	1818A-33-27	1198
	3.375	4.500	15.875	1818A-33-33	1243
	3.875	4.500	16.375	1818A-33-37	1289
	4.875	4.500	17.375	1818A-33-47	1380
	5.875	4.500	18.375	1818A-33-57	1471

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1818A-57-13	1279
	1.875	4.500	16.875	1818A-57-17	1334
	2.375	4.500	17.375	1818A-57-23	1380
	2.875	4.500	17.875	1818A-57-27	1426
	3.375	4.500	18.375	1818A-57-33	1471
	3.875	4.500	18.875	1818A-57-37	1517
	4.875	4.500	19.875	1818A-57-47	1608
	5.875	4.500	20.875	1818A-57-57	1699

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1818A-23-13	951
	1.875	3.500	12.375	1818A-23-17	996
	2.375	3.500	12.875	1818A-23-23	1042
	2.875	4.000	13.875	1818A-23-27	1097
	3.375	4.000	14.375	1818A-23-33	1142
	3.875	4.000	14.875	1818A-23-37	1188
	4.875	4.500	16.375	1818A-23-47	1289
	5.875	4.500	17.375	1818A-23-57	1380

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1818A-37-13	1097
	1.875	4.000	14.375	1818A-37-17	1142
	2.375	4.500	15.375	1818A-37-23	1198
	2.875	4.500	15.875	1818A-37-27	1243
	3.375	4.500	16.375	1818A-37-33	1289
	3.875	4.500	16.875	1818A-37-37	1334
	4.875	4.500	17.875	1818A-37-47	1426
	5.875	4.500	18.875	1818A-37-57	1517

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
17.97	18
19.97	20
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed (Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


17⁷/₈ x 20" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

17⁷/₈ x 20" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1820A-13-13	944
	1.875	3.000	10.875	1820A-13-17	995
	2.375	3.500	11.875	1820A-13-23	1056
	2.875	3.500	12.375	1820A-13-27	1107
	3.375	4.000	13.375	1820A-13-33	1168
	3.875	4.000	13.875	1820A-13-37	1219
	4.875	4.500	15.375	1820A-13-47	1331
	5.875	4.500	16.375	1820A-13-57	1432

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1820A-27-13	1107
	1.875	3.500	12.875	1820A-27-17	1157
	2.375	3.500	13.375	1820A-27-23	1208
	2.875	4.000	14.375	1820A-27-27	1269
	3.375	4.000	14.875	1820A-27-33	1320
	3.875	4.000	15.375	1820A-27-37	1371
	4.875	4.500	16.875	1820A-27-47	1483
	5.875	4.500	17.875	1820A-27-57	1584

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1820A-47-13	1320
	1.875	4.000	15.375	1820A-47-17	1371
	2.375	4.500	16.375	1820A-47-23	1432
	2.875	4.500	16.875	1820A-47-27	1483
	3.375	4.500	17.375	1820A-47-33	1533
	3.875	4.500	17.875	1820A-47-37	1584
	4.875	4.500	18.875	1820A-47-47	1685
	5.875	4.500	19.875	1820A-47-57	1786

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1820A-17-13	995
	1.875	3.000	11.375	1820A-17-17	1046
	2.375	3.500	12.375	1820A-17-23	1107
	2.875	3.500	12.875	1820A-17-27	1157
	3.375	4.000	13.875	1820A-17-33	1219
	3.875	4.000	14.375	1820A-17-37	1269
	4.875	4.500	15.875	1820A-17-47	1381
	5.875	4.500	16.875	1820A-17-57	1483

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1820A-33-13	1168
	1.875	4.000	13.875	1820A-33-17	1219
	2.375	4.000	14.375	1820A-33-23	1269
	2.875	4.500	15.375	1820A-33-27	1331
	3.375	4.500	15.875	1820A-33-33	1381
	3.875	4.500	16.375	1820A-33-37	1432
	4.875	4.500	17.375	1820A-33-47	1533
	5.875	4.500	18.375	1820A-33-57	1634

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1820A-57-13	1421
	1.875	4.500	16.875	1820A-57-17	1483
	2.375	4.500	17.375	1820A-57-23	1533
	2.875	4.500	17.875	1820A-57-27	1584
	3.375	4.500	18.375	1820A-57-33	1634
	3.875	4.500	18.875	1820A-57-37	1685
	4.875	4.500	19.875	1820A-57-47	1786
	5.875	4.500	20.875	1820A-57-57	1888

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1820A-23-13	1056
	1.875	3.500	12.375	1820A-23-17	1107
	2.375	3.500	12.875	1820A-23-23	1157
	2.875	4.000	13.875	1820A-23-27	1219
	3.375	4.000	14.375	1820A-23-33	1269
	3.875	4.000	14.875	1820A-23-37	1320
	4.875	4.500	16.375	1820A-23-47	1432
	5.875	4.500	17.375	1820A-23-57	1533

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1820A-37-13	1219
	1.875	4.000	14.375	1820A-37-17	1269
	2.375	4.500	15.375	1820A-37-23	1331
	2.875	4.500	15.875	1820A-37-27	1381
	3.375	4.500	16.375	1820A-37-33	1432
	3.875	4.500	16.875	1820A-37-37	1483
	4.875	4.500	17.875	1820A-37-47	1584
	5.875	4.500	18.875	1820A-37-57	1685

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57

See Items 7 & 8 below.


C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
19.97	20
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.

Ejector Housing Covers provided on both ends of mold when Ejector Bar Length E is nominal length of mold base. Customer to fabricate ejector housing covers for extended ejector bars.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type (For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750 (For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed (Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


17⁷/₈ x 23¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

17⁷/₈ x 23¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1823A-13-13	1109
	1.875	3.000	10.875	1823A-13-17	1169
	2.375	3.500	11.875	1823A-13-23	1241
	2.875	3.500	12.375	1823A-13-27	1300
	3.375	4.000	13.375	1823A-13-33	1372
	3.875	4.000	13.875	1823A-13-37	1432
	4.875	4.500	15.375	1823A-13-47	1563
	5.875	4.500	16.375	1823A-13-57	1682

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1823A-27-13	1300
	1.875	3.500	12.875	1823A-27-17	1360
	2.375	3.500	13.375	1823A-27-23	1419
	2.875	4.000	14.375	1823A-27-27	1491
	3.375	4.000	14.875	1823A-27-33	1551
	3.875	4.000	15.375	1823A-27-37	1610
	4.875	4.500	16.875	1823A-27-47	1742
	5.875	4.500	17.875	1823A-27-57	1861

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1823A-47-13	1551
	1.875	4.000	15.375	1823A-47-17	1610
	2.375	4.500	16.375	1823A-47-23	1682
	2.875	4.500	16.875	1823A-47-27	1742
	3.375	4.500	17.375	1823A-47-33	1801
	3.875	4.500	17.875	1823A-47-37	1861
	4.875	4.500	18.875	1823A-47-47	1980
	5.875	4.500	19.875	1823A-47-57	2099

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1823A-17-13	1169
	1.875	3.000	11.375	1823A-17-17	1228
	2.375	3.500	12.375	1823A-17-23	1300
	2.875	3.500	12.875	1823A-17-27	1360
	3.375	4.000	13.875	1823A-17-33	1432
	3.875	4.000	14.375	1823A-17-37	1491
	4.875	4.500	15.875	1823A-17-47	1623
	5.875	4.500	16.875	1823A-17-57	1742

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1823A-33-13	1372
	1.875	4.000	13.875	1823A-33-17	1432
	2.375	4.000	14.375	1823A-33-23	1491
	2.875	4.500	15.375	1823A-33-27	1563
	3.375	4.500	15.875	1823A-33-33	1623
	3.875	4.500	16.375	1823A-33-37	1682
	4.875	4.500	17.375	1823A-33-47	1801
	5.875	4.500	18.375	1823A-33-57	1920

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1823A-57-13	1670
	1.875	4.500	16.875	1823A-57-17	1742
	2.375	4.500	17.375	1823A-57-23	1801
	2.875	4.500	17.875	1823A-57-27	1861
	3.375	4.500	18.375	1823A-57-33	1920
	3.875	4.500	18.875	1823A-57-37	1980
	4.875	4.500	19.875	1823A-57-47	2099
	5.875	4.500	20.875	1823A-57-57	2218

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1823A-23-13	1241
	1.875	3.500	12.375	1823A-23-17	1300
	2.375	3.500	12.875	1823A-23-23	1360
	2.875	4.000	13.875	1823A-23-27	1432
	3.375	4.000	14.375	1823A-23-33	1491
	3.875	4.000	14.875	1823A-23-37	1551
	4.875	4.500	16.375	1823A-23-47	1682
	5.875	4.500	17.375	1823A-23-57	1801

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1823A-37-13	1432
	1.875	4.000	14.375	1823A-37-17	1491
	2.375	4.500	15.375	1823A-37-23	1563
	2.875	4.500	15.875	1823A-37-27	1623
	3.375	4.500	16.375	1823A-37-33	1682
	3.875	4.500	16.875	1823A-37-37	1842
	4.875	4.500	17.875	1823A-37-47	1861
	5.875	4.500	18.875	1823A-37-57	1980

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.47	23
25.97	26
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


17⁷/₈ x 26" A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

17⁷/₈ x 26" A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1826A-13-13	1227
	1.875	3.000	10.875	1826A-13-17	1293
	2.375	3.500	11.875	1826A-13-23	1373
	2.875	3.500	12.375	1826A-13-27	1439
	3.375	4.000	13.375	1826A-13-33	1518
	3.875	4.000	13.875	1826A-13-37	1584
	4.875	4.500	15.375	1826A-13-47	1730
	5.875	4.500	16.375	1826A-13-57	1861

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1826A-27-13	1439
	1.875	3.500	12.875	1826A-27-17	1504
	2.375	3.500	13.375	1826A-27-23	1570
	2.875	4.000	14.375	1826A-27-27	1650
	3.375	4.000	14.875	1826A-27-33	1716
	3.875	4.000	15.375	1826A-27-37	1782
	4.875	4.500	16.875	1826A-27-47	1927
	5.875	4.500	17.875	1826A-27-57	2059

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1826A-47-13	1716
	1.875	4.000	15.375	1826A-47-17	1782
	2.375	4.500	16.375	1826A-47-23	1861
	2.875	4.500	16.875	1826A-47-27	1927
	3.375	4.500	17.375	1826A-47-33	1993
	3.875	4.500	17.875	1826A-47-37	2059
	4.875	4.500	18.875	1826A-47-47	2190
	5.875	4.500	19.875	1826A-47-57	2322

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1826A-17-13	1293
	1.875	3.000	11.375	1826A-17-17	1359
	2.375	3.500	12.375	1826A-17-23	1439
	2.875	3.500	12.875	1826A-17-27	1504
	3.375	4.000	13.875	1826A-17-33	1584
	3.875	4.000	14.375	1826A-17-37	1650
	4.875	4.500	15.875	1826A-17-47	1795
	5.875	4.500	16.875	1826A-17-57	1927

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1826A-33-13	1518
	1.875	4.000	13.875	1826A-33-17	1584
	2.375	4.000	14.375	1826A-33-23	1650
	2.875	4.500	15.375	1826A-33-27	1730
	3.375	4.500	15.875	1826A-33-33	1795
	3.875	4.500	16.375	1826A-33-37	1861
	4.875	4.500	17.375	1826A-33-47	1993
	5.875	4.500	18.375	1826A-33-57	2125

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1826A-57-13	1847
	1.875	4.500	16.875	1826A-57-17	1927
	2.375	4.500	17.375	1826A-57-23	1993
	2.875	4.500	17.875	1826A-57-27	2059
	3.375	4.500	18.375	1826A-57-33	2125
	3.875	4.500	18.875	1826A-57-37	2190
	4.875	4.500	19.875	1826A-57-47	2322
	5.875	4.500	20.875	1826A-57-57	2454

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1826A-23-13	1373
	1.875	3.500	12.375	1826A-23-17	1439
	2.375	3.500	12.875	1826A-23-23	1504
	2.875	4.000	13.875	1826A-23-27	1584
	3.375	4.000	14.375	1826A-23-33	1650
	3.875	4.000	14.875	1826A-23-37	1716
	4.875	4.500	16.375	1826A-23-47	1861
	5.875	4.500	17.375	1826A-23-57	1993

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1826A-37-13	1584
	1.875	4.000	14.375	1826A-37-17	1650
	2.375	4.500	15.375	1826A-37-23	1730
	2.875	4.500	15.875	1826A-37-27	1795
	3.375	4.500	16.375	1826A-37-33	1861
	3.875	4.500	16.875	1826A-37-37	1927
	4.875	4.500	17.875	1826A-37-47	2059
	5.875	4.500	18.875	1826A-37-57	2190

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
25.97	26
29.47	29
35.47	35

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


17⁷/₈ x 29¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

17⁷/₈ x 29¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1829A-13-13	1392
	1.875	3.000	10.875	1829A-13-17	1467
	2.375	3.500	11.875	1829A-13-23	1558
	2.875	3.500	12.375	1829A-13-27	1632
	3.375	4.000	13.375	1829A-13-33	1723
	3.875	4.000	13.875	1829A-13-37	1797
	4.875	4.500	15.375	1829A-13-47	1962
	5.875	4.500	16.375	1829A-13-57	2112

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1829A-27-13	1632
	1.875	3.500	12.875	1829A-27-17	1707
	2.375	3.500	13.375	1829A-27-23	1782
	2.875	4.000	14.375	1829A-27-27	1872
	3.375	4.000	14.875	1829A-27-33	1947
	3.875	4.000	15.375	1829A-27-37	2021
	4.875	4.500	16.875	1829A-27-47	2186
	5.875	4.500	17.875	1829A-27-57	2336

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1829A-47-13	1947
	1.875	4.000	15.375	1829A-47-17	2021
	2.375	4.500	16.375	1829A-47-23	2112
	2.875	4.500	16.875	1829A-47-27	2186
	3.375	4.500	17.375	1829A-47-33	2261
	3.875	4.500	17.875	1829A-47-37	2336
	4.875	4.500	18.875	1829A-47-47	2485
	5.875	4.500	19.875	1829A-47-57	2635

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1829A-17-13	1467
	1.875	3.000	11.375	1829A-17-17	1542
	2.375	3.500	12.375	1829A-17-23	1632
	2.875	3.500	12.875	1829A-17-27	1707
	3.375	4.000	13.875	1829A-17-33	1797
	3.875	4.000	14.375	1829A-17-37	1872
	4.875	4.500	15.875	1829A-17-47	2037
	5.875	4.500	16.875	1829A-17-57	2186

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1829A-33-13	1723
	1.875	4.000	13.875	1829A-33-17	1797
	2.375	4.000	14.375	1829A-33-23	1872
	2.875	4.500	15.375	1829A-33-27	1962
	3.375	4.500	15.875	1829A-33-33	2037
	3.875	4.500	16.375	1829A-33-37	2112
	4.875	4.500	17.375	1829A-33-47	2261
	5.875	4.500	18.375	1829A-33-57	2410

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1829A-57-13	2096
	1.875	4.500	16.875	1829A-57-17	2186
	2.375	4.500	17.375	1829A-57-23	2261
	2.875	4.500	17.875	1829A-57-27	2336
	3.375	4.500	18.375	1829A-57-33	2410
	3.875	4.500	18.875	1829A-57-37	2485
	4.875	4.500	19.875	1829A-57-47	2635
	5.875	4.500	20.875	1829A-57-57	2784

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1829A-23-13	1558
	1.875	3.500	12.375	1829A-23-17	1632
	2.375	3.500	12.875	1829A-23-23	1707
	2.875	4.000	13.875	1829A-23-27	1797
	3.375	4.000	14.375	1829A-23-33	1872
	3.875	4.000	14.875	1829A-23-37	1947
	4.875	4.500	16.375	1829A-23-47	2112
	5.875	4.500	17.375	1829A-23-57	2261

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1829A-37-13	1797
	1.875	4.000	14.375	1829A-37-17	1872
	2.375	4.500	15.375	1829A-37-23	1962
	2.875	4.500	15.875	1829A-37-27	2037
	3.375	4.500	16.375	1829A-37-33	2112
	3.875	4.500	16.875	1829A-37-37	2186
	4.875	4.500	17.875	1829A-37-47	2336
	5.875	4.500	18.875	1829A-37-57	2485

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


17⁷/₈ x 35¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)


B-Series Assembly




Steel Configurations available in:

Steel


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

17⁷/₈ x 35¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1835A-13-13	1676
	1.875	3.000	10.875	1835A-13-17	1766
	2.375	3.500	11.875	1835A-13-23	1874
	2.875	3.500	12.375	1835A-13-27	1964
	3.375	4.000	13.375	1835A-13-33	2073
	3.875	4.000	13.875	1835A-13-37	2163
	4.875	4.500	15.375	1835A-13-47	2361
	5.875	4.500	16.375	1835A-13-57	2541

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1835A-27-13	1964
	1.875	3.500	12.875	1835A-27-17	2054
	2.375	3.500	13.375	1835A-27-23	2144
	2.875	4.000	14.375	1835A-27-27	2253
	3.375	4.000	14.875	1835A-27-33	2343
	3.875	4.000	15.375	1835A-27-37	2433
	4.875	4.500	16.875	1835A-27-47	2631
	5.875	4.500	17.875	1835A-27-57	2811

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1835A-47-13	2343
	1.875	4.000	15.375	1835A-47-17	2433
	2.375	4.500	16.375	1835A-47-23	2541
	2.875	4.500	16.875	1835A-47-27	2631
	3.375	4.500	17.375	1835A-47-33	2721
	3.875	4.500	17.875	1835A-47-37	2811
	4.875	4.500	18.875	1835A-47-47	2991
	5.875	4.500	19.875	1835A-47-57	3170

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1835A-17-13	1766
	1.875	3.000	11.375	1835A-17-17	1855
	2.375	3.500	12.375	1835A-17-23	1964
	2.875	3.500	12.875	1835A-17-27	2054
	3.375	4.000	13.875	1835A-17-33	2163
	3.875	4.000	14.375	1835A-17-37	2253
	4.875	4.500	15.875	1835A-17-47	2451
	5.875	4.500	16.875	1835A-17-57	2631

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1835A-33-13	2073
	1.875	4.000	13.875	1835A-33-17	2163
	2.375	4.000	14.375	1835A-33-23	2253
	2.875	4.500	15.375	1835A-33-27	2361
	3.375	4.500	15.875	1835A-33-33	2451
	3.875	4.500	16.375	1835A-33-37	2541
	4.875	4.500	17.375	1835A-33-47	2721
	5.875	4.500	18.375	1835A-33-57	2901

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1835A-57-13	2522
	1.875	4.500	16.875	1835A-57-17	2631
	2.375	4.500	17.375	1835A-57-23	2721
	2.875	4.500	17.875	1835A-57-27	2811
	3.375	4.500	18.375	1835A-57-33	2901
	3.875	4.500	18.875	1835A-57-37	2991
	4.875	4.500	19.875	1835A-57-47	3170
	5.875	4.500	20.875	1835A-57-57	3350

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1835A-23-13	1874
	1.875	3.500	12.375	1835A-23-17	1964
	2.375	3.500	12.875	1835A-23-23	2054
	2.875	4.000	13.875	1835A-23-27	2163
	3.375	4.000	14.375	1835A-23-33	2253
	3.875	4.000	14.875	1835A-23-37	2343
	4.875	4.500	16.375	1835A-23-47	2541
	5.875	4.500	17.375	1835A-23-57	2721

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1835A-37-13	2163
	1.875	4.000	14.375	1835A-37-17	2253
	2.375	4.500	15.375	1835A-37-23	2361
	2.875	4.500	15.875	1835A-37-27	2451
	3.375	4.500	16.375	1835A-37-33	2541
	3.875	4.500	16.875	1835A-37-37	2631
	4.875	4.500	17.875	1835A-37-47	2811
	5.875	4.500	18.875	1835A-37-57	2991

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


19¹/₂ x 23³/₄ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




B-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

19¹/₂ x 23³/₄ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1924A-13-13	1221
	1.875	3.000	10.875	1924A-13-17	1287
	2.375	3.500	11.875	1924A-13-23	1365
	2.875	3.500	12.375	1924A-13-27	1430
	3.375	4.000	13.375	1924A-13-33	1509
	3.875	4.000	13.875	1924A-13-37	1574
	4.875	4.500	15.375	1924A-13-47	1718
	5.875	4.500	16.375	1924A-13-57	1849

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1924A-27-13	1430
	1.875	3.500	12.875	1924A-27-17	1496
	2.375	3.500	13.375	1924A-27-23	1562
	2.875	4.000	14.375	1924A-27-27	1640
	3.375	4.000	14.875	1924A-27-33	1705
	3.875	4.000	15.375	1924A-27-37	1771
	4.875	4.500	16.875	1924A-27-47	1915
	5.875	4.500	17.875	1924A-27-57	2046

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1924A-47-13	1705
	1.875	4.000	15.375	1924A-47-17	1771
	2.375	4.500	16.375	1924A-47-23	1849
	2.875	4.500	16.875	1924A-47-27	1915
	3.375	4.500	17.375	1924A-47-33	1980
	3.875	4.500	17.875	1924A-47-37	2046
	4.875	4.500	18.875	1924A-47-47	2177
	5.875	4.500	19.875	1924A-47-57	2308

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1924A-17-13	1287
	1.875	3.000	11.375	1924A-17-17	1352
	2.375	3.500	12.375	1924A-17-23	1430
	2.875	3.500	12.875	1924A-17-27	1496
	3.375	4.000	13.875	1924A-17-33	1574
	3.875	4.000	14.375	1924A-17-37	1640
	4.875	4.500	15.875	1924A-17-47	1784
	5.875	4.500	16.875	1924A-17-57	1915

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1924A-33-13	1509
	1.875	4.000	13.875	1924A-33-17	1574
	2.375	4.000	14.375	1924A-33-23	1640
	2.875	4.500	15.375	1924A-33-27	1718
	3.375	4.500	15.875	1924A-33-33	1784
	3.875	4.500	16.375	1924A-33-37	1849
	4.875	4.500	17.375	1924A-33-47	1980
	5.875	4.500	18.375	1924A-33-57	2112

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1924A-57-13	1837
	1.875	4.500	16.875	1924A-57-17	1915
	2.375	4.500	17.375	1924A-57-23	1980
	2.875	4.500	17.875	1924A-57-27	2046
	3.375	4.500	18.375	1924A-57-33	2112
	3.875	4.500	18.875	1924A-57-37	2177
	4.875	4.500	19.875	1924A-57-47	2308
	5.875	4.500	20.875	1924A-57-57	2440

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1924A-23-13	1365
	1.875	3.500	12.375	1924A-23-17	1430
	2.375	3.500	12.875	1924A-23-23	1496
	2.875	4.000	13.875	1924A-23-27	1574
	3.375	4.000	14.375	1924A-23-33	1640
	3.875	4.000	14.875	1924A-23-37	1705
	4.875	4.500	16.375	1924A-23-47	1849
	5.875	4.500	17.375	1924A-23-57	1980

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1924A-37-13	1574
	1.875	4.000	14.375	1924A-37-17	1640
	2.375	4.500	15.375	1924A-37-23	1718
	2.875	4.500	15.875	1924A-37-27	1784
	3.375	4.500	16.375	1924A-37-33	1849
	3.875	4.500	16.875	1924A-37-37	1915
	4.875	4.500	17.875	1924A-37-47	2046
	5.875	4.500	18.875	1924A-37-57	2177

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.72	24
29.47	29
35.47	35

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


19¹/₂ x 29¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

19¹/₂ x 29¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1929A-13-13	1516
	1.875	3.000	10.875	1929A-13-17	1598
	2.375	3.500	11.875	1929A-13-23	1695
	2.875	3.500	12.375	1929A-13-27	1777
	3.375	4.000	13.375	1929A-13-33	1874
	3.875	4.000	13.875	1929A-13-37	1955
	4.875	4.500	15.375	1929A-13-47	2134
	5.875	4.500	16.375	1929A-13-57	2297

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1929A-27-13	1777
	1.875	3.500	12.875	1929A-27-17	1858
	2.375	3.500	13.375	1929A-27-23	1849
	2.875	4.000	14.375	1929A-27-27	2037
	3.375	4.000	14.875	1929A-27-33	2118
	3.875	4.000	15.375	1929A-27-37	2200
	4.875	4.500	16.875	1929A-27-47	2378
	5.875	4.500	17.875	1929A-27-57	2541

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1929A-47-13	2118
	1.875	4.000	15.375	1929A-47-17	2200
	2.375	4.500	16.375	1929A-47-23	2297
	2.875	4.500	16.875	1929A-47-27	2378
	3.375	4.500	17.375	1929A-47-33	2460
	3.875	4.500	17.875	1929A-47-37	2541
	4.875	4.500	18.875	1929A-47-47	2704
	5.875	4.500	19.875	1929A-47-57	2867

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1929A-17-13	1598
	1.875	3.000	11.375	1929A-17-17	1679
	2.375	3.500	12.375	1929A-17-23	1777
	2.875	3.500	12.875	1929A-17-27	1858
	3.375	4.000	13.875	1929A-17-33	1955
	3.875	4.000	14.375	1929A-17-37	2037
	4.875	4.500	15.875	1929A-17-47	2215
	5.875	4.500	16.875	1929A-17-57	2378

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1929A-33-13	1874
	1.875	4.000	13.875	1929A-33-17	1955
	2.375	4.000	14.375	1929A-33-23	2037
	2.875	4.500	15.375	1929A-33-27	2134
	3.375	4.500	15.875	1929A-33-33	2215
	3.875	4.500	16.375	1929A-33-37	2297
	4.875	4.500	17.375	1929A-33-47	2460
	5.875	4.500	18.375	1929A-33-57	2623

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1929A-57-13	2281
	1.875	4.500	16.875	1929A-57-17	2378
	2.375	4.500	17.375	1929A-57-23	2460
	2.875	4.500	17.875	1929A-57-27	2541
	3.375	4.500	18.375	1929A-57-33	2623
	3.875	4.500	18.875	1929A-57-37	2704
	4.875	4.500	19.875	1929A-57-47	2867
	5.875	4.500	20.875	1929A-57-57	3030

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1929A-23-13	1695
	1.875	3.500	12.375	1929A-23-17	1777
	2.375	3.500	12.875	1929A-23-23	1858
	2.875	4.000	13.875	1929A-23-27	1955
	3.375	4.000	14.375	1929A-23-33	2037
	3.875	4.000	14.875	1929A-23-37	2118
	4.875	4.500	16.375	1929A-23-47	2297
	5.875	4.500	17.375	1929A-23-57	2460

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1929A-37-13	1955
	1.875	4.000	14.375	1929A-37-17	2037
	2.375	4.500	15.375	1929A-37-23	2134
	2.875	4.500	15.875	1929A-37-27	2215
	3.375	4.500	16.375	1929A-37-33	2297
	3.875	4.500	16.875	1929A-37-37	2378
	4.875	4.500	17.875	1929A-37-47	2541
	5.875	4.500	18.875	1929A-37-57	2704

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

19¹/₂ x 35¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

19¹/₂ x 35¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.375	1935A-13-13	1825
	1.875	3.000	10.875	1935A-13-17	1923
	2.375	3.500	11.875	1935A-13-23	2040
	2.875	3.500	12.375	1935A-13-27	2138
	3.375	4.000	13.375	1935A-13-33	2255
	3.875	4.000	13.875	1935A-13-37	2353
	4.875	4.500	15.375	1935A-13-47	2568
	5.875	4.500	16.375	1935A-13-57	2764

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.375	1935A-27-13	2138
	1.875	3.500	12.875	1935A-27-17	2236
	2.375	3.500	13.375	1935A-27-23	2334
	2.875	4.000	14.375	1935A-27-27	2451
	3.375	4.000	14.875	1935A-27-33	2549
	3.875	4.000	15.375	1935A-27-37	2647
	4.875	4.500	16.875	1935A-27-47	2862
	5.875	4.500	17.875	1935A-27-57	3058

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	14.875	1935A-47-13	2549
	1.875	4.000	15.375	1935A-47-17	2647
	2.375	4.500	16.375	1935A-47-23	2764
	2.875	4.500	16.875	1935A-47-27	2862
	3.375	4.500	17.375	1935A-47-33	2960
	3.875	4.500	17.875	1935A-47-37	3058
	4.875	4.500	18.875	1935A-47-47	3254
	5.875	4.500	19.875	1935A-47-57	3450

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	10.875	1935A-17-13	1923
	1.875	3.000	11.375	1935A-17-17	2021
	2.375	3.500	12.375	1935A-17-23	2138
	2.875	3.500	12.875	1935A-17-27	2236
	3.375	4.000	13.875	1935A-17-33	2353
	3.875	4.000	14.375	1935A-17-37	2451
	4.875	4.500	15.875	1935A-17-47	2666
	5.875	4.500	16.875	1935A-17-57	2862

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.375	1935A-33-13	2255
	1.875	4.000	13.875	1935A-33-17	2353
	2.375	4.000	14.375	1935A-33-23	2451
	2.875	4.500	15.375	1935A-33-27	2568
	3.375	4.500	15.875	1935A-33-33	2666
	3.875	4.500	16.375	1935A-33-37	2764
	4.875	4.500	17.375	1935A-33-47	2960
	5.875	4.500	18.375	1935A-33-57	3156

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	15.875	1935A-57-13	2745
	1.875	4.500	16.875	1935A-57-17	2862
	2.375	4.500	17.375	1935A-57-23	2960
	2.875	4.500	17.875	1935A-57-27	3058
	3.375	4.500	18.375	1935A-57-33	3156
	3.875	4.500	18.875	1935A-57-37	3254
	4.875	4.500	19.875	1935A-57-47	3450
	5.875	4.500	20.875	1935A-57-57	3646

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	11.875	1935A-23-13	2040
	1.875	3.500	12.375	1935A-23-17	2138
	2.375	3.500	12.875	1935A-23-23	2236
	2.875	4.000	13.875	1935A-23-27	2353
	3.375	4.000	14.375	1935A-23-33	2451
	3.875	4.000	14.875	1935A-23-37	2549
	4.875	4.500	16.375	1935A-23-47	2764
	5.875	4.500	17.375	1935A-23-57	2960

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	13.875	1935A-37-13	2353
	1.875	4.000	14.375	1935A-37-17	2451
	2.375	4.500	15.375	1935A-37-23	2568
	2.875	4.500	15.875	1935A-37-27	2666
	3.375	4.500	16.375	1935A-37-33	2764
	3.875	4.500	16.875	1935A-37-37	2862
	4.875	4.500	17.875	1935A-37-47	3058
	5.875	4.500	18.875	1935A-37-57	3254

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

23³/₄ x 23³/₄ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series
and T-Series Mold Bases, see pages 173-198.)

**Steel
Configurations
available in:**



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

23³/₄ x 23³/₄ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.875	2424A-13-13	1562
	1.875	3.000	11.375	2424A-13-17	1642
	2.375	3.500	12.375	2424A-13-23	1734
	2.875	3.500	12.875	2424A-13-27	1814
	3.375	4.000	13.875	2424A-13-33	1907
	3.875	4.000	14.375	2424A-13-37	1987
	4.875	4.500	15.875	2424A-13-47	2159
	5.875	4.500	16.875	2424A-13-57	2319

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.875	2424A-27-13	1814
	1.875	3.500	13.375	2424A-27-17	1894
	2.375	3.500	13.875	2424A-27-23	1974
	2.875	4.000	14.875	2424A-27-27	2066
	3.375	4.000	15.375	2424A-27-33	2146
	3.875	4.000	15.875	2424A-27-37	2226
	4.875	4.500	17.375	2424A-27-47	2399
	5.875	4.500	18.375	2424A-27-57	2558

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	15.375	2424A-47-13	2146
	1.875	4.000	15.875	2424A-47-17	2226
	2.375	4.500	16.875	2424A-47-23	2319
	2.875	4.500	17.375	2424A-47-27	2399
	3.375	4.500	17.875	2424A-47-33	2479
	3.875	4.500	18.375	2424A-47-37	2558
	4.875	4.500	19.375	2424A-47-47	2718
	5.875	4.500	20.375	2424A-47-57	2878

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	11.375	2424A-17-13	1642
	1.875	3.000	11.875	2424A-17-17	1722
	2.375	3.500	12.875	2424A-17-23	1814
	2.875	3.500	13.375	2424A-17-27	1894
	3.375	4.000	14.375	2424A-17-33	1987
	3.875	4.000	14.875	2424A-17-37	2066
	4.875	4.500	16.375	2424A-17-47	2239
	5.875	4.500	17.375	2424A-17-57	2399

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.875	2424A-33-13	1907
	1.875	4.000	14.375	2424A-33-17	1987
	2.375	4.000	14.875	2424A-33-23	2066
	2.875	4.500	15.875	2424A-33-27	2159
	3.375	4.500	16.375	2424A-33-33	2239
	3.875	4.500	16.875	2424A-33-37	2319
	4.875	4.500	17.875	2424A-33-47	2479
	5.875	4.500	18.875	2424A-33-57	2638

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	16.375	2424A-57-13	2306
	1.875	4.500	17.375	2424A-57-17	2399
	2.375	4.500	17.875	2424A-57-23	2479
	2.875	4.500	18.375	2424A-57-27	2558
	3.375	4.500	18.875	2424A-57-33	2638
	3.875	4.500	19.375	2424A-57-37	2718
	4.875	4.500	20.375	2424A-57-47	1878
	5.875	4.500	21.375	2424A-57-57	3038

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	12.375	2424A-23-13	1734
	1.875	3.500	12.875	2424A-23-17	1814
	2.375	3.500	13.375	2424A-23-23	1894
	2.875	4.000	14.375	2424A-23-27	1987
	3.375	4.000	14.875	2424A-23-33	2066
	3.875	4.000	15.375	2424A-23-37	2146
	4.875	4.500	16.875	2424A-23-47	2319
	5.875	4.500	17.875	2424A-23-57	2479

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	14.375	2424A-37-13	1987
	1.875	4.000	14.875	2424A-37-17	2066
	2.375	4.500	15.875	2424A-37-23	2159
	2.875	4.500	16.375	2424A-37-27	2239
	3.375	4.500	16.875	2424A-37-33	2319
	3.875	4.500	17.375	2424A-37-37	2399
	4.875	4.500	18.375	2424A-37-47	2558
	5.875	4.500	19.375	2424A-37-57	2718

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
23.72	24
29.47	29
35.47	35

See Item 6 below.





WHEN ORDERING, PLEASE SPECIFY:


- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

23³/₄ x 29¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections



(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

Steel Configurations available in:



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

23³/₄ x 29¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.875	2429A-13-13	1940
	1.875	3.000	11.375	2429A-13-17	2039
	2.375	3.500	12.375	2429A-13-23	2154
	2.875	3.500	12.875	2429A-13-27	2253
	3.375	4.000	13.875	2429A-13-33	2368
	3.875	4.000	14.375	2429A-13-37	2467
	4.875	4.500	15.875	2429A-13-47	2681
	5.875	4.500	16.875	2429A-13-57	2880

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.875	2429A-27-13	2253
	1.875	3.500	13.375	2429A-27-17	2352
	2.375	3.500	13.875	2429A-27-23	2452
	2.875	4.000	14.875	2429A-27-27	2567
	3.375	4.000	15.375	2429A-27-33	2666
	3.875	4.000	15.875	2429A-27-37	2765
	4.875	4.500	17.375	2429A-27-47	2979
	5.875	4.500	18.375	2429A-27-57	3178

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	15.375	2429A-47-13	2666
	1.875	4.000	15.875	2429A-47-17	2765
	2.375	4.500	16.875	2429A-47-23	2880
	2.875	4.500	17.375	2429A-47-27	2979
	3.375	4.500	17.875	2429A-47-33	3078
	3.875	4.500	18.375	2429A-47-37	3178
	4.875	4.500	19.375	2429A-47-47	3376
	5.875	4.500	20.375	2429A-47-57	3575

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	11.375	2429A-17-13	2039
	1.875	3.000	11.875	2429A-17-17	2138
	2.375	3.500	12.875	2429A-17-23	2253
	2.875	3.500	13.375	2429A-17-27	2352
	3.375	4.000	14.375	2429A-17-33	2467
	3.875	4.000	14.875	2429A-17-37	2567
	4.875	4.500	16.375	2429A-17-47	2781
	5.875	4.500	17.375	2429A-17-57	2979

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.875	2429A-33-13	2368
	1.875	4.000	14.375	2429A-33-17	2467
	2.375	4.000	14.875	2429A-33-23	2567
	2.875	4.500	15.875	2429A-33-27	2681
	3.375	4.500	16.375	2429A-33-33	2781
	3.875	4.500	16.875	2429A-33-37	2880
	4.875	4.500	17.875	2429A-33-47	3078
	5.875	4.500	18.875	2429A-33-57	3277

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	16.375	2429A-57-13	2864
	1.875	4.500	17.375	2429A-57-17	2979
	2.375	4.500	17.875	2429A-57-23	3078
	2.875	4.500	18.375	2429A-57-27	3178
	3.375	4.500	18.875	2429A-57-33	3277
	3.875	4.500	19.375	2429A-57-37	3376
	4.875	4.500	20.375	2429A-57-47	3575
	5.875	4.500	21.375	2429A-57-57	3773

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	12.375	2429A-23-13	2154
	1.875	3.500	12.875	2429A-23-17	2253
	2.375	3.500	13.375	2429A-23-23	2352
	2.875	4.000	14.375	2429A-23-27	2467
	3.375	4.000	14.875	2429A-23-33	2567
	3.875	4.000	15.375	2429A-23-37	2666
	4.875	4.500	16.875	2429A-23-47	2880
	5.875	4.500	17.875	2429A-23-57	3078

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	14.375	2429A-37-13	2467
	1.875	4.000	14.875	2429A-37-17	2567
	2.375	4.500	15.875	2429A-37-23	2681
	2.875	4.500	16.375	2429A-37-27	2781
	3.375	4.500	16.875	2429A-37-33	2880
	3.875	4.500	17.375	2429A-37-37	2979
	4.875	4.500	18.375	2429A-37-47	3178
	5.875	4.500	19.375	2429A-37-57	3376

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
29.47	29
35.47	35

See Item 6 below.




WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment


23³/₄ x 35¹/₂ A-Series Mold Bases

See opposite page for general dimensions, ejector stroke data, locating rings, sprue bushings, ejector bar lengths and other ordering information.




Mold Base Selections

A-Series Assembly




(For X-Series Stripper Plate, AX-Series and T-Series Mold Bases, see pages 173-198.)

B-Series Assembly




Steel Configurations available in:


No. 1 Steel Assembly



No. 3 Steel Assembly



No. 7 Steel Assembly



Other steel combinations also available. (Ejector Plates and Housings are No. 1 Steel, unless otherwise specified.) For additional Steel information, see page 42.

23³/₄ x 35¹/₂ A-Series Mold Bases

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.375 (1-3/8)	1.375	3.000	10.875	2435A-13-13	2334
	1.875	3.000	11.375	2435A-13-17	2454
	2.375	3.500	12.375	2435A-13-23	2592
	2.875	3.500	12.875	2435A-13-27	2711
	3.375	4.000	13.875	2435A-13-33	2850
	3.875	4.000	14.375	2435A-13-37	2969
	4.875	4.500	15.875	2435A-13-47	3227
	5.875	4.500	16.875	2435A-13-57	3466

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.875 (2-7/8)	1.375	3.500	12.875	2435A-27-13	2711
	1.875	3.500	13.375	2435A-27-17	2831
	2.375	3.500	13.875	2435A-27-23	2950
	2.875	4.000	14.875	2435A-27-27	3089
	3.375	4.000	15.375	2435A-27-33	3208
	3.875	4.000	15.875	2435A-27-37	3327
	4.875	4.500	17.375	2435A-27-47	3585
	5.875	4.500	18.375	2435A-27-57	3824

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
4.875 (4-7/8)	1.375	4.000	15.375	2435A-47-13	3208
	1.875	4.000	15.875	2435A-47-17	3327
	2.375	4.500	16.875	2435A-47-23	3466
	2.875	4.500	17.375	2435A-47-27	3585
	3.375	4.500	17.875	2435A-47-33	3705
	3.875	4.500	18.375	2435A-47-37	3824
	4.875	4.500	19.375	2435A-47-47	4063
	5.875	4.500	20.375	2435A-47-57	4302

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
1.875 (1-7/8)	1.375	3.000	11.375	2435A-17-13	2454
	1.875	3.000	11.875	2435A-17-17	2573
	2.375	3.500	12.875	2435A-17-23	2711
	2.875	3.500	13.375	2435A-17-27	2831
	3.375	4.000	14.375	2435A-17-33	2969
	3.875	4.000	14.875	2435A-17-37	3089
	4.875	4.500	16.375	2435A-17-47	3346
	5.875	4.500	17.375	2435A-17-57	3585

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.375 (3-3/8)	1.375	4.000	13.875	2435A-33-13	2850
	1.875	4.000	14.375	2435A-33-17	2969
	2.375	4.000	14.875	2435A-33-23	3089
	2.875	4.500	15.875	2435A-33-27	3227
	3.375	4.500	16.375	2435A-33-33	3346
	3.875	4.500	16.875	2435A-33-37	3466
	4.875	4.500	17.875	2435A-33-47	3705
	5.875	4.500	18.875	2435A-33-57	3943

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
5.875 (5-7/8)	1.375	4.000	16.375	2435A-57-13	3447
	1.875	4.500	17.375	2435A-57-17	3585
	2.375	4.500	17.875	2435A-57-23	3705
	2.875	4.500	18.375	2435A-57-27	3824
	3.375	4.500	18.875	2435A-57-33	3943
	3.875	4.500	19.375	2435A-57-37	4063
	4.875	4.500	20.375	2435A-57-47	4302
	5.875	4.500	21.375	2435A-57-57	4541

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
2.375 (2-3/8)	1.375	3.500	12.375	2435A-23-13	2592
	1.875	3.500	12.875	2435A-23-17	2711
	2.375	3.500	13.375	2435A-23-23	2831
	2.875	4.000	14.375	2435A-23-27	2969
	3.375	4.000	14.875	2435A-23-33	3089
	3.875	4.000	15.375	2435A-23-37	3208
	4.875	4.500	16.875	2435A-23-47	3466
	5.875	4.500	17.875	2435A-23-57	3705

A	B	C	H	ASSEMBLY ITEM NO.	NET WT.
3.875 (3-7/8)	1.375	4.000	14.375	2435A-37-13	2969
	1.875	4.000	14.875	2435A-37-17	3089
	2.375	4.500	15.875	2435A-37-23	3227
	2.875	4.500	16.375	2435A-37-27	3346
	3.375	4.500	16.875	2435A-37-33	3466
	3.875	4.500	17.375	2435A-37-37	3585
	4.875	4.500	18.375	2435A-37-47	3824
	5.875	4.500	19.375	2435A-37-57	4063

Other plate thickness, riser height and ejector bar length options available

CP TOP CLAMP PLATE	SU SUPPORT PLATE	BCP BOTTOM CLAMP PLATE	PLATE THICKNESS NO.
THICKNESS	THICKNESS	THICKNESS	
0.875	0.875	0.875	7
1.375	1.375	1.375	13
1.875	1.875	1.875	17
2.375	2.375	2.375	23
2.875	2.875	2.875	27
3.375	3.375	3.375	33
3.875	3.875	3.875	37
4.875	4.875	4.875	47
5.875	5.875	5.875	57


See Items 7 & 8 below.

C RISER		
C RISER HEIGHT	RISER HEIGHT NO.	S MAX. STROKE OF EJECTOR BAR
3.000	30	1.063
3.500	35	1.563
4.000	40	2.063
4.500	45	2.563
5.000	50	3.063
5.500	55	3.563
6.000	60	4.063

See Item 8 below.

EB EJECTOR BAR	
E LENGTH NOM.	EJECTOR BAR LENGTH NO.
35.47	35

See Item 6 below.



WHEN ORDERING, PLEASE SPECIFY:

- Quantity
- Assembly Item Number (For B-Series, replace A with B)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other CP Top Clamp Plate or SU Support Plate thicknesses as needed
(Recommended thicknesses are highlighted in yellow)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a Three-Piece Housing (for other steels, please specify)
- Optional and special features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

Available in 43 Nominal Sizes

The DME B-Series Mold Base offers economy of design without sacrificing the high-quality steel and workmanship of the A-Series. The two mold bases are identical except for the B-Series "two-plate" design. A thicker A-plate acts as both Top Clamping Plate and upper Cavity Plate. Similarly, a thicker B-plate eliminates the need for a Support Plate on the B side of the mold. The B-Series is sometimes specified for single-cavity plastics molds or die-cast dies where the cavity and core are machined directly into the Cavity Plates; or where overall mold height is critical. As a two-plate design, cavity inserts have to be installed into "blind" pockets.

Instructions for ordering:

B-Series Mold Bases are available in the same variety of steels, sizes and plate combinations as the A-Series. Since the clamp slots are located in the A-plate, the recommended minimum A-plate thickness for a B-Series Mold Base is 1.875. If an A-plate less than 1.875 is desired, exact clamp slot and center hold specifications must be provided.

Unless otherwise specified, the size and location of return pins and screws will be identical to those of the corresponding size A-Series Mold Base. In addition, unless otherwise specified, the riser height will be supplied to conform with the standard C dimension listed for the corresponding size A-Series Mold Base.

To create assembly item number:

Use item number prefix shown in chart at right, followed by A and B-plate thickness codes.


Example: 10.875 x 14 B-Series with 2.375 A-plate and 2.875 B-plate = 1114B-23-27

PLATE THICKNESS CODES	
THICKNESS	CODE
.875*	7
1.375*	13
1.875	17
2.375	23
2.875	27
3.375	33
3.875	37
4.875	47
5.875	57

*Not recommended for A-Plate. See instructions for ordering above.

STANDARD SIZE		ITEM NO. PREFIX
W	L	
7.875	7.875	88B
	11.875	812B
9.875	8.000	108B
	11.875	1012B
	16.000	1016B
	20.000	1020B
	23.500	1023B
10.875	12.000	1112B
	14.000	1114B
	18.000	1118B
	23.500	1123B
11.875	12.000	1212B
	15.000	1215B
	20.000	1220B
	23.500	1223B
	29.500	1239B
13.375	15.000	1315B
	18.000	1318B
	20.750	1321B
	23.500	1323B
	26.000	1326B
	29.500	1329B
14.875	17.875	1518B
	23.750	1524B
	29.500	1529B

STANDARD SIZE		ITEM NO. PREFIX
W	L	
15.875	16.000	1616B
	20.000	1620B
	23.500	1623B
	26.000	1626B
	29.500	1629B
	35.500	1635B
16.500	23.750	1724B
	29.500	1729B
17.875	18.000	1818B
	20.000	1820B
	23.500	1823B
	26.000	1826B
	29.500	1829B
	35.500	1835B
19.500	23.750	1924B
	29.500	1929B
	35.500	1935B
23.750	23.750	2424B
	29.500	2429B
	35.500	2435B

**WHEN ORDERING, PLEASE SPECIFY:**

- Quantity
- Assembly Item Number (as created above)
- Steel: #1, #3 or #7 (for other steels, please specify)
- Locating ring item number:
Item No. 6501 (D = 3.990 Diameter of Locating Ring) standard
Item No. 6504 (D = 3.990 Diameter of Locating Ring) clamp type
(For other rings see DME Mold Components Catalog)
- Type of sprue bushing, series letters: (i.e., B, etc.)
O = Small dia. of sprue bushing orifice: .156, .218, .281 or .343
R = Spherical radius of sprue bushing: .500 or .750
(For sprue bushings see DME Mold Components Catalog)
- Ejector Bar Length E (Ejector Bar Length at nominal length of mold base is highlighted in yellow. All other lengths provide an extended ejector bar)
- Other C Riser heights as needed. Also, other BCP Bottom Clamp Plate thicknesses as needed. Riser height C and BCP Bottom Clamp Plate thicknesses which are highlighted in yellow are available in #1 Steel in a one-piece Welded Housing. Also, all Riser heights C and all BCP Bottom Clamp Plate thicknesses are available in #1 or #7 Steel in a three-piece Housing (for other steels, please specify)
- Other features as needed (i.e. Guided Ejection, Lifting Holes, Pry Bar Slots, as well as Leader Pin, Return Pin, or Assembly Screw Relocations, etc.)
- Method of shipment

DME X-,AX-and T-Series Mold Bases

**A WIDE SELECTION OF DME
STANDARD STRIPPER PLATE, AX-
AND T-SERIES MOLD BASES AVAILABLE
IN DOZENS OF STANDARD SIZES**




Table of Contents

<i>Stripper Plate Series Mold Bases</i>	<i>124</i>	<i>7-7/8 T-Series 3-Plate Mold Base.....</i>	<i>136</i>
<i>AX- and T-Series Mold Bases</i>	<i>125</i>	<i>9-7/8 T-Series Mold Bases.....</i>	<i>137</i>
<i>7-7/8 and 9-7/8 Stripper Plate Mold Bases</i>	<i>126</i>	<i>10-7/8 T-Series Mold Bases.....</i>	<i>138</i>
<i>10-7/8 Stripper Plate Mold Bases</i>	<i>127</i>	<i>11-7/8 T-Series Mold Bases</i>	<i>139</i>
<i>11-7/8 Stripper Plate Mold Bases.....</i>	<i>128</i>	<i>13-3/8 T-Series Mold Bases.....</i>	<i>140</i>
<i>13-3/8 Stripper Plate Mold Bases</i>	<i>129</i>	<i>14-7/8 T-Series Mold Bases.....</i>	<i>141</i>
<i>14-7/8 Stripper Plate Mold Bases</i>	<i>130</i>	<i>15-7/8 T-Series Mold Bases.....</i>	<i>142</i>
<i>15-7/8 and 16-1/2 Stripper Plate Mold Bases.....</i>	<i>131</i>	<i>16-1/2 T-Series Mold Bases.....</i>	<i>143</i>
<i>17-7/8 Stripper Plate Mold Bases</i>	<i>132</i>	<i>17-7/8 T-Series Mold Bases</i>	<i>144</i>
<i>19-1/2 and 23-3/4 Stripper Plate Mold Bases</i>	<i>133</i>	<i>19-1/2 T-Series Mold Bases.....</i>	<i>145</i>
<i>Multiple Stripper Plate Mold Bases</i>	<i>134</i>	<i>23-3/4 T-Series Mold Bases.....</i>	<i>146</i>
<i>AX-Series Mold Bases.....</i>	<i>135</i>	<i>3-Plate Extension Bushing.....</i>	<i>147</i>
		<i>Ball Bushings for Floating Plates</i>	<i>148</i>


Stripper Plate Series Mold Base Features

DME Standard Stripper (X-Series) Mold Bases are available with either the 5- or 6-plate construction. The location of the return pins, leader pins, screws and dowels are identical to the Standard A-Series Mold Bases. Specifications are listed for every DME Standard size from 7.875×7.875 to 23.75×35.5 .

5 PLATE SERIES



6 PLATE SERIES




AX- and T-Series Mold Base Features

AX-Series Mold Bases

A DME Standard AX-Series Mold Base is basically an A-Series type mold base with a floating plate (X-1-plate) added between the cavity plates. This type assembly is used when it is desirable to have the floating plate remain with the upper half of the assembly.


AX-SERIES



T-Series Mold Bases

DME Standard T-Series Mold Bases are available in 42 standard sizes, from 7.875×7.875 to 23.75×35.5 . They are used for top runner molds that require two floating plates (X-1 – runner stripper plate, X-2 – cavity plate) to remain with the upper or stationary half of the assembly.

"T" SERIES



7 $\frac{7}{8}$ " and 9 $\frac{7}{8}$ " Stripper Plate Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates are No. 1 Steel

NO. 3 STEEL ASSEMBLIES

All plates above the ejector housing are No. 3 Steel

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel




W	L	TCP	AX	C	5 PLATE		6 PLATE	
					ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
7.875	7.875	0.875	0.875	2.5	88X-5-7	111	88X-6-7	136
			1.375	2.5	88X-5-13	120	88X-6-13	145
			1.875	2.5	88X-5-17	129	88X-6-17	154
			2.375	2.5	88X-5-23	138	88X-6-23	163
	11.875	0.875	0.875	2.5	812X-5-7	174	812X-6-7	211
			1.375	3	812X-5-13	187	812X-6-13	224
			1.875	3.5	812X-5-17	200	812X-6-17	237
			2.375	3.5	812X-5-23	214	812X-6-23	251
			0.875	2.5	108X-5-7	158	108X-6-7	189
			1.375	3	108X-5-13	173	108X-6-13	204
			1.875	3.5	108X-5-17	187	108X-6-17	218
			2.375	3.5	108X-5-23	198	108X-6-23	229
9.875	8	0.875	2.875	4	108X-5-27	213	108X-6-27	244
			3.375	4.5	108X-5-33	227	108X-6-33	258
	11.875	0.875	0.875	2.5	1012X-5-7	235	1012X-6-7	281
			1.375	3	1012X-5-13	256	1012X-6-13	302
			1.875	3.5	1012X-5-17	277	1012X-6-17	323
			2.375	3.5	1012X-5-23	294	1012X-6-23	340
			2.875	4	1012X-5-27	316	1012X-6-27	362
			3.375	4.5	1012X-5-33	337	1012X-6-33	383
	16	0.875	0.875	2.5	1016X-5-7	316	1016X-6-7	378
			1.375	3	1016X-5-13	345	1016X-6-13	407
			1.875	3.5	1016X-5-17	374	1016X-6-17	436
			2.375	3.5	1016X-5-23	396	1016X-6-23	458
			2.875	4	1016X-5-27	425	1016X-6-27	487
			3.375	4.5	1016X-5-33	454	1016X-6-33	516
	20	0.875	0.875	2.5	1020X-5-7	395	1020X-6-7	472
			1.375	3	1020X-5-13	431	1020X-6-13	508
			1.875	3.5	1020X-5-17	467	1020X-6-17	544
			2.375	3.5	1020X-5-23	495	1020X-6-23	572
			2.875	4	1020X-5-27	531	1020X-6-27	608
			3.375	4.5	1020X-5-33	567	1020X-6-33	644

NOTE: Mold bases listed above may be ordered with X, AX, and BX-plate thicknesses other than those shown in chart. Prices on request.


WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- Method of Shipment
- 1.375 Top Clamping Plate if desired

Refer to corresponding size A-Series Mold Base for detail dimensions

5 PLATE SERIES

*1.375 for 88X and 812X only

6 PLATE SERIES

*1.375 for 88X and 812X only

10⁷/₈" Stripper Plate Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES


All plates are No. 7 Steel.



W	L	TCP	AX	C	5 PLATE BX = 1.875 X = 0.875		6 PLATE BX = 1.375 X = 0.875	
					ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
10.875	12	0.875	0.875	2.5	1112X-5-7	262	1112X-6-7	313
			1.375	3	1112X-5-13	286	1112X-6-13	337
			1.875	3.5	1112X-5-17	310	1112X-6-17	361
			2.375	3.5	1112X-5-23	329	1112X-6-23	380
			2.875	4	1112X-5-27	353	1112X-6-27	404
			3.375	4.5	1112X-5-33	377	1112X-6-33	428
	14	0.875	0.875	2.5	1114X-5-7	306	1114X-6-7	366
			1.375	3	1114X-5-13	334	1114X-6-13	394
			1.875	3.5	1114X-5-17	362	1114X-6-17	422
			2.375	3.5	1114X-5-23	384	1114X-6-23	444
			2.875	4	1114X-5-27	412	1114X-6-27	472
			3.375	4.5	1114X-5-33	440	1114X-6-33	500
	18	0.875	0.875	2.5	1118X-5-7	393	1118X-6-7	470
			1.375	3	1118X-5-13	429	1118X-6-13	506
			1.875	3.5	1118X-5-17	466	1118X-6-17	543
			2.375	3.5	1118X-5-23	493	1118X-6-23	570
			2.875	4	1118X-5-27	530	1118X-6-27	607
			3.375	4.5	1118X-5-33	566	1118X-6-33	643
	23.5	0.875	0.875	2.5	1123X-5-7	513	1123X-6-7	613
			1.375	3	1123X-5-13	560	1123X-6-13	660
			1.875	3.5	1123X-5-17	608	1123X-6-17	708
			2.375	3.5	1123X-5-23	644	1123X-6-23	744
			2.875	4	1123X-5-27	691	1123X-6-27	791
			3.375	4.5	1123X-5-33	739	1123X-6-33	839

NOTE: Mold bases listed above may be ordered with X, AX, and -BX-plate thicknesses other than those shown in chart. Prices on request.

Refer to corresponding size A-Series Mold Base for detail dimensions

**WHEN ORDERING, PLEASE SPECIFY:**

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- Method of Shipment
- 1.375 Top Clamping Plate if desired

11 $\frac{7}{8}$ " Stripper Plate Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates are No. 1 Steel

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel





W	L	AX	C	5 PLATE		6 PLATE	
				ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
11.875	12	1.375	3	1212X-5-13	315	1212X-6-13	371
		1.875	3.5	1212X-5-17	341	1212X-6-17	397
		2.375	3.5	1212X-5-23	361	1212X-6-23	417
		2.875	4	1212X-5-27	387	1212X-6-27	443
		3.375	4	1212X-5-33	407	1212X-6-33	463
		3.875	4.5	1212X-5-37	433	1212X-6-37	489
	15	1.375	3	1215X-5-13	393	1215X-6-13	463
		1.875	3.5	1215X-5-17	426	1215X-6-17	496
		2.375	3.5	1215X-5-23	451	1215X-6-23	521
		2.875	4	1215X-5-27	483	1215X-6-27	553
		3.375	4	1215X-5-33	509	1215X-6-33	579
		3.875	4.5	1215X-5-37	541	1215X-6-37	611
	20	1.375	3	1220X-5-13	525	1220X-6-13	618
		1.875	3.5	1220X-5-17	568	1220X-6-17	661
		2.375	3.5	1220X-5-23	601	1220X-6-23	694
		2.875	4	1220X-5-27	645	1220X-6-27	738
		3.375	4	1220X-5-33	678	1220X-6-33	771
		3.875	4.5	1220X-5-37	721	1220X-6-37	814
	23.5	1.375	3	1223X-5-13	616	1223X-6-13	725
		1.875	3.5	1223X-5-17	667	1223X-6-17	776
		2.375	3.5	1223X-5-23	706	1223X-6-23	815
		2.875	4	1223X-5-27	757	1223X-6-27	866
		3.375	4	1223X-5-33	797	1223X-6-33	906
		3.875	4.5	1223X-5-37	848	1223X-6-37	957

NOTE: Mold bases listed above may be ordered with X, AX, and BX-plate thicknesses other than those shown in chart. Prices on request.

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3, or No. 7 Steel
3. Locating Ring Item Number
4. E, O and R Dimensions
5. Method of Shipment
6. 1.375 Top Clamping Plate if desired

Refer to corresponding size A-Series Mold Base for detail dimensions.

5 PLATE SERIES**6 PLATE SERIES**

13³/₈" Stripper Plate Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plate above the Ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.





W	L	AX	C	5 PLATE		6 PLATE	
				ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
13.375	15	1.375	3	1315X-5-13	477	1315X-6-13	556
		1.875	3.5	1315X-5-17	513	1315X-6-17	592
		2.375	3.5	1315X-5-23	542	1315X-6-23	621
		2.875	4	1315X-5-27	578	1315X-6-27	657
		3.375	4	1315X-5-33	607	1315X-6-33	686
		3.875	4.5	1315X-5-37	643	1315X-6-37	722
	18	1.375	3	1318X-5-13	572	1318X-6-13	666
		1.875	3.5	1318X-5-17	616	1318X-6-17	710
		2.375	3.5	1318X-5-23	650	1318X-6-23	744
		2.875	4	1318X-5-27	694	1318X-6-27	788
		3.375	4	1318X-5-33	728	1318X-6-33	822
		3.875	4.5	1318X-5-37	771	1318X-6-37	865
	20.75	1.375	3	1321X-5-13	660	1321X-6-13	769
		1.875	3.5	1321X-5-17	710	1321X-6-17	819
		2.375	3.5	1321X-5-23	749	1321X-6-23	858
		2.875	4	1321X-5-27	800	1321X-6-27	909
		3.375	4	1321X-5-33	839	1321X-6-33	948
		3.875	4.5	1321X-5-37	889	1321X-6-37	998
	23.5	1.375	3	1323X-5-13	747	1323X-6-13	870
		1.875	3.5	1323X-5-17	804	1323X-6-17	927
		2.375	3.5	1323X-5-23	849	1323X-6-23	972
		2.875	4	1323X-5-27	906	1323X-6-27	1029
		3.375	4	1323X-5-33	950	1323X-6-33	1073
		3.875	4.5	1323X-5-37	1007	1323X-6-37	1130
	26	1.375	3	1326X-5-13	826	1326X-6-13	962
		1.875	3.5	1326X-5-17	889	1326X-6-17	1025
		2.375	3.5	1326X-5-23	939	1326X-6-23	1075
		2.875	4	1326X-5-27	1002	1326X-6-27	1138
		3.375	4	1326X-5-33	1051	1326X-6-33	1187
		3.875	4.5	1326X-5-37	1114	1326X-6-37	1250
	29.5	1.375	3	1329X-5-13	938	1329X-6-13	1092
		1.875	3.5	1329X-5-17	1009	1329X-6-17	1163
		2.375	3.5	1329X-5-23	1065	1329X-6-23	1219
		2.875	4	1329X-5-27	1137	1329X-6-27	1291
		3.375	4	1329X-5-33	1192	1329X-6-33	1346
		3.875	4.5	1329X-5-37	1264	1329X-6-37	1418

NOTE: Mold bases listed above may be ordered with X, AX, and BX-plate thicknesses other than those shown in chart. Prices on request.

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3, or No. 7 Steel
3. Locating Ring Item Number
4. E, O and R Dimensions
5. Method of Shipment

Refer to corresponding size A-Series Mold Base for detail dimensions.



14⁷/₈" Stripper Plate Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES



All plates are No. 7 Steel.



Refer to corresponding size A-Series Mold Base for detail dimensions.

W	L	AX	C	5 PLATE		6 PLATE	
				ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
14.875	17.875	1.375	3	1518X-5-13	668	1518X-6-13	772
		1.875	3.5	1518X-5-17	715	1518X-6-17	819
		2.375	3.5	1518X-5-23	752	1518X-6-23	856
		2.875	4	1518X-5-27	800	1518X-6-27	904
		3.375	4	1518X-5-33	837	1518X-6-33	941
		3.875	4.5	1518X-5-37	885	1518X-6-37	989
	23.75	1.375	3	1524X-5-13	887	1524X-6-13	1025
		1.875	3.5	1524X-5-17	950	1524X-6-17	1088
		2.375	3.5	1524X-5-23	1000	1524X-6-23	1138
		2.875	4	1524X-5-27	1063	1524X-6-27	1201
		3.375	4	1524X-5-33	1112	1524X-6-33	1250
		3.875	4.5	1524X-5-37	1175	1524X-6-37	1313
	29.5	1.375	3	1529X-5-13	1102	1529X-6-13	1273
		1.875	3.5	1529X-5-17	1180	1529X-6-17	1351
		2.375	3.5	1529X-5-23	1242	1529X-6-23	1413
		2.875	4	1529X-5-27	1320	1529X-6-27	1491
		3.375	4	1529X-5-33	1382	1529X-6-33	1553
		3.875	4.5	1529X-5-37	1460	1529X-6-37	1631

NOTE: Mold bases listed above may be ordered with X, AX, and BX-plate thicknesses other than those shown in chart. Prices on request.

5 PLATE SERIES**6 PLATE SERIES****WHEN ORDERING, PLEASE SPECIFY:**

1. Quantity & Item Number
2. No. 1, No. 3, or No. 7 Steel
3. Locating Ring Item Number
4. E, O and R Dimensions
5. Method of Shipment

15⁷/₈" and 16¹/₂" Stripper Plate Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates No. 7 Steel.

5 PLATE SERIES**6 PLATE SERIES**

W	L	AX	C	5 PLATE		6 PLATE	
				ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
15.875	16	1.375	3	1616X-5-13	637	1616X-6-13	736
		1.875	3.5	1616X-5-17	682	1616X-6-17	781
		2.375	3.5	1616X-5-23	717	1616X-6-23	816
		2.875	4	1616X-5-27	762	1616X-6-27	861
		3.375	4	1616X-5-33	798	1616X-6-33	897
		3.875	4.5	1616X-5-37	843	1616X-6-37	942
	20	1.375	3	1620X-5-13	796	1620X-6-13	920
		1.875	3.5	1620X-5-17	852	1620X-6-17	976
		2.375	3.5	1620X-5-23	896	1620X-6-23	1020
		2.875	4	1620X-5-27	952	1620X-6-27	1076
		3.375	4	1620X-5-33	997	1620X-6-33	1121
		3.875	4.5	1620X-5-37	1053	1620X-6-37	1177
	23.5	1.375	3	1623X-5-13	935	1623X-6-13	1081
		1.875	3.5	1623X-5-17	1001	1623X-6-17	1147
		2.375	3.5	1623X-5-23	1053	1623X-6-23	1199
		2.875	4	1623X-5-27	1119	1623X-6-27	1265
		3.375	4	1623X-5-33	1171	1623X-6-33	1317
		3.875	4.5	1623X-5-37	1237	1623X-6-37	1383
	26	1.375	3	1626X-5-13	1034	1626X-6-13	1195
		1.875	3.5	1626X-5-17	1107	1626X-6-17	1268
		2.375	3.5	1626X-5-23	1165	1626X-6-23	1326
		2.875	4	1626X-5-27	1238	1626X-6-27	1399
		3.375	4	1626X-5-33	1296	1626X-6-33	1457
		3.875	4.5	1626X-5-37	1368	1626X-6-37	1529
	29.5	1.375	3	1629X-5-13	1174	1629X-6-13	1357
		1.875	3.5	1629X-5-17	1256	1629X-6-17	1439
		2.375	3.5	1629X-5-23	1322	1629X-6-23	1505
		2.875	4	1629X-5-27	1404	1629X-6-27	1587
		3.375	4	1629X-5-33	1470	1629X-6-33	1653
		3.875	4.5	1629X-5-37	1553	1629X-6-37	1736
	35.5	1.375	3	1635X-5-13	1412	1635X-6-13	1632
		1.875	3.5	1635X-5-17	1511	1635X-6-17	1731
		2.375	3.5	1635X-5-23	1591	1635X-6-23	1811
		2.875	4	1635X-5-27	1690	1635X-6-27	1910
		3.375	4	1635X-5-33	1769	1635X-6-33	1989
		3.875	4.5	1635X-5-37	1868	1635X-6-37	2088
16.5	23.75	1.375	3	1724X-5-13	981	1724X-6-13	1134
		1.875	3.5	1724X-5-17	1050	1724X-6-17	1203
		2.375	3.5	1724X-5-23	1105	1724X-6-23	1258
		2.875	4	1724X-5-27	1173	1724X-6-27	1326
		3.375	4	1724X-5-33	1229	1724X-6-33	1382
		3.875	4.5	1724X-5-37	1297	1724X-6-37	1450
	29.5	1.375	3	1729X-5-13	1219	1729X-6-13	1409
		1.875	3.5	1729X-5-17	1304	1729X-6-17	1494
		2.375	3.5	1729X-5-23	1372	1729X-6-23	1562
		2.875	4	1729X-5-27	1457	1729X-6-27	1647
		3.375	4	1729X-5-33	1526	1729X-6-33	1716
		3.875	4.5	1729X-5-37	1611	1729X-6-37	1801

NOTE: Mold bases listed above may be ordered with X, AX, and BX-plate thicknesses other than those shown in chart. Prices on request.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- Method of Shipment

17 $\frac{7}{8}$ " Stripper Plate Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES


All plates are No. 7 Steel.



Refer to corresponding size A-Series Mold Base for detail dimensions.


W	L	AX	C	5 PLATE		6 PLATE	
				ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
17.875	18	1.375	3	1818X-5-13	850	1818X-6-13	976
		1.875	3.5	1818X-5-17	905	1818X-6-17	1031
		2.375	3.5	1818X-5-23	951	1818X-6-23	1077
		2.875	4	1818X-5-27	1006	1818X-6-27	1132
		3.375	4	1818X-5-33	1051	1818X-6-33	1177
		3.875	4.5	1818X-5-37	1107	1818X-6-37	1233
	20	1.375	3	1820X-5-13	944	1820X-6-13	1084
		1.875	3.5	1820X-5-17	1006	1820X-6-17	1146
		2.375	3.5	1820X-5-23	1056	1820X-6-23	1196
		2.875	4	1820X-5-27	1118	1820X-6-27	1258
		3.375	4	1820X-5-33	1168	1820X-6-33	1308
		3.875	4.5	1820X-5-37	1230	1820X-6-37	1370
	23.5	1.375	3	1823X-5-13	1109	1823X-6-13	1273
		1.875	3.5	1823X-5-17	1182	1823X-6-17	1346
		2.375	3.5	1823X-5-23	1241	1823X-6-23	1405
		2.875	4	1823X-5-27	1313	1823X-6-27	1477
		3.375	4	1823X-5-33	1372	1823X-6-33	1536
		3.875	4.5	1823X-5-37	1445	1823X-6-37	1609
	26	1.375	3	1826X-5-13	1227	1826X-6-13	1409
		1.875	3.5	1826X-5-17	1307	1826X-6-17	1489
		2.375	3.5	1826X-5-23	1373	1826X-6-23	1555
		2.875	4	1826X-5-27	1453	1826X-6-27	1635
		3.375	4	1826X-5-33	1518	1826X-6-33	1700
		3.875	4.5	1826X-5-37	1598	1826X-6-37	1780
	29.5	1.375	3	1829X-5-13	1392	1829X-6-13	1598
		1.875	3.5	1829X-5-17	1483	1829X-6-17	1689
		2.375	3.5	1829X-5-23	1558	1829X-6-23	1764
		2.875	4	1829X-5-27	1648	1829X-6-27	1854
		3.375	4	1829X-5-33	1723	1829X-6-33	1929
		3.875	4.5	1829X-5-37	1813	1829X-6-37	2019
	35.5	1.375	3	1835X-5-13	1676	1835X-6-13	1924
		1.875	3.5	1835X-5-17	1785	1835X-6-17	2033
		2.375	3.5	1835X-5-23	1874	1835X-6-23	2122
		2.875	4	1835X-5-27	1983	1835X-6-27	2231
		3.375	4	1835X-5-33	2073	1835X-6-33	2321
		3.875	4.5	1835X-5-37	2182	1835X-6-37	2430

NOTE: Mold bases listed above may be ordered with X, AX, and BX-plate thicknesses other than those shown in chart. Prices on request.

5 PLATE SERIES

BX = 2.375

X = 1.375

6 PLATE SERIES

BX = 1.375

X = 1.375

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3, or No. 7 Steel
3. Locating Ring Item Number
4. E, O and R Dimensions
5. Method of Shipment

19½" and 23¾" Stripper Plate Mold Bases

NO. 1 STEEL ASSEMBLIES

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel





Refer to corresponding size A-Series Mold Base for detail dimensions.

W	L	AX	C	5 PLATE		6 PLATE	
				ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
19.5	23.75	1.375	3	1924X-5-13	1221	1924X-6-13	1402
		1.875	3.5	1924X-5-17	1300	1924X-6-17	1481
		2.375	3.5	1924X-5-23	1365	1924X-6-23	1546
		2.875	4	1924X-5-27	1443	1924X-6-27	1624
		3.375	4	1924X-5-33	1509	1924X-6-33	1690
		3.875	4.5	1924X-5-37	1587	1924X-6-37	1768
	29.5	1.375	3	1929X-5-13	1516	1929X-6-13	1741
		1.875	3.5	1929X-5-17	1614	1929X-6-17	1839
		2.375	3.5	1929X-5-23	1695	1929X-6-23	1920
		2.875	4	1929X-5-27	1793	1929X-6-27	2018
		3.375	4	1929X-5-33	1874	1929X-6-33	2099
		3.875	4.5	1929X-5-37	1971	1929X-6-37	2196
	35.5	1.375	3	1935X-5-13	1825	1935X-6-13	2095
		1.875	3.5	1935X-5-17	1942	1935X-6-17	2212
		2.375	3.5	1935X-5-23	2040	1935X-6-23	2310
		2.875	4	1935X-5-27	2157	1935X-6-27	2427
		3.375	4	1935X-5-33	2255	1935X-6-33	2525
		3.875	4.5	1935X-5-37	2372	1935X-6-37	2642
23.75	23.75	1.375	3	2424X-5-13	1562	2424X-6-13	1782
		1.875	3.5	2424X-5-17	1655	2424X-6-17	1875
		2.375	3.5	2424X-5-23	1734	2424X-6-23	1954
		2.875	4	2424X-5-27	1827	2424X-6-27	2047
		3.375	4	2424X-5-33	1907	2424X-6-33	2127
		3.875	4.5	2424X-5-37	2000	2424X-6-37	2220
	29.5	1.375	3	2429X-5-13	1940	2429X-6-13	2213
		1.875	3.5	2429X-5-17	2055	2429X-6-17	2328
		2.375	3.5	2429X-5-23	2154	2429X-6-23	2427
		2.875	4	2429X-5-27	2269	2429X-6-27	2542
		3.375	4	2429X-5-33	2368	2429X-6-33	2641
		3.875	4.5	2429X-5-37	2483	2429X-6-37	2756
	35.5	1.375	3	2435X-5-13	2334	2435X-6-13	2663
		1.875	3.5	2435X-5-17	2473	2435X-6-17	2802
		2.375	3.5	2435X-5-23	2592	2435X-6-23	2921
		2.875	4	2435X-5-27	2730	2435X-6-27	3059
		3.375	4	2435X-5-33	2850	2435X-6-33	3179
		3.875	4.5	2435X-5-37	2988	2435X-6-37	3317

NOTE: Mold bases listed above may be ordered with X, AX, and BX-plate thicknesses other than those shown in chart. Prices on request.


WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3, or No. 7 Steel
3. Locating Ring Item Number
4. E, O and R Dimensions
5. Method of Shipment




Multiple Stripper Plate Mold Bases

Multiple Stripper Plate Mold Bases consist of a 5 or 6 plate X-Series Mold Base with one or more floating plates added to the assembly. The assembly "without the support plate" has the same construction as the 5 Plate "X-Series. When this type of assembly is required please refer to the plate designations listed below. Prices quoted on request.



VARIATIONS IN EJECTOR ASSEMBLY

DOUBLE EJECTION - SPECIAL ORDER - PLEASE CONTACT CUSTOMER SERVICE



Double ejection is sometimes required when using multiple stripper plate mold assemblies. Prices quoted on request.

AX-Series Mold Bases

NO. 1 STEEL ASSEMBLIES

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES


All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

Any plates are No.7 Steel.



AX-Series Assembly



MOLD BASE SIZE WIDTH (W)	TOP CLAMPING PLATE THICKNESS
7.875 to 11.875	0.875
13.375 to 23.75	1.375

X-1-PLATE THICKNESSES AVAILABLE:

0.875, 1.375, 1.875, 2.375, 2.875, 3.375, 4.875, 5.875

A DME Standard AX-Series Mold Base is basically an A-series type mold base with a floating plate (X1-plate) added between the A and B-plates. This type assembly is used where it is desirable to have the floating plate remain with the upper half of the assembly.

INSTRUCTIONS FOR ORDERING:

When ordering AX-Series Mold Bases, refer to the corresponding size A-Series Mold Base for detailed dimensions.

To create a Item number, add an X after the A in Item number of corresponding size A-Series mold base, and follow with thickness of the (1) A-Plate, (2) X1-Plate and (3) B-Plate.

Example: 1012AX-13-17-23

STANDARD MOLD BASE SIZE		ITEM NUMBER PREFIX
W	L	
7.875	7.875	88AX
	11.875	812AX
9.875	8	108AX
	11.875	1012AX
	16	1016AX
	20	1020AX
	23.5	1123AX
10.875	12	1112AX
	14	1114AX
	18	1118AX
	23.5	1123AX
11.875	12	1212AX
	15	1215AX
	20	1220AX
	23.5	1223AX
	29.5	1329AX
13.375	15	1315AX
	18	1318AX
	20.75	1321AX
	23.5	1323AX
	26	1326AX
14.875	17.875	1518AX
	23.75	1524AX
	29.5	1529AX

STANDARD MOLD BASE SIZE		ITEM NUMBER PREFIX
W	L	
15.875	16	1616AX
	20	1620AX
	23.5	1623AX
	26	1626AX
	29.5	1629AX
16.5	35.5	1635AX
	23.75	1724AX
	29.5	1729AX
17.875	18	1818AX
	20	1820AX
	23.5	1823AX
	26	1826AX
	29.5	1829AX
19.5	35.5	1835AX
	23.75	1924AX
	29.5	1929AX
23.75	35.5	1935AX
	23.75	2424AX
	29.5	2429AX
	35.5	2435AX



WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- X-1-Plate Thickness
- Locating Ring Item Number
- E, O and R Dimensions
- Method of Shipment
- 1.375 Top Clamping Plate if desired

7 $\frac{7}{8}$ " T-Series (3-Plate) Mold Bases

A typical 3-plate top runner mold operates as follows: The mold opens first at Parting Line 1 (spring loaded). The runner and cavity sprues are pulled from the cavities in the X-2-Plate and held against the X-1-Plate by undercut puller pins.

As the mold continues to open (X-2-Plate moving forward), stripper bolts SB-1 pull the X-1-Plate forward (at the end of the X-2-Plate movement). The X-1-Plate travel is determined by stripper bolts SB-2. The travel of the X-1-Plate (breaking at Parting Line 2) strips the entire runner system from the puller pins, breaks the main sprue (held to a minimum length), and allows the runner to drop free. Mold opening at Parting Line 3 then takes place for piece-part ejection.



For detailed dimensions, see corresponding size A-Series Mold Base

X-1 = 0.875				7.875 x 7.875	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.375	0.875	2.5	9.75	88T-13-7	153
	1.375	2.5	10.25	88T-13-13	162
	1.875	2.5	10.75	88T-13-17	171
1.875	0.875	2.5	10.25	88T-17-7	162
	1.375	2.5	10.75	88T-17-13	171
	1.875	2.5	11.25	88T-17-17	180
2.375	1.375	2.5	11.25	88T-23-13	180
	1.875	2.5	11.75	88T-23-17	188
	2.375	3	12.75	88T-23-23	200
2.875	1.375	3	12.25	88T-27-13	191
	1.875	3.5	13.25	88T-27-17	203
	2.375	3.5	13.75	88T-27-23	212
3.375	1.875	3.5	13.75	88T-33-17	212
	2.375	4	14.75	88T-33-23	223
	2.875	4	15.25	88T-33-27	232
3.875	1.875	3.5	14.25	88T-37-17	220
	2.375	4	15.25	88T-37-23	232
	2.875	4	15.75	88T-37-27	241
4.875	2.375	4	16.25	88T-47-23	250
	2.875	4	16.75	88T-47-27	258
	3.375	4.5	17.75	88T-47-33	270

X-1 = 0.875				7.875 x 11.875	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.375	0.875	2.5	9.75	812T-13-7	237
	1.375	3	10.75	812T-13-13	254
	1.875	3	11.25	812T-13-17	268
1.875	0.875	2.5	10.25	812T-17-7	250
	1.375	3	11.25	812T-17-13	268
	1.875	3.5	12.25	812T-17-17	285
2.375	1.375	3	11.75	812T-23-13	281
	1.875	3.5	12.75	812T-23-17	298
	2.375	3.5	13.25	812T-23-23	312
2.875	1.375	3	12.25	812T-27-13	294
	1.875	3.5	13.25	812T-27-17	312
	2.375	3.5	13.75	812T-27-23	325
3.375	1.875	3.5	13.75	812T-33-17	325
	2.375	4	14.75	812T-33-23	342
	2.875	4	15.25	812T-33-27	355
3.875	1.875	3.5	14.25	812T-37-17	338
	2.375	4	15.25	812T-37-23	355
	2.875	4	15.75	812T-37-27	369
4.875	2.375	4	16.25	812T-47-23	382
	2.875	4	16.75	812T-47-27	395
	3.375	4.5	17.75	812T-47-33	413

NOTE: Stripper bolts, puller pins and spring shown are not included. When gating directly into the cavity from a top runner, the 3-plate T-Series assembly may be used. It incorporates an additional runner stripper plate (X-1) to facilitate automatic removal of the runner from the mold.

The X-1 and X-2-Plates have standard shoulder bushings and ride on standard leader pins. (When heavy X-2-Plates are required, moldmaker may want to specify larger diameter leader pins and have them relocated. Contact customer service for a quotation to your specifications). The X-1-Plate is supplied without a center hole. A standard sprue bushing long enough to extend through the X-1-plate is provided to allow the moldmaker to finish the sprue bushing hole as desired, or to install a recessed bushing to give the shortest main sprue length for minimum stripper plate movement.

Detailed dimensions for the T-Series are identical to corresponding size A-Series Mold Bases. Center sprue puller pin and pin holes as well as the socket head cap screws in the A-Clamping Plate are omitted since the are not required.

9⁷/₈" T-Series Mold Bases

X-1 = 0.875				9.875 × 8"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.375	0.875	2.5	10.25	108T-13-7	211
	1.375	2.5	10.75	108T-13-13	223
	1.875	3	11.75	108T-13-17	237
1.875	0.875	2.5	10.75	108T-17-7	223
	1.375	3	11.75	108T-17-13	237
	1.875	3.5	12.75	108T-17-17	251
2.375	1.375	3	12.25	108T-23-13	248
	1.875	3.5	13.25	108T-23-17	263
	2.375	3.5	13.75	108T-23-23	274
2.875	1.375	3	12.75	108T-27-13	259
	1.875	3.5	13.75	108T-27-17	274
	2.375	3.5	14.25	108T-27-23	285
3.375	1.875	3.5	14.25	108T-33-17	285
	2.375	4	15.25	108T-33-23	299
	2.875	4	15.75	108T-33-27	311
3.875	1.875	3.5	14.75	108T-37-17	296
	2.375	4	15.75	108T-37-23	311
	2.875	4	16.25	108T-37-27	322
4.875	2.375	4	16.75	108T-47-23	333
	2.875	4	17.25	108T-47-27	344
	3.375	4.5	18.25	108T-47-33	359

X-1 = 0.875				9.875 × 11.875	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.375	0.875	2.5	10.25	1012T-13-7	313
	1.375	3	11.25	1012T-13-13	335
	1.875	3	11.75	1012T-13-17	351
1.875	0.875	2.5	10.75	1012T-17-7	330
	1.375	3	11.75	1012T-17-13	352
	1.875	3.5	12.75	1012T-17-17	373
2.375	1.375	3	12.25	1012T-23-13	368
	1.875	3.5	13.25	1012T-23-17	390
	2.375	3.5	13.75	1012T-23-23	406
2.875	1.375	3	12.75	1012T-27-13	385
	1.875	3.5	13.75	1012T-27-17	406
	2.375	3.5	14.25	1012T-27-23	423
3.375	1.875	3.5	14.25	1012T-33-17	423
	2.375	4	15.25	1012T-33-23	444
	2.875	4	15.75	1012T-33-27	461
3.875	1.875	3.5	14.75	1012T-37-17	439
	2.375	4	15.75	1012T-37-23	461
	2.875	4	16.25	1012T-37-27	477
4.875	2.375	4	16.75	1012T-47-23	494
	2.875	4	17.25	1012T-47-27	511
	3.375	4.5	18.25	1012T-47-33	532

X-1 = 0.875				9.875 × 16"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.375	0.875	2.5	10.25	1016T-13-7	422
	1.375	3	11.25	1016T-13-13	451
	1.875	3	11.75	1016T-13-17	473
1.875	0.875	2.5	10.75	1016T-17-7	444
	1.375	3	11.75	1016T-17-13	473
	1.875	3.5	12.75	1016T-17-17	502
2.375	1.375	3	12.25	1016T-23-13	496
	1.875	3.5	13.25	1016T-23-17	525
	2.375	3.5	13.75	1016T-23-23	547
2.875	1.375	3	12.75	1016T-27-13	518
	1.875	3.5	13.75	1016T-27-17	547
	2.375	3.5	14.25	1016T-27-23	569
3.375	1.875	3.5	14.25	1016T-33-17	569
	2.375	4	15.25	1016T-33-23	598
	2.875	4	15.75	1016T-33-27	621
3.875	1.875	3.5	14.75	1016T-37-17	592
	2.375	4	15.75	1016T-37-23	621
	2.875	4	16.25	1016T-37-27	643
4.875	2.375	4	16.75	1016T-47-23	665
	2.875	4	17.25	1016T-47-27	688
	3.375	4.5	18.25	1016T-47-33	717

NO. 1 STEEL ASSEMBLIES

All plates are No. 1 Steel.


NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.

NOTE: For 3-Plate Extension Bushings, see page 147.



For detailed dimensions, see corresponding size A-Series Mold Bases.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- L Dimension (Leader Pin Length)
- Method of Shipment

10⁷/₈" T-Series Mold Bases**NO. 1 STEEL ASSEMBLIES**

All plates are No. 1 Steel.


NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.

NOTE: For 3-Plate Extension Bushings, see page 147.



For detailed dimensions, see corresponding size A-Series Mold Bases.

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Locating Ring Item Number
4. E, O and R Dimensions
5. L Dimension (Leader Pin Length)
6. Method of Shipment

X-1 = 0.875				10.875 × 12"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	2.5	10.75	1112T-17-7	368
	1.375	3	11.75	1112T-17-13	393
	1.875	3.5	12.75	1112T-17-17	417
2.375	1.375	3	12.25	1112T-23-13	411
	1.875	3.5	13.25	1112T-23-17	435
	2.375	3.5	13.75	1112T-23-23	454
2.875	1.375	3	12.75	1112T-27-13	430
	1.875	3.5	13.75	1112T-27-17	454
	2.375	3.5	14.25	1112T-27-23	472
3.375	1.875	3.5	14.25	1112T-33-17	472
	2.375	4	15.25	1112T-33-23	497
	2.875	4	15.75	1112T-33-27	515
3.875	1.875	3.5	14.75	1112T-37-17	491
	2.375	4	15.75	1112T-37-23	515
	2.875	4	16.25	1112T-37-27	534
4.875	2.375	4	16.75	1112T-47-23	552
	2.875	4	17.25	1112T-47-27	570
	3.375	4.5	18.25	1112T-47-33	595
5.875	2.875	4	18.25	1112T-57-27	607
	3.875	4.5	19.75	1112T-57-37	650
	4.875	4.5	20.75	1112T-57-47	687

X-1 = 0.875				10.875 × 18"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	2.5	10.75	1118T-17-7	552
	1.375	3	11.75	1118T-17-13	589
	1.875	3.5	12.75	1118T-17-17	625
2.375	1.375	3	12.25	1118T-23-13	616
	1.875	3.5	13.25	1118T-23-17	653
	2.375	3.5	13.75	1118T-23-23	680
2.875	1.375	3	12.75	1118T-27-13	644
	1.875	3.5	13.75	1118T-27-17	680
	2.375	3.5	14.25	1118T-27-23	708
3.375	1.875	3.5	14.25	1118T-33-17	708
	2.375	4	15.25	1118T-33-23	745
	2.875	4	15.75	1118T-33-27	772
3.875	1.875	3.5	14.75	1118T-37-17	736
	2.375	4	15.75	1118T-37-23	772
	2.875	4	16.25	1118T-37-27	800
4.875	2.375	4	16.75	1118T-47-23	828
	2.875	4	17.25	1118T-47-27	855
	3.375	4.5	18.25	1118T-47-33	892
5.875	2.875	4	18.25	1118T-57-27	911
	3.875	4.5	19.75	1118T-57-37	975
	4.875	4.5	20.75	1118T-57-47	1030

X-1 = 0.875				10.875 × 14"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	2.5	10.75	1114T-17-7	430
	1.375	3	11.75	1114T-17-13	458
	1.875	3.5	12.75	1114T-17-17	486
2.375	1.375	3	12.25	1114T-23-13	480
	1.875	3.5	13.25	1114T-23-17	508
	2.375	3.5	13.75	1114T-23-23	529
2.875	1.375	3	12.75	1114T-27-13	501
	1.875	3.5	13.75	1114T-27-17	529
	2.375	3.5	14.25	1114T-27-23	551
3.375	1.875	3.5	14.25	1114T-33-17	551
	2.375	4	15.25	1114T-33-23	579
	2.875	4	15.75	1114T-33-27	601
3.875	1.875	3.5	14.75	1114T-37-17	573
	2.375	4	15.75	1114T-37-23	601
	2.875	4	16.25	1114T-37-27	622
4.875	2.375	4	16.75	1114T-47-23	644
	2.875	4	17.25	1114T-47-27	665
	3.375	4.5	18.25	1114T-47-33	694
5.875	2.875	4	18.25	1114T-57-27	709
	3.875	4.5	19.75	1114T-57-37	758
	4.875	4.5	20.75	1114T-57-47	802

X-1 = 1.375				10.875 × 23.5"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1123T-17-13	805
	1.875	3.5	13.25	1123T-17-17	852
	2.375	3.5	13.75	1123T-17-23	888
2.375	1.375	3	12.75	1123T-23-13	841
	1.875	3.5	13.75	1123T-23-17	888
	2.375	3.5	14.25	1123T-23-23	924
2.875	1.375	3	13.25	1123T-27-13	877
	1.875	3.5	14.25	1123T-27-17	924
	2.375	3.5	14.75	1123T-27-23	961
3.375	1.875	3.5	14.75	1123T-33-17	961
	2.375	4	15.75	1123T-33-23	1008
	2.875	4	16.25	1123T-33-27	1044
3.875	1.875	3.5	15.25	1123T-37-17	997
	2.375	4	16.25	1123T-37-23	1044
	2.875	4	16.75	1123T-37-27	1080
4.875	2.375	4	17.25	1123T-47-23	1117
	2.875	4	17.75	1123T-47-27	1153
	3.375	4.5	18.75	1123T-47-33	1200
5.875	2.875	4	18.75	1123T-57-27	1225
	3.875	4.5	20.25	1123T-57-37	1309
	4.875	4.5	21.25	1123T-57-47	1381

11⁷/₈" T-Series Mold Bases

X-1 = 0.875				11.875 × 12"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	3	11.25	1212T-17-7	411
	1.375	3	11.75	1212T-17-13	431
	1.875	3	12.25	1212T-17-17	451
2.375	1.375	3.5	12.75	1212T-23-13	457
	1.875	3.5	13.25	1212T-23-17	477
	2.375	3.5	13.75	1212T-23-23	497
2.875	1.375	3.5	13.25	1212T-27-13	477
	1.875	3.5	13.75	1212T-27-17	497
	2.375	3.5	14.25	1212T-27-23	518
3.375	1.875	3.5	14.25	1212T-33-17	518
	2.375	4	15.25	1212T-33-23	543
	2.875	4	15.75	1212T-33-27	564
3.875	1.875	4	15.25	1212T-37-17	543
	2.375	4.5	16.25	1212T-37-23	569
	2.875	4.5	16.75	1212T-37-27	590
4.875	2.375	4.5	17.25	1212T-47-23	610
	2.875	4.5	17.75	1212T-47-27	630
	3.375	4.5	18.25	1212T-47-33	650
5.875	2.875	4.5	18.75	1212T-57-27	670
	3.875	4.5	19.75	1212T-57-37	711
	4.875	4.5	20.75	1212T-57-47	751

X-1 = 0.875				11.875 × 15"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	3	11.25	1215T-17-7	513
	1.375	3	11.75	1215T-17-13	539
	1.875	3	12.25	1215T-17-17	564
2.375	1.375	3.5	12.75	1215T-23-13	571
	1.875	3.5	13.25	1215T-23-17	596
	2.375	3.5	13.75	1215T-23-23	621
2.875	1.375	3.5	13.25	1215T-27-13	596
	1.875	3.5	13.75	1215T-27-17	621
	2.375	3.5	14.25	1215T-27-23	647
3.375	1.875	3.5	14.25	1215T-33-17	647
	2.375	4	15.25	1215T-33-23	679
	2.875	4	15.75	1215T-33-27	704
3.875	1.875	4	15.25	1215T-37-17	679
	2.375	4.5	16.25	1215T-37-23	711
	2.875	4.5	16.75	1215T-37-27	737
4.875	2.375	4.5	17.25	1215T-47-23	762
	2.875	4.5	17.75	1215T-47-27	787
	3.375	4.5	18.25	1215T-47-33	812
5.875	2.875	4.5	18.75	1215T-57-27	839
	3.875	4.5	19.75	1215T-57-37	888
	4.875	4.5	20.75	1215T-57-47	939

X-1 = 0.875				11.875 × 20"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	3	11.25	1220T-17-7	684
	1.375	3	11.75	1220T-17-13	718
	1.875	3	12.25	1220T-17-17	752
2.375	1.375	3.5	12.75	1220T-23-13	761
	1.875	3.5	13.25	1220T-23-17	795
	2.375	3.5	13.75	1220T-23-23	828
2.875	1.375	3.5	13.25	1220T-27-13	795
	1.875	3.5	13.75	1220T-27-17	828
	2.375	3.5	14.25	1220T-27-23	862
3.375	1.875	3.5	14.25	1220T-33-17	862
	2.375	4	15.25	1220T-33-23	905
	2.875	4	15.75	1220T-33-27	939
3.875	1.875	4	15.25	1220T-37-17	905
	2.375	4.5	16.25	1220T-37-23	949
	2.875	4.5	16.75	1220T-37-27	982
4.875	2.375	4.5	17.25	1220T-47-23	1016
	2.875	4.5	17.75	1220T-47-27	1049
	3.375	4.5	18.25	1220T-47-33	1083
5.875	2.875	4.5	18.75	1220T-57-27	1117
	3.875	4.5	19.75	1220T-57-37	1184
	4.875	4.5	20.75	1220T-57-47	1251

X-1 = 1.375				11.875 × 23.5"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1223T-17-13	883
	1.875	3	12.75	1223T-17-17	923
	2.375	3.5	13.75	1223T-17-23	973
2.375	1.375	3.5	13.25	1223T-23-13	934
	1.875	3.5	13.75	1223T-23-17	973
	2.375	3.5	14.25	1223T-23-23	1013
2.875	1.375	3.5	13.75	1223T-27-13	973
	1.875	3.5	14.25	1223T-27-17	1013
	2.375	3.5	14.75	1223T-27-23	1052
3.375	1.875	3.5	14.75	1223T-33-17	1052
	2.375	4	15.75	1223T-33-23	1103
	2.875	4	16.25	1223T-33-27	1143
3.875	1.875	4	15.75	1223T-37-17	1103
	2.375	4.5	16.75	1223T-37-23	1154
	2.875	4.5	17.25	1223T-37-27	1193
4.875	2.375	4.5	17.75	1223T-47-23	1233
	2.875	4.5	18.25	1223T-47-27	1272
	3.375	4.5	18.75	1223T-47-33	1312
5.875	2.875	4.5	19.25	1223T-57-27	1352
	3.875	4.5	20.25	1223T-57-37	1431
	4.875	4.5	21.25	1223T-57-47	1510

NO. 1 STEEL ASSEMBLIES

All plates are No. 1 Steel.


NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.

NOTE: For 3-Plate Extension Bushings, see page 147.



For detailed dimensions, see corresponding size A-Series Mold Bases.

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Locating Ring Item Number
4. E, O and R Dimensions
5. L Dimension (Leader Pin Length)
6. Method of Shipment

13³/₈" T-Series Mold Bases

NO. 1 ASSEMBLIES

All plates are No. 1 Steel.

X-1 = 0.875				13.375 x 15"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	3	11.25	1315T-17-7	584
	1.375	3	11.75	1315T-17-13	612
	1.875	3	12.25	1315T-17-17	640
2.375	1.375	3.5	12.75	1315T-23-13	648
	1.875	3.5	13.25	1315T-23-17	677
	2.375	3.5	13.75	1315T-23-23	705
2.875	1.375	3.5	13.25	1315T-27-13	677
	1.875	3.5	13.75	1315T-27-17	705
	2.375	3.5	14.25	1315T-27-23	734
3.375	1.875	3.5	14.25	1315T-33-17	734
	2.375	4	15.25	1315T-33-23	770
	2.875	4	15.75	1315T-33-27	798
3.875	1.875	4	15.25	1315T-37-17	770
	2.375	4.5	16.25	1315T-37-23	806
	2.875	4.5	16.75	1315T-37-27	835
4.875	2.375	4.5	17.25	1315T-47-23	863
	2.875	4.5	17.75	1315T-47-27	892
	3.375	4.5	18.25	1315T-47-33	920
5.875	2.875	4.5	18.75	1315T-57-27	949
	3.875	4.5	19.75	1315T-57-37	1005
	4.875	4.5	20.75	1315T-57-47	1062

X-1 = 0.875				13.375 x 18"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	3	11.25	1318T-17-7	700
	1.375	3	11.75	1318T-17-13	734
	1.875	3	12.25	1318T-17-17	768
2.375	1.375	3.5	12.75	1318T-23-13	778
	1.875	3.5	13.25	1318T-23-17	812
	2.375	3.5	13.75	1318T-23-23	846
2.875	1.375	3.5	13.25	1318T-27-13	812
	1.875	3.5	13.75	1318T-27-17	846
	2.375	3.5	14.25	1318T-27-23	880
3.375	1.875	3.5	14.25	1318T-33-17	880
	2.375	4	15.25	1318T-33-23	924
	2.875	4	15.75	1318T-33-27	958
3.875	1.875	4	15.25	1318T-37-17	924
	2.375	4.5	16.25	1318T-37-23	968
	2.875	4.5	16.75	1318T-37-27	1002
4.875	2.375	4.5	17.25	1318T-47-23	1036
	2.875	4.5	17.75	1318T-47-27	1070
	3.375	4.5	18.25	1318T-47-33	1104
5.875	2.875	4.5	18.75	1318T-57-27	1138
	3.875	4.5	19.75	1318T-57-37	1206
	4.875	4.5	20.75	1318T-57-47	1274

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

X-1 = 0.875				13.375 x 20.75"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	0.875	3	11.25	1321T-17-7	807
	1.375	3	11.75	1321T-17-13	846
	1.875	3	12.25	1321T-17-17	886
2.375	1.375	3.5	12.75	1321T-23-13	897
	1.875	3.5	13.25	1321T-23-17	936
	2.375	3.5	13.75	1321T-23-23	975
2.875	1.375	3.5	13.25	1321T-27-13	936
	1.875	3.5	13.75	1321T-27-17	975
	2.375	3.5	14.25	1321T-27-23	1015
3.375	1.875	3.5	14.25	1321T-33-17	1015
	2.375	4	15.25	1321T-33-23	1065
	2.875	4	15.75	1321T-33-27	1104
3.875	1.875	4	15.25	1321T-37-17	1065
	2.375	4.5	16.25	1321T-37-23	1115
	2.875	4.5	16.75	1321T-37-27	1155
4.875	2.375	4.5	17.25	1321T-47-23	1194
	2.875	4.5	17.75	1321T-47-27	1233
	3.375	4.5	18.25	1321T-47-33	1272
5.875	2.875	4.5	18.75	1321T-57-27	1312
	3.875	4.5	19.75	1321T-57-37	1390
	4.875	4.5	20.75	1321T-57-47	1469

X-1 = 1.375				13.375 x 23.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1323T-17-13	1003
	1.875	3	12.75	1323T-17-17	1047
	2.375	3.5	13.75	1323T-17-23	1104
2.375	1.375	3.5	13.25	1323T-23-13	1060
	1.875	3.5	13.75	1323T-23-17	1104
	2.375	3.5	14.25	1323T-23-23	1149
2.875	1.375	3.5	13.75	1323T-27-13	1104
	1.875	3.5	14.25	1323T-27-17	1149
	2.375	3.5	14.75	1323T-27-23	1194
3.375	1.875	3.5	14.75	1323T-33-17	1194
	2.375	4	15.75	1323T-33-23	1251
	2.875	4	16.25	1323T-33-27	1295
3.875	1.875	4	15.75	1323T-37-17	1251
	2.375	4.5	16.75	1323T-37-23	1308
	2.875	4.5	17.25	1323T-37-27	1352
4.875	2.375	4.5	17.75	1323T-47-23	1397
	2.875	4.5	18.25	1323T-47-27	1441
	3.375	4.5	18.75	1323T-47-33	1486
5.875	2.875	4.5	19.25	1323T-57-27	1530
	3.875	4.5	20.25	1323T-57-37	1619
	4.875	4.5	21.25	1323T-57-47	1708

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.

X-1 = 1.375				13.375 x 26"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1326T-17-13	1110
	1.875	3	12.75	1326T-17-17	1159
	2.375	3.5	13.75	1326T-17-23	1222
2.375	1.375	3.5	13.25	1326T-23-13	1173
	1.875	3.5	13.75	1326T-23-17	1222
	2.375	3.5	14.25	1326T-23-23	1271
2.875	1.375	3.5	13.75	1326T-27-13	1222
	1.875	3.5	14.25	1326T-27-17	1271
	2.375	3.5	14.75	1326T-27-23	1320
3.375	1.875	3.5	14.75	1326T-33-17	1320
	2.375	4	15.75	1326T-33-23	1384
	2.875	4	16.25	1326T-33-27	1433
3.875	1.875	4	15.75	1326T-37-17	1384
	2.375	4.5	16.75	1326T-37-23	1447
	2.875	4.5	17.25	1326T-37-27	1496
4.875	2.375	4.5	17.75	1326T-47-23	1545
	2.875	4.5	18.25	1326T-47-27	1594
	3.375	4.5	18.75	1326T-47-33	1644
5.875	2.875	4.5	19.25	1326T-57-27	1693
	3.875	4.5	20.25	1326T-57-37	1791
	4.875	4.5	21.25	1326T-57-47	1890

X-1 = 1.375				13.375 x 29.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1329T-17-13	1259
	1.875	3	12.75	1329T-17-17	1315
	2.375	3.5	13.75	1329T-17-23	1386
2.375	1.375	3.5	13.25	1329T-23-13	1330
	1.875	3.5	13.75	1329T-23-17	1386
	2.375	3.5	14.25	1329T-23-23	1442
2.875	1.375	3.5	13.75	1329T-27-13	1386
	1.875	3.5	14.25	1329T-27-17	1442
	2.375	3.5	14.75	1329T-27-23	1498
3.375	1.875	3.5	14.75	1329T-33-17	1498
	2.375	4	15.75	1329T-33-23	1570
	2.875	4	16.25	1329T-33-27	1626
3.875	1.875	4	15.75	1329T-37-17	1570
	2.375	4.5	16.75	1329T-37-23	1641
	2.875	4.5	17.25	1329T-37-27	1697
4.875	2.375	4.5	17.75	1329T-47-23	1753
	2.875	4.5	18.25	1329T-47-27	1809
	3.375	4.5	18.75	1329T-47-33	1865
5.875	2.875	4.5	19.25	1329T-57-27	1921
	3.875	4.5	20.25	1329T-57-37	2032
	4.875	4.5	21.25	1329T-57-47	2145

For detailed dimensions, see corresponding size A-Series Mold Bases.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimension
- L Dimension (Leader Pin Length)
- Method of Shipment

NOTE: For 3-Plate Extension Bushings, see page 147.

14⁷/₈" T-Series Mold Bases**NO. 1 STEEL ASSEMBLIES**


All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.



For detailed dimensions,
see corresponding size
A-Series Mold Bases.



X-1 = 0.875				14.875 x 17.875	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1518T-17-13	847
	1.875	3.5	13.25	1518T-17-17	894
	2.375	3.5	13.75	1518T-17-23	931
2.375	1.375	3.5	13.25	1518T-23-13	894
	1.875	3.5	13.75	1518T-23-17	931
	2.375	3.5	14.25	1518T-23-23	969
2.875	1.375	3.5	13.75	1518T-27-13	931
	1.875	3.5	14.25	1518T-27-17	969
	2.375	3.5	14.75	1518T-27-23	1007
3.375	1.875	4	15.25	1518T-33-17	1016
	2.375	4	15.75	1518T-33-23	1054
	2.875	4.5	16.75	1518T-33-27	1101
3.875	1.875	4	15.75	1518T-37-17	1054
	2.375	4.5	16.75	1518T-37-23	1101
	2.875	4.5	17.25	1518T-37-27	1139
4.875	2.375	4.5	17.75	1518T-47-23	1176
	2.875	4.5	18.25	1518T-47-27	1214
	3.375	4.5	18.75	1518T-47-33	1252
5.875	2.875	4.5	19.25	1518T-57-27	1289
	3.875	4.5	20.25	1518T-57-37	1365
	4.875	4.5	21.25	1518T-57-47	1440
X-1 = 1.375				14.875 x 23.75	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1524T-17-13	1175
	1.875	3.5	13.75	1524T-17-17	1237
	2.375	3.5	14.25	1524T-17-23	1287
2.375	1.375	3.5	13.75	1524T-23-13	1237
	1.875	3.5	14.25	1524T-23-17	1287
	2.375	3.5	14.75	1524T-23-23	1337
2.875	1.375	3.5	14.25	1524T-27-13	1287
	1.875	3.5	14.75	1524T-27-17	1337
	2.375	3.5	15.25	1524T-27-23	1387
3.375	1.875	4	15.75	1524T-33-17	1400
	2.375	4	16.25	1524T-33-23	1450
	2.875	4.5	17.25	1524T-33-27	1513
3.875	1.875	4	16.25	1524T-37-17	1450
	2.375	4.5	17.25	1524T-37-23	1513
	2.875	4.5	17.75	1524T-37-27	1563
4.875	2.375	4.5	18.25	1524T-47-23	1613
	2.875	4.5	18.75	1524T-47-27	1663
	3.375	4.5	19.25	1524T-47-33	1713
5.875	2.875	4.5	19.75	1524T-57-27	1763
	3.875	4.5	20.75	1524T-57-37	1863
	4.875	4.5	21.75	1524T-57-47	1963
X-1 = 1.375				14.875 x 29.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1529T-17-13	1459
	1.875	3.5	13.75	1529T-17-17	1537
	2.375	3.5	14.25	1529T-17-23	1599
2.375	1.375	3.5	13.75	1529T-23-13	1537
	1.875	3.5	14.25	1529T-23-17	1599
	2.375	3.5	14.75	1529T-23-23	1661
2.875	1.375	3.5	14.25	1529T-27-13	1599
	1.875	3.5	14.75	1529T-27-17	1661
	2.375	3.5	15.25	1529T-27-23	1723
3.375	1.875	4	15.75	1529T-33-17	1739
	2.375	4	16.25	1529T-33-23	1801
	2.875	4.5	17.25	1529T-33-27	1879
3.875	1.875	4	16.25	1529T-37-17	1801
	2.375	4.5	17.25	1529T-37-23	1879
	2.875	4.5	17.75	1529T-37-27	1941
4.875	2.375	4.5	18.25	1529T-47-23	2003
	2.875	4.5	18.75	1529T-47-27	2065
	3.375	4.5	19.25	1529T-47-33	2128
5.875	2.875	4.5	19.75	1529T-57-27	2190
	3.875	4.5	20.75	1529T-57-37	2314
	4.875	4.5	21.75	1529T-57-47	2438

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- L Dimension (Leader Pin Length)
- Method of Shipment

NOTE: For 3-Plate Extension Bushings,
see page 147.

15⁷/₈" T-Series Mold Bases

NO. 1 STEEL ASSEMBLIES

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.

X-1 = 0.875				15.875 × 16"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1616T-17-13	808
	1.875	3.5	13.25	1616T-17-17	852
	2.375	3.5	13.75	1616T-17-23	888
2.375	1.375	3.5	13.25	1616T-23-13	852
	1.875	3.5	13.75	1616T-23-17	888
	2.375	3.5	14.25	1616T-23-23	924
2.875	1.375	3.5	13.75	1616T-27-13	888
	1.875	3.5	14.25	1616T-27-17	924
	2.375	3.5	14.75	1616T-27-23	960
3.375	1.875	4	15.25	1616T-33-17	969
	2.375	4	15.75	1616T-33-23	1005
	2.875	4.5	16.75	1616T-33-27	1049
3.875	1.875	4	15.75	1616T-37-17	1005
	2.375	4.5	16.75	1616T-37-23	1049
	2.875	4.5	17.25	1616T-37-27	1085
4.875	2.375	4.5	17.75	1616T-47-23	1121
	2.875	4.5	18.25	1616T-47-27	1157
	3.375	4.5	18.75	1616T-47-33	1193
5.875	2.875	4.5	19.25	1616T-57-27	1229
	3.875	4.5	20.25	1616T-57-37	1301
	4.875	4.5	21.25	1616T-57-47	1373

X-1 = 1.375				15.875 × 23.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1623T-17-13	1239
	1.875	3.5	13.75	1623T-17-17	1304
	2.375	3.5	14.25	1623T-17-23	1357
2.375	1.375	3.5	13.75	1623T-23-13	1304
	1.875	3.5	14.25	1623T-23-17	1357
	2.375	3.5	14.75	1623T-23-23	1410
2.875	1.375	3.5	14.25	1623T-27-13	1357
	1.875	3.5	14.75	1623T-27-17	1410
	2.375	3.5	15.25	1623T-27-23	1463
3.375	1.875	4	15.75	1623T-33-17	1475
	2.375	4	16.25	1623T-33-23	1528
	2.875	4.5	17.25	1623T-33-27	1593
3.875	1.875	4	16.25	1623T-37-17	1528
	2.375	4.5	17.25	1623T-37-23	1593
	2.875	4.5	17.75	1623T-37-27	1646
4.875	2.375	4.5	18.25	1623T-47-23	1699
	2.875	4.5	18.75	1623T-47-27	1752
	3.375	4.5	19.25	1623T-47-33	1805
5.875	2.875	4.5	19.75	1623T-57-27	1858
	3.875	4.5	20.75	1623T-57-37	1963
	4.875	4.5	21.75	1623T-57-47	2069

X-1 = 1.375				15.875 × 29.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1629T-17-13	1555
	1.875	3.5	13.75	1629T-17-17	1637
	2.375	3.5	14.25	1629T-17-23	1703
2.375	1.375	3.5	13.75	1629T-23-13	1637
	1.875	3.5	14.25	1629T-23-17	1703
	2.375	3.5	14.75	1629T-23-23	1770
2.875	1.375	3.5	14.25	1629T-27-13	1703
	1.875	3.5	14.75	1629T-27-17	1770
	2.375	3.5	15.25	1629T-27-23	1836
3.375	1.875	4	15.75	1629T-33-17	1852
	2.375	4	16.25	1629T-33-23	1918
	2.875	4.5	17.25	1629T-33-27	2000
3.875	1.875	4	16.25	1629T-37-17	1918
	2.375	4.5	17.25	1629T-37-23	2000
	2.875	4.5	17.75	1629T-37-27	2066
4.875	2.375	4.5	18.25	1629T-47-23	2133
	2.875	4.5	18.75	1629T-47-27	2199
	3.375	4.5	19.25	1629T-47-33	2266
5.875	2.875	4.5	19.75	1629T-57-27	2332
	3.875	4.5	20.75	1629T-57-37	2465
	4.875	4.5	21.75	1629T-57-47	2597

X-1 = 0.875				15.875 × 20"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.25	1620T-17-13	1009
	1.875	3.5	13.25	1620T-17-17	1065
	2.375	3.5	13.75	1620T-17-23	1110
2.375	1.375	3.5	13.25	1620T-23-13	1065
	1.875	3.5	13.75	1620T-23-17	1110
	2.375	3.5	14.25	1620T-23-23	1155
2.875	1.375	3.5	13.75	1620T-27-13	1110
	1.875	3.5	14.25	1620T-27-17	1155
	2.375	3.5	14.75	1620T-27-23	1200
3.375	1.875	4	15.25	1620T-33-17	1211
	2.375	4	15.75	1620T-33-23	1256
	2.875	4.5	16.75	1620T-33-27	1311
3.875	1.875	4	15.75	1620T-37-17	1256
	2.375	4.5	16.75	1620T-37-23	1311
	2.875	4.5	17.25	1620T-37-27	1356
4.875	2.375	4.5	17.75	1620T-47-23	1401
	2.875	4.5	18.25	1620T-47-27	1446
	3.375	4.5	18.75	1620T-47-33	1491
5.875	2.875	4.5	19.25	1620T-57-27	1536
	3.875	4.5	20.25	1620T-57-37	1626
	4.875	4.5	21.25	1620T-57-47	1716

X-1 = 1.375				15.875 × 26"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1626T-17-13	1371
	1.875	3.5	13.75	1626T-17-17	1443
	2.375	3.5	14.25	1626T-17-23	1501
2.375	1.375	3.5	13.75	1626T-23-13	1443
	1.875	3.5	14.25	1626T-23-17	1501
	2.375	3.5	14.75	1626T-23-23	1560
2.875	1.375	3.5	14.25	1626T-27-13	1501
	1.875	3.5	14.75	1626T-27-17	1560
	2.375	3.5	15.25	1626T-27-23	1618
3.375	1.875	4	15.75	1626T-33-17	1632
	2.375	4	16.25	1626T-33-23	1691
	2.875	4.5	17.25	1626T-33-27	1763
3.875	1.875	4	16.25	1626T-37-17	1691
	2.375	4.5	17.25	1626T-37-23	1763
	2.875	4.5	17.75	1626T-37-27	1821
4.875	2.375	4.5	18.25	1626T-47-23	1880
	2.875	4.5	18.75	1626T-47-27	1938
	3.375	4.5	19.25	1626T-47-33	1997
5.875	2.875	4.5	19.75	1626T-57-27	2055
	3.875	4.5	20.75	1626T-57-37	2172
	4.875	4.5	21.75	1626T-57-47	2289

X-1 = 1.375				15.875 × 35.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1635T-17-13	1871
	1.875	3.5	13.75	1635T-17-17	1970
	2.375	3.5	14.25	1635T-17-23	2050
2.375	1.375	3.5	13.75	1635T-23-13	1970
	1.875	3.5	14.25	1635T-23-17	2050
	2.375	3.5	14.75	1635T-23-23	2130
2.875	1.375	3.5	14.25	1635T-27-13	2050
	1.875	3.5	14.75	1635T-27-17	2130
	2.375	3.5	15.25	1635T-27-23	2209
3.375	1.875	4	15.75	1635T-33-17	2228
	2.375	4	16.25	1635T-33-23	2308
	2.875	4.5	17.25	1635T-33-27	2407
3.875	1.875	4	16.25	1635T-37-17	2308
	2.375	4.5	17.25	1635T-37-23	2407
	2.875	4.5	17.75	1635T-37-27	2487
4.875	2.375	4.5	18.25	1635T-47-23	2566
	2.875	4.5	18.75	1635T-47-27	2646
	3.375	4.5	19.25	1635T-47-33	2726
5.875	2.875	4.5	19.75	1635T-57-27	2806
	3.875	4.5	20.75	1635T-57-37	2966
	4.875	4.5	21.75	1635T-57-47	3125

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- L Dimension (Leader Pin Length)
- Method of Shipment

For detailed dimensions, see corresponding size A-Series Mold Bases.

NOTE: For 3-Plate Extension Bushings, see page 147.

16½" T-Series Mold Bases

NO. 1 STEEL ASSEMBLIES

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No.3 Steel.


NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.



X-1 = 1.375				16.5 × 23.75	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1724T-17-13	1300
	1.875	3.5	13.75	1724T-17-17	1369
	2.375	3.5	14.25	1724T-17-23	1424
2.375	1.375	3.5	13.75	1724T-23-13	1369
	1.875	3.5	14.25	1724T-23-17	1424
	2.375	3.5	14.75	1724T-23-23	1480
2.875	1.375	3.5	14.25	1724T-27-13	1424
	1.875	3.5	14.75	1724T-27-17	1480
	2.375	3.5	15.25	1724T-27-23	1535
3.375	1.875	4	15.75	1724T-33-17	1548
	2.375	4	16.25	1724T-33-23	1603
	2.875	4.5	17.25	1724T-33-27	1671
3.875	1.875	4	16.25	1724T-37-17	1603
	2.375	4.5	17.25	1724T-37-23	1671
	2.875	4.5	17.75	1724T-37-27	1727
4.875	2.375	4.5	18.25	1724T-47-23	1782
	2.875	4.5	18.75	1724T-47-27	1838
	3.375	4.5	19.25	1724T-47-33	1893
5.875	2.875	4.5	19.75	1724T-57-27	1949
	3.875	4.5	20.75	1724T-57-37	2060
	4.875	4.5	21.75	1724T-57-47	2171

X-1 = 1.375				16.5 × 29.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1729T-17-13	1615
	1.875	3.5	13.75	1729T-17-17	1700
	2.375	3.5	14.25	1729T-17-23	1769
2.375	1.375	3.5	13.75	1729T-23-13	1700
	1.875	3.5	14.25	1729T-23-17	1769
	2.375	3.5	14.75	1729T-23-23	1838
2.875	1.375	3.5	14.25	1729T-27-13	1769
	1.875	3.5	14.75	1729T-27-17	1838
	2.375	3.5	15.25	1729T-27-23	1907
3.375	1.875	4	15.75	1729T-33-17	1922
	2.375	4	16.25	1729T-33-23	1991
	2.875	4.5	17.25	1729T-33-27	2076
3.875	1.875	4	16.25	1729T-37-17	1991
	2.375	4.5	17.25	1729T-37-23	2076
	2.875	4.5	17.75	1729T-37-27	2145
4.875	2.375	4.5	18.25	1729T-47-23	2214
	2.875	4.5	18.75	1729T-47-27	2283
	3.375	4.5	19.25	1729T-47-33	2352
5.875	2.875	4.5	19.75	1729T-57-27	2421
	3.875	4.5	20.75	1729T-57-37	2559
	4.875	4.5	21.75	1729T-57-47	2696



For detailed dimensions, see corresponding size A-Series Mold Bases.

NOTE: For 3-Plate Extension Bushings, see page 147.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- L Dimension (Leader Pin Length)
- Method of Shipment

17⁷/₈" T-Series Mold Bases

NO. 1 STEEL ASSEMBLIES

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No.3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.

X-1 = 1.375				17.875 x 18"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1818T-17-13	1066
	1.875	3	13.25	1818T-17-17	1112
	2.375	3.5	14.25	1818T-17-23	1167
2.375	1.375	3.5	13.75	1818T-23-13	1122
	1.875	3.5	14.25	1818T-23-17	1167
	2.375	3.5	14.75	1818T-23-23	1213
2.875	1.375	3.5	14.25	1818T-27-13	1167
	1.875	3.5	14.75	1818T-27-17	1213
	2.375	3.5	15.25	1818T-27-23	1258
3.375	1.875	4	15.75	1818T-33-17	1268
	2.375	4	16.25	1818T-33-23	1313
	2.875	4.5	17.25	1818T-33-27	1369
3.875	1.875	4	16.25	1818T-37-17	1313
	2.375	4.5	17.25	1818T-37-23	1369
	2.875	4.5	17.75	1818T-37-27	1414
4.875	2.375	4.5	18.25	1818T-47-23	1460
	2.875	4.5	18.75	1818T-47-27	1505
	3.375	4.5	19.25	1818T-47-33	1551
5.875	2.875	4.5	19.75	1818T-57-27	1596
	3.875	4.5	20.75	1818T-57-37	1688
	4.875	4.5	21.75	1818T-57-47	1779

X-1 = 1.375				17.875 x 23.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1823T-17-13	1392
	1.875	3	13.25	1823T-17-17	1452
	2.375	3.5	14.25	1823T-17-23	1524
2.375	1.375	3.5	13.75	1823T-23-13	1464
	1.875	3.5	14.25	1823T-23-17	1524
	2.375	3.5	14.75	1823T-23-23	1583
2.875	1.375	3.5	14.25	1823T-27-13	1524
	1.875	3.5	14.75	1823T-27-17	1583
	2.375	3.5	15.25	1823T-27-23	1643
3.375	1.875	4	15.75	1823T-33-17	1655
	2.375	4	16.25	1823T-33-23	1714
	2.875	4.5	17.25	1823T-33-27	1786
3.875	1.875	4	16.25	1823T-37-17	1714
	2.375	4.5	17.25	1823T-37-23	1786
	2.875	4.5	17.75	1823T-37-27	1846
4.875	2.375	4.5	18.25	1823T-47-23	1905
	2.875	4.5	18.75	1823T-47-27	1965
	3.375	4.5	19.25	1823T-47-33	2024
5.875	2.875	4.5	19.75	1823T-57-27	2084
	3.875	4.5	20.75	1823T-57-37	2203
	4.875	4.5	21.75	1823T-57-47	2322

X-1 = 1.375				17.875 x 29.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1829T-17-13	1747
	1.875	3	13.25	1829T-17-17	1822
	2.375	3.5	14.25	1829T-17-23	1912
2.375	1.375	3.5	13.75	1829T-23-13	1838
	1.875	3.5	14.25	1829T-23-17	1912
	2.375	3.5	14.75	1829T-23-23	1987
2.875	1.375	3.5	14.25	1829T-27-13	1912
	1.875	3.5	14.75	1829T-27-17	1987
	2.375	3.5	15.25	1829T-27-23	2062
3.375	1.875	4	15.75	1829T-33-17	2077
	2.375	4	16.25	1829T-33-23	2152
	2.875	4.5	17.25	1829T-33-27	2242
3.875	1.875	4	16.25	1829T-37-17	2152
	2.375	4.5	17.25	1829T-37-23	2242
	2.875	4.5	17.75	1829T-37-27	2317
4.875	2.375	4.5	18.25	1829T-47-23	2392
	2.875	4.5	18.75	1829T-47-27	2466
	3.375	4.5	19.25	1829T-47-33	2541
5.875	2.875	4.5	19.75	1829T-57-27	2616
	3.875	4.5	20.75	1829T-57-37	2765
	4.875	4.5	21.75	1829T-57-47	2915

X-1 = 1.375				17.875 x 20"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1820T-17-13	1185
	1.875	3	13.25	1820T-17-17	1235
	2.375	3.5	14.25	1820T-17-23	1297
2.375	1.375	3.5	13.75	1820T-23-13	1246
	1.875	3.5	14.25	1820T-23-17	1297
	2.375	3.5	14.75	1820T-23-23	1347
2.875	1.375	3.5	14.25	1820T-27-13	1297
	1.875	3.5	14.75	1820T-27-17	1347
	2.375	3.5	15.25	1820T-27-23	1398
3.375	1.875	4	15.75	1820T-33-17	1409
	2.375	4	16.25	1820T-33-23	1459
	2.875	4.5	17.25	1820T-33-27	1521
3.875	1.875	4	16.25	1820T-37-17	1459
	2.375	4.5	17.25	1820T-37-23	1521
	2.875	4.5	17.75	1820T-37-27	1571
4.875	2.375	4.5	18.25	1820T-47-23	1622
	2.875	4.5	18.75	1820T-47-27	1672
	3.375	4.5	19.25	1820T-47-33	1723
5.875	2.875	4.5	19.75	1820T-57-27	1774
	3.875	4.5	20.75	1820T-57-37	1875
	4.875	4.5	21.75	1820T-57-47	1976

X-1 = 1.375				17.875 x 26"	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1826T-17-13	1540
	1.875	3	13.25	1826T-17-17	1606
	2.375	3.5	14.25	1826T-17-23	1686
2.375	1.375	3.5	13.75	1826T-23-13	1620
	1.875	3.5	14.25	1826T-23-17	1686
	2.375	3.5	14.75	1826T-23-23	1751
2.875	1.375	3.5	14.25	1826T-27-13	1686
	1.875	3.5	14.75	1826T-27-17	1751
	2.375	3.5	15.25	1826T-27-23	1817
3.375	1.875	4	15.75	1826T-33-17	1831
	2.375	4	16.25	1826T-33-23	1897
	2.875	4.5	17.25	1826T-33-27	1976
3.875	1.875	4	16.25	1826T-37-17	1897
	2.375	4.5	17.25	1826T-37-23	1976
	2.875	4.5	17.75	1826T-37-27	2042
4.875	2.375	4.5	18.25	1826T-47-23	2108
	2.875	4.5	18.75	1826T-47-27	2174
	3.375	4.5	19.25	1826T-47-33	2240
5.875	2.875	4.5	19.75	1826T-57-27	2306
	3.875	4.5	20.75	1826T-57-37	2437
	4.875	4.5	21.75	1826T-57-47	2569

X-1 = 1.375				17.875 x 35.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1835T-17-13	2103
	1.875	3	13.25	1835T-17-17	2193
	2.375	3.5	14.25	1835T-17-23	2301
2.375	1.375	3.5	13.75	1835T-23-13	2211
	1.875	3.5	14.25	1835T-23-17	2301
	2.375	3.5	14.75	1835T-23-23	2391
2.875	1.375	3.5	14.25	1835T-27-13	2301
	1.875	3.5	14.75	1835T-27-17	2391
	2.375	3.5	15.25	1835T-27-23	2481
3.375	1.875	4	15.75	1835T-33-17	2500
	2.375	4	16.25	1835T-33-23	2590
	2.875	4.5	17.25	1835T-33-27	2699
3.875	1.875	4	16.25	1835T-37-17	2590
	2.375	4.5	17.25	1835T-37-23	2699
	2.875	4.5	17.75	1835T-37-27	2788
4.875	2.375	4.5	18.25	1835T-47-23	2878
	2.875	4.5	18.75	1835T-47-27	2968
	3.375	4.5	19.25	1835T-47-33	3058
5.875	2.875	4.5	19.75	1835T-57-27	3148
	3.875	4.5	20.75	1835T-57-37	3328
	4.875	4.5	21.75	1835T-57-47	3508

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- L Dimension (Leader Pin Length)
- Method of Shipment

For detailed dimensions, see corresponding size "Series Mold Bases.

NOTE: For 3-Plate Extension Bushings, see page 147.

19½" T-Series Mold Bases

NO. 1 STEEL ASSEMBLIES


All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES

All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.



For detailed dimensions, see corresponding size A-Series Mold Bases.

X-1 = 1.375				19.5 × 23.75	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1924T-17-13	1533
	1.875	3	13.25	1924T-17-17	1598
	2.375	3.5	14.25	1924T-17-23	1676
2.375	1.375	3.5	13.75	1924T-23-13	1611
	1.875	3.5	14.25	1924T-23-17	1676
	2.375	3.5	14.75	1924T-23-23	1742
2.875	1.375	3.5	14.25	1924T-27-13	1676
	1.875	3.5	14.75	1924T-27-17	1742
	2.375	3.5	15.25	1924T-27-23	1808
3.375	1.875	4	15.75	1924T-33-17	1820
	2.375	4	16.25	1924T-33-23	1886
	2.875	4.5	17.25	1924T-33-27	1964
3.875	1.875	4	16.25	1924T-37-17	1886
	2.375	4.5	17.25	1924T-37-23	1964
	2.875	4.5	17.75	1924T-37-27	2030
4.875	2.375	4.5	18.25	1924T-47-23	2095
	2.875	4.5	18.75	1924T-47-27	2161
	3.375	4.5	19.25	1924T-47-33	2226
5.875	2.875	4.5	19.75	1924T-57-27	2292
	3.875	4.5	20.75	1924T-57-37	2423
	4.875	4.5	21.75	1924T-57-47	2554

X-1 = 1.375				19.5 × 29.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1929T-17-13	1903
	1.875	3	13.25	1929T-17-17	1985
	2.375	3.5	14.25	1929T-17-23	2082
2.375	1.375	3.5	13.75	1929T-23-13	2001
	1.875	3.5	14.25	1929T-23-17	2082
	2.375	3.5	14.75	1929T-23-23	2164
2.875	1.375	3.5	14.25	1929T-27-13	2082
	1.875	3.5	14.75	1929T-27-17	2164
	2.375	3.5	15.25	1929T-27-23	2245
3.375	1.875	4	15.75	1929T-33-17	2261
	2.375	4	16.25	1929T-33-23	2342
	2.875	4.5	17.25	1929T-33-27	2439
3.875	1.875	4	16.25	1929T-37-17	2342
	2.375	4.5	17.25	1929T-37-23	2439
	2.875	4.5	17.75	1929T-37-27	2521
4.875	2.375	4.5	18.25	1929T-47-23	2602
	2.875	4.5	18.75	1929T-47-27	2684
	3.375	4.5	19.25	1929T-47-33	2765
5.875	2.875	4.5	19.75	1929T-57-27	2847
	3.875	4.5	20.75	1929T-57-37	3010
	4.875	4.5	21.75	1929T-57-47	3173

X-1 = 1.375				19.5 × 35.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	12.75	1935T-17-13	2291
	1.875	3	13.25	1935T-17-17	2389
	2.375	3.5	14.25	1935T-17-23	2506
2.375	1.375	3.5	13.75	1935T-23-13	2408
	1.875	3.5	14.25	1935T-23-17	2506
	2.375	3.5	14.75	1935T-23-23	2604
2.875	1.375	3.5	14.25	1935T-27-13	2506
	1.875	3.5	14.75	1935T-27-17	2604
	2.375	3.5	15.25	1935T-27-23	2702
3.375	1.875	4	15.75	1935T-33-17	2721
	2.375	4	16.25	1935T-33-23	2819
	2.875	4.5	17.25	1935T-33-27	2936
3.875	1.875	4	16.25	1935T-37-17	2819
	2.375	4.5	17.25	1935T-37-23	2936
	2.875	4.5	17.75	1935T-37-27	3034
4.875	2.375	4.5	18.25	1935T-47-23	3132
	2.875	4.5	18.75	1935T-47-27	3230
	3.375	4.5	19.25	1935T-47-33	3328
5.875	2.875	4.5	19.75	1935T-57-27	3426
	3.875	4.5	20.75	1935T-57-37	3622
	4.875	4.5	21.75	1935T-57-47	3818

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- L Dimension (Leader Pin Length)
- Method of Shipment

NOTE: For 3-Plate Extension Bushings, see page 147.

23³/₄" T-Series Mold Bases**NO. 1 OR NO. 2 STEEL ASSEMBLIES**

All plates are No. 1 Steel.

NO. 3 STEEL ASSEMBLIES


All plates above ejector housing are No. 3 Steel.

NO. 7 STEEL ASSEMBLIES

All plates are No. 7 Steel.



NOTE: Clamp slots for 23.75" wide bases will be type B, not type D as shown in photo.



For detailed dimensions, see corresponding size A-Series Mold Bases.

X-1 = 1.375				23.75 × 23.75	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	13.75	2424T-17-13	2021
	1.875	3	14.25	2424T-17-17	2101
	2.375	3.5	15.25	2424T-17-23	2194
2.375	1.375	3.5	14.75	2424T-23-13	2114
	1.875	3.5	15.25	2424T-23-17	2194
	2.375	3.5	15.75	2424T-23-23	2274
2.875	1.375	3.5	15.25	2424T-27-13	2194
	1.875	3.5	15.75	2424T-27-17	2274
	2.375	3.5	16.25	2424T-27-23	2353
3.375	1.875	4	16.75	2424T-33-17	2366
	2.375	4	17.25	2424T-33-23	2446
	2.875	4.5	18.25	2424T-33-27	2538
3.875	1.875	4	17.25	2424T-37-17	2446
	2.375	4.5	18.25	2424T-37-23	2538
	2.875	4.5	18.75	2424T-37-27	2618
4.875	2.375	4.5	19.25	2424T-47-23	2698
	2.875	4.5	19.75	2424T-47-27	2778
	3.375	4.5	20.25	2424T-47-33	2858
5.875	2.875	4.5	20.75	2424T-57-27	2938
	3.875	4.5	21.75	2424T-57-37	3098
	4.875	4.5	22.75	2424T-57-47	3258

X-1 = 1.375				23.75 × 29.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	13.75	2429T-17-13	2510
	1.875	3	14.25	2429T-17-17	2610
	2.375	3.5	15.25	2429T-17-23	2725
2.375	1.375	3.5	14.75	2429T-23-13	2625
	1.875	3.5	15.25	2429T-23-17	2725
	2.375	3.5	15.75	2429T-23-23	2824
2.875	1.375	3.5	15.25	2429T-27-13	2725
	1.875	3.5	15.75	2429T-27-17	2824
	2.375	3.5	16.25	2429T-27-23	2923
3.375	1.875	4	16.75	2429T-33-17	2939
	2.375	4	17.25	2429T-33-23	3038
	2.875	4.5	18.25	2429T-33-27	3153
3.875	1.875	4	17.25	2429T-37-17	3038
	2.375	4.5	18.25	2429T-37-23	3153
	2.875	4.5	18.75	2429T-37-27	3252
4.875	2.375	4.5	19.25	2429T-47-23	3351
	2.875	4.5	19.75	2429T-47-27	3451
	3.375	4.5	20.25	2429T-47-33	3550
5.875	2.875	4.5	20.75	2429T-57-27	3649
	3.875	4.5	21.75	2429T-57-37	3848
	4.875	4.5	22.75	2429T-57-47	4046

X-1 = 1.375				23.75 × 35.5	
X-2	B	C	H	ITEM NUMBER	NET WT.
1.875	1.375	3	13.75	2435T-17-13	3021
	1.875	3	14.25	2435T-17-17	3140
	2.375	3.5	15.25	2435T-17-23	3279
2.375	1.375	3.5	14.75	2435T-23-13	3159
	1.875	3.5	15.25	2435T-23-17	3279
	2.375	3.5	15.75	2435T-23-23	3398
2.875	1.375	3.5	15.25	2435T-27-13	3279
	1.875	3.5	15.75	2435T-27-17	3398
	2.375	3.5	16.25	2435T-27-23	3518
3.375	1.875	4	16.75	2435T-33-17	3536
	2.375	4	17.25	2435T-33-23	3656
	2.875	4.5	18.25	2435T-33-27	3794
3.875	1.875	4	17.25	2435T-37-17	3656
	2.375	4.5	18.25	2435T-37-23	3794
	2.875	4.5	18.75	2435T-37-27	3914
4.875	2.375	4.5	19.25	2435T-47-23	4033
	2.875	4.5	19.75	2435T-47-27	4152
	3.375	4.5	20.25	2435T-47-33	4272
5.875	2.875	4.5	20.75	2435T-57-27	4391
	3.875	4.5	21.75	2435T-57-37	4630
	4.875	4.5	22.75	2435T-57-47	4869

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3, or No. 7 Steel
- Locating Ring Item Number
- E, O and R Dimensions
- L Dimension (Leader Pin Length)
- Method of Shipment

NOTE: For 3-Plate Extension Bushings, see page 147.

3-Plate Extension Bushings


Three-plate extension bushings can save material, reduce cycle time and help prevent runner hang-ups in 3-plate molds.



Runner Stripper
Plate Bushing
TEB-0001

NOTES:


- 1.Stripper plate bushing TEB-0001 is used with all small and large extension nozzle bushings.
- 2.Appropriate S.H.C.S. are included with all bushings TEB-0001 thru TEB-0009).
- 3.Select small or large bushing based on A-clamping plate (A.C.P.) thickness, X-1 stripper plate thickness, machine nozzle spherical radius and machine nozzle clearance requirements.



ITEM NUMBER	R SPH. RAD	Ø A	Ø B	Ø C	E	F	G	H	J	K	L
TEB-0002	1/2	4.490	2.375	3.120	.375	2.265	1.377	1.875	2.640	#10-24 x 7/8 LONG (2) INCLUDED	1.781
TEB-0003	3/4							1.812			
TEB-0004	1/2							2.375			
TEB-0005	3/4							2.312	3.140		
TEB-0006	1/2	5.490	3.250	3.932	.750	2.765	1.877	2.375	3.140	5/16-18 x 7/8 LONG (2) INCLUDED	2.312
TEB-0007	3/4							2.312			
TEB-0008	1/2							2.875			
TEB-0009	3/4							2.812	3.640		

Ball Bushings for Floating Plates*

Ball Bushings are a highly effective means of reducing frictional drag in floating plates within a mold. Multiple-opening molds, with heavy floating X-plates, are the most frequent application for either Lineal type or Pre-Loaded type Ball Bushings.



General Dimensions for DME Pre-Loaded Type Ball Bushings*

NOMINAL SIZE	3/4	1"	1 1/4	1 1/2	1 3/4	2"
A (PIN DIA.)	.753	1.003	1.253	1.503	1.753	2.003
B (BUSHING DIA.)	1.387	1.717	2.107	2.437	2.747	3.162
C (BUSHING LENGTH)	1 3/4 TO 6"	2" TO 7"	2 1/2 TO 9"	3" TO 12"	3" TO 13"	3" TO 14"
D (1/4 INCREMENT RETAINER LENGTH)	1 1/2" TO 2"	1 1/2 TO 2 1/4	2" TO 3"	2 1/2 TO 3 1/2	2 3/4 TO 4"	3 1/4 TO 4 1/4
M (PIN LENGTH)	3" TO 6"	3 3/4 TO 9"	4 1/2 TO 12"	4 1/2 TO 14"	5" TO 17"	5 1/2 TO 18"

NOTES:

Specifications shown are for DME precision grade.

Due to the larger O.D. of the bushing counterbore required, ball bushings cannot be installed in standard leader pin locations in the mold base assembly.

General Dimensions for Thomson Lineal Type Ball Bushings

BUSHING IT	A-122026	A-162536	A-203242	A-243848	A-324864
A (PIN DIA.)	.750	1.000	1.250	1.500	2.000
B (BUSHING DIA.)	1.250	1.5625	2.000	2.375	3.000
C (BUSHING LENGTH)	1.625	2.250	2.625	3.000	4.000
RETAINER RING ITEM NUMBER	W-750	W-1000	W-1250	W-1500	W-2000
D	1.062	1.625	1.875	2.250	3.000
E	1.620	2.040	2.500	2.910	3.600
COUNTERBORE DIA. (FOR RETAINER RING)	1.69	2.10	2.55	3.01	3.69

NOTES:

Specifications shown are for Thomson precision series A.

Two rings are required for each bushing.

Due to the larger O.D. of the bushing counterbore required, ball bushings usually cannot be installed in standard leader pin locations in the mold base assembly.

* THESE ARE SPECIAL ORDER ITEMS ONLY.

DME Small and Shuttle Mold Bases

HIGH-QUALITY, ECONOMICAL
MOLD BASE ASSEMBLIES
FOR PROTOTYPE OR
PRODUCTION RUNS




Small and Shuttle Mold Bases

Table of Contents

<i>Small Mold Base Adapter Plates.....</i>	<i>150</i>
<i>Custom Adapter Plates.....</i>	<i>151</i>
<i>56U3 Mold Bases</i>	<i>152</i>
<i>58U2 Mold Bases</i>	<i>153</i>
<i>58U3 Mold Bases</i>	<i>154</i>
<i>68J Mold Base</i>	<i>155</i>
<i>68SH Shuttle Mold Base.....</i>	<i>156-157</i>
<i>810SH Shuttle Mold Base</i>	<i>158-159</i>
<i>Metric Equivalents & Conversions</i>	<i>160</i>

Small Mold Base Bolster/Adapter/Platen Plates



DME No. 3 Steel

With DME Small Mold Base Bolster Plates You Can...

Lower your mold costs

Only one set of low cost Bolster Plates is required for each injection molding machine. The plates can become a permanent part of your press platen...or can easily be removed to allow installation of larger mold bases. The Bolster/Platen Plates can also be moved to another press to meet your production requirements. DME Small Mold Bases provide the highest quality, most economical mold base assemblies for either short runs or production runs. Cavity and support plates are made from DME No. 3 cavity steel.

Change mold bases in minutes


With the DME exclusive Bolster/Platen Plate System, standard 5"x 6" U and 5"x 8" U Series Mold Bases can be easily changed in 10 minutes or less. Costly machine downtime is reduced to a minimum.

Increase your profits

The DME Bolster Plate System provides economic manufacturing for greater profitability. The unique system lends itself to minimum cavity, high-speed cycle operations. Fast interchangeability of mold bases makes short runs just as profitable as long runs... no costly fill-ins!


DME Bolster/Platen Plates are:

- ① Pre-drilled and tapped to match platen holes
- ② Pre-machined with clearance holes for knockout rods
- ③ Pre-drilled and tapped to match mounting holes on DME 5"x 6" U series mold bases... with precision dowels for fast, accurate alignment. (One dowel is off-set to prevent improper installation.)
- ④ Completely machined to accommodate your choice of sprue bushing and locating ring.



Custom Designed Standard Universal Bolster/Adapter Plates – AP-5658-SET

DME No. 3 Steel



Item Number: AP-5658-SET*

***Consists of:**

ITEM	LENGTH	WIDTH	THICKNESS	NET WT.
(1) 5658S-AP-2 (SPRUE SIDE)	9.875	7.875	.875	20
(1) 5658E-AP-2 (EJECTOR SIDE)	9.875	7.875	.875	20

NOTE: Sprue bushings are supplied with DME Small mold bases. Plates MAY be ordered separately.

5" x 6" U 3-Plate Mold Bases – 56U3

These 3-plate assemblies are designed for use with DME Universal Adapter Plates.

Ejector stroke data


C = (height of riser) = 1.625

S = (max. stroke of ejector bar) = .750



WHEN ORDERING PLEASE SPECIFY:

- Quantity & Item Number
- Type of Sprue Bushing ("U", "UV" or "UR" Series)
see DME Sprue Bushings
- O & R Dimensions
O = .15625, .21875 or .28125
R = .500 or .750 ("U" Series)
500 ("UV" Series Standard)
or .750 ("UV" Series Special)
No spherical radius on "UR" Series
- Method of Shipment



A	B	ITEM NUMBER	H	OVERALL ASSEMBLY HEIGHT INCLUDING ADAPTER PLATES	NET WT.
7/8	7/8	56U3-7-7	45/8	63/8	37
7/8	13/8	56U3-7-13	51/8	67/8	41
7/8	17/8	56U3-7-17	55/8	73/8	46
13/8	7/8	56U3-13-7	51/8	67/8	41
13/8	13/8	56U3-13-13	55/8	73/8	46

A	B	ITEM NUMBER	H	OVERALL ASSEMBLY HEIGHT INCLUDING ADAPTER PLATES	NET WT.
13/8	17/8	56U3-13-17	61/8	77/8	37
17/8	7/8	56U3-17-7	55/8	73/8	46
17/8	13/8	56U3-17-13	61/8	77/8	50
13/8	17/8	56U3-17-17	65/8	83/8	54

5" x 8" U 2-Plate Mold Bases – 58U2


**These 2 & 3 Plate Assemblies
are designed for use with
DME Universal Adapter Plates**

General Dimensions

**O = Small Dia. of Sprue Bushing
Orifice .15625, .21875 or .28125**
**R = Spherical Radius of
Sprue Bushing .500 or .750
(see item 3 to the right)**

**WHEN ORDERING PLEASE SPECIFY:**

1. Quantity & Item Number
2. Type of Sprue Bushing
("U", "UV" or "UR" Series)
see DME Sprue Bushings
3. O & R Dimensions
O = .15625, .21875 or .28125
R = .500 or .750 ("U" Series)
500 ("UV" Series Standard)
or .750 ("UV" Series Special)
No spherical radius on "UR" Series
4. Method of Shipment



2-Plate Assembly

A	ITEM NUMBER	H	OVERALL ASSEMBLY HEIGHT INCLUDING ADAPTER PLATES	NET WT.
7/8	58U2-7	3 3/4	5 1/2	37
1 3/8	58U2-13	4 1/4	6	43
1 7/8	58U2-17	4 3/4	6 1/2	49


All 2 & 3-Plate assemblies listed are supplied complete with mounting and locating holes to match DME Universal Adapter Plates, and Standard Sprue Bushing specified. Cavity plates are made from DME No. 3 Steel.

NOTE: For 58U Plates and housings, see Mold Plates section.



S = (max. stroke of ejector bar) = .750

These 3-plate assemblies are designed for use with DME adapter plates.




3-Plate Assembly

A	B	ITEM NUMBER	H	OVERALL ASSEMBLY HEIGHT INCLUDING ADAPTER PLATES	NET WT.
7/8	7/8	58U3-7-7	45/8	63/8	47
7/8	13/8	58U3-7-13	51/8	67/8	53
7/8	17/8	58U3-7-17	55/8	73/8	58
13/8	7/8	58U3-13-7	51/8	67/8	53
13/8	13/8	58U3-13-13	55/8	73/8	58

A	B	ITEM NUMBER	H	OVERALL ASSEMBLY HEIGHT INCLUDING ADAPTER PLATES	NET WT.
1 $\frac{3}{8}$	1 $\frac{7}{8}$	58U3-13-17	6 $\frac{1}{8}$	7 $\frac{7}{8}$	64
1 $\frac{7}{8}$	7 $\frac{1}{8}$	58U3-17-7	5 $\frac{5}{8}$	7 $\frac{3}{8}$	58
1 $\frac{7}{8}$	1 $\frac{3}{8}$	58U3-17-13	6 $\frac{1}{8}$	7 $\frac{7}{8}$	64
1 $\frac{3}{8}$	1 $\frac{7}{8}$	58U3-17-17	6 $\frac{5}{8}$	8 $\frac{3}{8}$	70

5 7/8" x 8" J Mold Bases – 68J

Ejector stroke data

C = (height of riser) = 1 5/8**S** = (max stroke of ejector bar) = 7/8

ITEM NUMBER	A	B	C	NET WT.
68J-13-13	1 3/8	1 3/8	1 5/8	84

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment


6" x 8" SH Shuttle Mold Bases – 68SH

Engineered and designed for various models of Autojectors, Moslo and Newbury vertical injection presses with shuttle tables.



EJECTOR STROKE DATA

C = (Height of Riser) = 1.25

S = (Max. Stroke of Ejector Bar) = 0.5




6" x 8" SH Shuttle Mold Bases – 68SH

2-PLATE
SERIES4-PLATE
SERIES

Shuttle Mold Bases listed below are supplied complete with one upper and two lower sub-assemblies. Upper and lower sub-assemblies are pre-drilled to match platen holes of presses listed in chart. The one piece ejector housings include set screws to securely hold the ejector plates in place during installation or removal.

All plates and housings are made from DME No. 3 Steel (see page 8), except for the ejector and ejector retainer plates.



SERIES	TOP PLATE	A	B	BH	SH	H	S	FITS PRESS*	ITEM NUMBER	NET WT.
2 PLATE	—	2.875	—	3.5	—	6.375	0.5		68SH2-0-27-22-0	124
3 PLATE	1	1.875	—	3.5	—	6.375	0.5	**AJ-M-N	68SH3-10-17-22-0	124
	—	2.875	1.375	—	2.125	6.375	0.5		68SH3-0-27-13-7	124
4 PLATE	—	1.875	0.875	0.875	—	2.625		N	68SH4-17-7-7-13	123
	—	1.875	0.875	1.375	—	2.125			68SH4-17-7-13-7	123
	—	1.375	1.375	0.875	—	2.625	6.25		68SH4-13-13-7-13	123
	—	1.375	1.375	1.375	—	2.125			68SH4-13-13-13-7	123
	1	1.875	0.875	—	2.625			**AJ-M-N	68SH4-10-17-7-13	124
	1	1.875	1.375	—	2.125	6.375	0.5		68SH4-10-17-13-7	124
	1	2	1.375	—	2.125	6.5	0.5	AJ-N	68SH4-10-20-13-7	126


*AJ = Autojectors

M = Moslo

N = Newbury


NOTE: For 68SH Components, see DME's Mold Components catalog.

****NOTE:** Autojector applications with 6.375 H dimension require a 0.125" thick spacer for upper half (check with molder; machine may be equipped with required spacer).



SECTION Z-Z REF.

2-PLATE SERIES – 1 PLATE UPPER HALF
1 PLATE LOWER HALF



ALTERNATIVE UPPER HALF MOUNTING HOLES PROVIDED ONLY WHEN AUTOJECTORS APPLICATION IS SPECIFIED (SEE ITEM 3 BELOW).

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Mounting Hole Requirement: Standard or Autojectors
4. Method of Shipment

8" x 9⁷/₈" SH Shuttle Mold Bases – 810SH


Engineered and designed for various models of Autojectors, Moslo, Newbury, Reed, and Van Dorn vertical injection presses with shuttle tables.



EJECTOR STROKE DATA

C	1.25	1.875
S	0.5	1"


C = Height of Riser.

S = Max. Stroke of Ejector Bar.



8" x 9⁷/₈" SH Shuttle Mold Bases – 810SH2-PLATE
SERIES4-PLATE
SERIES


Shuttle Mold Bases listed below are supplied complete with one upper and two lower sub-assemblies. Upper and lower sub-assemblies are pre-drilled to match platen holes of presses listed in chart. Solid rails (spacer blocks) extend beyond support or cavity plate for ease of installation in press.



SERIES	TOP PLATE	A	B	SUPP. PLATE	C	H	S	FITS PRESS*	ITEM NUMBER	NET WT.
2 PLATE	—	3.375	3.875	—	1.25	8.5	0.5		810SH2-0-33-37-0	298
3 PLATE	1	2.375	3.875	—	1.25		0.5	* * AJ-M-N -RD-V	810SH3-10-23-37-0	298
	—	3.375	1.375	1.875					810SH3-0-33-13-17	286
	—	3.375	1.875	1.375	1.875	8.5	1		810SH3-0-33-17-13	286
	—	3.375	1.875	1.375	1.875	8.5	1		810SH3-0-33-17-13	286
	—	3.375	2.375	0.875					810SH3-0-33-23-7	286
4 PLATE	2.375	0.875	0.875	2.375				N-RD-V	810SH4-23-7-7-23	284
	2.375	0.875	1.375	1.875					810SH4-23-7-13-17	284
	1.875	1.375	1.375	1.875		8.375			810SH4-17-13-13-17	284
	1.875	1.375	1.875	1.375		8.375			810SH4-17-13-17-13	284
	1.875	1.375	2.375	0.875	1.875		1		810SH4-17-13-23-7	284
	1.375	1.875	1.875	1.375					810SH4-13-17-17-13	284
	1	2.375	1.375	1.875					810SH4-10-23-13-17	286
	1	2.375	1.875	1.375		8.5		* * AJ-M-N -RD-V	810SH4-10-23-17-13	286
	1	2.375	2.375	0.875					810SH4-10-23-23-7	286
	1	2.375	2.375	0.875					810SH4-10-23-23-7	286

*AJ = Autojectors M = Moslo N = Newbury RD = Reed V = Van Dorn

** NOTE: All Autojector applications require a 0.5" thick spacer for upper half (check with molder; machine may be equipped with required spacer).



SECTION Z-Z REF.
2-PLATE SERIES – 1 PLATE UPPER HALF
1 PLATE LOWER HALF

AVAILABLE IN:

- DME No. 1 or No. 3 Steel

NO. 3 STEEL ASSEMBLY

- "A" and "B" Plate - No. 3 Steel
- Top & Support Plates - No. 2 Steel

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1 or No. 3 Steel
3. Method of Shipment

Metric Equivalents and Conversions

Equivalents: Inch, fraction, decimal, millimeter

INCHES	MILLIMETERS	INCHES	MILLIMETERS
1	25.4	34	863.6
2	50.8	35	889.0
3	76.2	36	914.4
4	101.6	37	939.8
5	127.0	38	965.2
6	152.4	39	990.6
7	177.8	40	1016.0
8	203.2	41	1041.4
9	228.6	42	1066.8
10	254.0	43	1092.2
11	279.4	44	1117.6
12	304.8	45	1143.0
13	330.2	46	1168.4
14	355.6	47	1193.8
15	381.0	48	1219.2
16	406.4	49	1244.6
17	431.8	50	1270.0
18	457.2	51	1295.4
19	482.6	52	1320.8
20	508.0	53	1346.2
21	533.4	54	1371.6
22	558.8	55	1397.0
23	584.2	56	1422.4
24	609.6	57	1447.8
25	635.0	58	1473.2
26	660.4	59	1498.6
27	685.8	60	1524.0
28	711.2	61	1549.4
29	736.6	62	1574.8
30	762.0	63	1600.2
31	787.4	64	1625.6
32	812.8	65	1651.0
33	838.2	66	1676.4

INCHES	MILLIMETERS	INCHES	MILLIMETERS
1/64	0.015625	33/64	0.515625
1/32	0.031250	17/32	0.531250
3/64	0.046875	35/64	0.546875
1/16	0.062500	9/16	0.562500
5/64	0.078125	37/64	0.578125
3/32	0.093750	19/32	0.593750
7/64	0.109375	39/64	0.609375
1/8	0.125000	5/8	0.625000
9/64	0.140625	41/64	0.640625
5/32	0.156250	21/32	0.656250
11/64	0.171875	43/64	0.671875
3/16	0.187500	11/16	0.687500
13/64	0.203125	45/64	0.703125
7/32	0.218750	23/32	0.718750
15/64	0.234375	47/64	0.734375
1/4	0.250000	3/4	0.750000
17/64	0.265625	49/64	0.765625
9/32	0.281250	25/32	0.781250
19/64	0.296875	51/64	0.796875
5/16	0.312500	13/16	0.812500
21/64	0.328125	53/64	0.828125
11/32	0.343750	27/32	0.843750
23/64	0.359375	55/64	0.859375
3/8	0.375000	7/8	0.875000
25/64	0.390625	57/64	0.890625
13/32	0.406250	29/32	0.906250
27/64	0.421875	59/64	0.921875
7/16	0.437500	15/16	0.937500
29/64	0.453125	61/64	0.953125
15/32	0.468750	31/32	0.968750
31/64	0.484375	63/64	0.984375
1/2	0.500000	1	1.000000

Equivalents: Decimal, millimeter

INCHES	MILLIMETERS	INCHES	MILLIMETERS	INCHES	MILLIMETERS
0.001	0.0254	0.01	0.254	0.1	2.54
0.002	0.0508	0.02	0.508	0.2	5.08
0.003	0.0762	0.03	0.762	0.3	7.62
0.004	0.1016	0.04	1.016	0.4	10.16
0.005	0.1270	0.05	1.270	0.5	12.70
0.006	0.1524	0.06	1.524	0.6	15.24
0.007	0.1778	0.07	1.778	0.7	17.78
0.008	0.2032	0.08	2.032	0.8	20.32
0.009	0.2286	0.09	2.286	0.9	22.86

Measurement conversions

MULTIPLY BY	FROM	TO	MULTIPLY BY
0.03937	inch	millimeter	25.4
0.0016	inch ²	millimeter ²	645.16
0.061	inch ³	centimeter ³	16.3871
0.2642	gallon (U.S.)	liter	3.7854
0.03527	oz. (avdp.)	gram	28.3495
2.2044	pound	kilogram	0.4536
62.43	lbs/ft ³	g/cm ³	0.0160
0.145	psi	kPa	6.8948
14.2247	psi	kg/cm ²	0.0703
1.8°C + 32	°F	°C	(°F-32)/1.8

**Cavity retainer sets to match your
application requirements**



Cavity Retainer Sets

Steel Information

Two- and Three-Plate Cavity Retainer Sets offer accurate alignment and complete interchangeability

DME Standard Cavity Retainer Sets are available in 43 standard sizes from $7\frac{7}{8}" \times 7\frac{7}{8}"$ to $23\frac{3}{4}" \times 35\frac{1}{2}"$. Each size is offered in various cavity plate thickness combinations in your choice of DME No. 1, No. 3 or No. 7 Steel (No. 7 available up to $2\frac{7}{8}"$ thick standard). DME's precision-built interchangeable construction makes possible the wide variety of two-plate combinations as well as the three-plate construction. Guide/Leader Pins locations consistent with DME Classic 2.0 Mold Bases.

DME No. 1 Steel

DME No. 1 Steel is a medium carbon (SAE 1030), silicon-killed forging quality steel with approximately 25% greater tensile strength than typical low-carbon warehouse steels. It machines easily, but is not "sticky," permitting a faster and smoother cut.


DME No. 3 Steel

DME No. 3 Steel is a P-20 AISI 4130 (modified) type cavity steel. Exceptionally clean, it is pre-heat treated block applications. It is supplied pre-to 271-321 Bhn (28-34 HRC). It provides high hardness, good machinability and exceptional polishability.


DME No. 7 Steel

No. 7 Steel is a modified AISI 400 series stainless steel for holder series stainless steel for block applications. It is supplied pre-hardened to 32-36 HRC (302-340 Bhn). This stainless steel offers corrosion resistance and exceptional machinability but cannot be further hardened (see DME No. 6). For humid environments, corrosive plastics, "clean room" or "100% stainless" applications, it is an ideal choice for all structural (non-cavity/core) mold plates.

Two-Plate Cavity Retainer Set



Three-Plate Cavity Retainer Set





When Three-plate Cavity Sets are ordered the following information should be specified:

- Width and length of Cavity Set
- Length of leader pins
- Thicknesses of A, X-1 and B-plates
- Type of steel required

For quotations on assemblies with more than one floating plate, contact DME.

Cavity Retainer Sets

7⁷/₈ × 7⁷/₈ and 7⁷/₈ × 11⁷/₈



A	B	ITEM NUMBER	NET WT.
7 ⁷ / ₈	7 ⁷ / ₈	88-7-7	31
	1 ³ / ₈	88-7-13	40
	1 ⁷ / ₈	88-7-17	49
	2 ³ / ₈	88-7-23	58
	2 ⁷ / ₈	88-7-27	66
	3 ³ / ₈	88-7-33	75
	3 ⁷ / ₈	88-7-37	84
	4 ⁷ / ₈	88-7-47	102
1 ³ / ₈	5 ⁷ / ₈	88-7-57	119
	7 ⁷ / ₈	88-13-7	40
	1 ³ / ₈	88-13-13	49
	1 ⁷ / ₈	88-13-17	58
	2 ³ / ₈	88-13-23	66
	2 ⁷ / ₈	88-13-27	75
	3 ³ / ₈	88-13-33	84
	3 ⁷ / ₈	88-13-37	93
1 ⁷ / ₈	4 ⁷ / ₈	88-13-47	110
	5 ⁷ / ₈	88-13-57	128
	7 ⁷ / ₈	88-17-7	49
	1 ³ / ₈	88-17-13	58
	1 ⁷ / ₈	88-17-17	66
	2 ³ / ₈	88-17-23	75
	2 ⁷ / ₈	88-17-27	84
	3 ³ / ₈	88-17-33	93
2 ³ / ₈	3 ⁷ / ₈	88-17-37	102
	4 ⁷ / ₈	88-17-47	119
	5 ⁷ / ₈	88-17-57	137
	7 ⁷ / ₈	88-23-7	58
	1 ³ / ₈	88-23-13	66
	1 ⁷ / ₈	88-23-17	75
	2 ³ / ₈	88-23-23	84
	2 ⁷ / ₈	88-23-27	93
2 ⁷ / ₈	3 ³ / ₈	88-23-33	102
	3 ⁷ / ₈	88-23-37	110
	4 ⁷ / ₈	88-23-47	128
	5 ⁷ / ₈	88-23-57	145
	7 ⁷ / ₈	88-27-7	66
	1 ³ / ₈	88-27-13	75
	1 ⁷ / ₈	88-27-17	84
	2 ³ / ₈	88-27-23	93
2 ⁷ / ₈	2 ⁷ / ₈	88-27-27	102
	3 ³ / ₈	88-27-33	110
	3 ⁷ / ₈	88-27-37	119
	4 ⁷ / ₈	88-27-47	137
	5 ⁷ / ₈	88-27-57	154
	7 ⁷ / ₈	88-27-7	66
	1 ³ / ₈	88-27-13	75
	1 ⁷ / ₈	88-27-17	84

A	B	ITEM NUMBER	NET WT.
3 ⁷ / ₈	7 ⁷ / ₈	88-33-7	75
	1 ³ / ₈	88-33-13	84
	1 ⁷ / ₈	88-33-17	93
	2 ³ / ₈	88-33-23	102
	2 ⁷ / ₈	88-33-27	110
	3 ³ / ₈	88-33-33	119
	3 ⁷ / ₈	88-33-37	128
	4 ⁷ / ₈	88-33-47	145
3 ⁷ / ₈	5 ⁷ / ₈	88-33-57	163
	7 ⁷ / ₈	88-37-7	84
	1 ³ / ₈	88-37-13	93
	1 ⁷ / ₈	88-37-17	102
	2 ³ / ₈	88-37-23	110
	2 ⁷ / ₈	88-37-27	119
	3 ³ / ₈	88-37-33	128
	3 ⁷ / ₈	88-37-37	137
4 ⁷ / ₈	4 ⁷ / ₈	88-37-47	154
	5 ⁷ / ₈	88-37-57	172
	7 ⁷ / ₈	88-47-7	102
	1 ³ / ₈	88-47-13	110
	1 ⁷ / ₈	88-47-17	119
	2 ³ / ₈	88-47-23	128
	2 ⁷ / ₈	88-47-27	137
	3 ³ / ₈	88-47-33	145
5 ⁷ / ₈	3 ⁷ / ₈	88-47-37	154
	4 ⁷ / ₈	88-47-47	172
	5 ⁷ / ₈	88-47-57	189
	7 ⁷ / ₈	88-57-7	119
	1 ³ / ₈	88-57-13	128
	1 ⁷ / ₈	88-57-17	137
	2 ³ / ₈	88-57-23	145
	2 ⁷ / ₈	88-57-27	154
5 ⁷ / ₈	3 ³ / ₈	88-57-33	163
	3 ⁷ / ₈	88-57-37	172
	4 ⁷ / ₈	88-57-47	189
	5 ⁷ / ₈	88-57-57	207

A	B	ITEM NUMBER	NET WT.
7 ⁷ / ₈	7 ⁷ / ₈	812-7-7	48
	1 ³ / ₈	812-7-13	61
	1 ⁷ / ₈	812-7-17	74
	2 ³ / ₈	812-7-23	87
	2 ⁷ / ₈	812-7-27	100
	3 ³ / ₈	812-7-33	113
	3 ⁷ / ₈	812-7-37	126
	4 ⁷ / ₈	812-7-47	153
1 ³ / ₈	5 ⁷ / ₈	812-7-57	179
	7 ⁷ / ₈	812-13-7	61
	1 ³ / ₈	812-13-13	74
	1 ⁷ / ₈	812-13-17	87
	2 ³ / ₈	812-13-23	100
	2 ⁷ / ₈	812-13-27	113
	3 ³ / ₈	812-13-33	126
	3 ⁷ / ₈	812-13-37	139
1 ⁷ / ₈	4 ⁷ / ₈	812-13-47	166
	5 ⁷ / ₈	812-13-57	192
	7 ⁷ / ₈	812-17-7	74
	1 ³ / ₈	812-17-13	87
	1 ⁷ / ₈	812-17-17	100
	2 ³ / ₈	812-17-23	113
	2 ⁷ / ₈	812-17-27	126
	3 ³ / ₈	812-17-33	139
2 ³ / ₈	3 ⁷ / ₈	812-17-37	152
	4 ⁷ / ₈	812-17-47	179
	5 ⁷ / ₈	812-17-57	205
	7 ⁷ / ₈	812-23-7	87
	1 ³ / ₈	812-23-13	100
	1 ⁷ / ₈	812-23-17	113
	2 ³ / ₈	812-23-23	126
	2 ⁷ / ₈	812-23-27	139
2 ⁷ / ₈	3 ³ / ₈	812-23-33	152
	3 ⁷ / ₈	812-23-37	165
	4 ⁷ / ₈	812-23-47	192
	5 ⁷ / ₈	812-23-57	218

A	B	ITEM NUMBER	NET WT.
2 ⁷ / ₈	7 ⁷ / ₈	812-27-7	100
	1 ³ / ₈	812-27-13	113
	1 ⁷ / ₈	812-27-17	126
	2 ³ / ₈	812-27-23	139
	2 ⁷ / ₈	812-27-27	152
	3 ³ / ₈	812-27-33	165
	3 ⁷ / ₈	812-27-37	178
	4 ⁷ / ₈	812-27-47	205
3 ³ / ₈	5 ⁷ / ₈	812-27-57	231
	7 ⁷ / ₈	812-33-7	113
	1 ³ / ₈	812-33-13	126
	1 ⁷ / ₈	812-33-17	139
	2 ³ / ₈	812-33-23	152
	2 ⁷ / ₈	812-33-27	165
	3 ³ / ₈	812-33-33	178
	3 ⁷ / ₈	812-33-37	191
3 ⁷ / ₈	4 ⁷ / ₈	812-33-47	218
	5 ⁷ / ₈	812-33-57	244
	7 ⁷ / ₈	812-37-7	126
	1 ³ / ₈	812-37-13	139
	1 ⁷ / ₈	812-37-17	152
	2 ³ / ₈	812-37-23	165
	2 ⁷ / ₈	812-37-27	178
	3 ³ / ₈	812-37-33	191
4 ⁷ / ₈	3 ⁷ / ₈	812-37-37	204
	4 ⁷ / ₈	812-37-47	231
	5 ⁷ / ₈	812-37-57	257
	7 ⁷ / ₈	812-47-7	153
	1 ³ / ₈	812-47-13	166
	1 ⁷ / ₈	812-47-17	179
	2 ³ / ₈	812-47-23	192
	2 ⁷ / ₈	812-47-27	205
5 ⁷ / ₈	3 ³ / ₈	812-47-33	218
	3 ⁷ / ₈	812-47-37	231
	4 ⁷ / ₈	812-47-47	258
	5 ⁷ / ₈	812-47-57	284
	7 ⁷ / ₈	812-57-7	179
	1 ³ / ₈	812-57-13	192
	1 ⁷ / ₈	812-57-17	205
	2 ³ / ₈	812-57-23	218
5 ⁷ / ₈	2 ⁷ / ₈	812-57-27	231
	3 ³ / ₈	812-57-33	244
	3 ⁷ / ₈	812-57-37	257
	4 ⁷ / ₈	812-57-47	284
	5 ⁷ / ₈	812-57-57	310


Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment


Cavity Retainer Sets

9⁷/₈ × 8 and 9⁷/₈ × 11⁷/₈



A	B	ITEM NUMBER	NET WT.
7 ⁷ / ₈	7 ⁷ / ₈	108-7-7	40
	1 ³ / ₈	108-7-13	51
	1 ⁷ / ₈	108-7-17	62
	2 ³ / ₈	108-7-23	73
	2 ⁷ / ₈	108-7-27	84
	3 ³ / ₈	108-7-33	96
	3 ⁷ / ₈	108-7-37	107
	4 ⁷ / ₈	108-7-47	129
	5 ⁷ / ₈	108-7-57	152
	7 ⁷ / ₈	108-13-7	51
1 ³ / ₈	1 ³ / ₈	108-13-13	62
	1 ⁷ / ₈	108-13-17	73
	2 ³ / ₈	108-13-23	84
	2 ⁷ / ₈	108-13-27	96
	3 ³ / ₈	108-13-33	107
	3 ⁷ / ₈	108-13-37	118
	4 ⁷ / ₈	108-13-47	140
	5 ⁷ / ₈	108-13-57	163
	7 ⁷ / ₈	108-17-7	62
	1 ³ / ₈	108-17-13	73
1 ⁷ / ₈	1 ⁷ / ₈	108-17-17	84
	2 ³ / ₈	108-17-23	96
	2 ⁷ / ₈	108-17-27	107
	3 ³ / ₈	108-17-33	118
	3 ⁷ / ₈	108-17-37	129
	4 ⁷ / ₈	108-17-47	152
	5 ⁷ / ₈	108-17-57	174
	7 ⁷ / ₈	108-23-7	73
	1 ³ / ₈	108-23-13	84
	1 ⁷ / ₈	108-23-17	96
2 ³ / ₈	2 ³ / ₈	108-23-23	107
	2 ⁷ / ₈	108-23-27	118
	3 ³ / ₈	108-23-33	129
	3 ⁷ / ₈	108-23-37	140
	4 ⁷ / ₈	108-23-47	163
	5 ⁷ / ₈	108-23-57	185
	7 ⁷ / ₈	108-27-7	84
	1 ³ / ₈	108-27-13	96
	1 ⁷ / ₈	108-27-17	107
	2 ³ / ₈	108-27-23	118
2 ⁷ / ₈	2 ⁷ / ₈	108-27-27	129
	3 ³ / ₈	108-27-33	140
	3 ⁷ / ₈	108-27-37	152
	4 ⁷ / ₈	108-27-47	174
	5 ⁷ / ₈	108-27-57	196
	7 ⁷ / ₈	108-27-57	196

A	B	ITEM NUMBER	NET WT.
3 ⁷ / ₈	7 ⁷ / ₈	108-33-7	96
	1 ³ / ₈	108-33-13	107
	1 ⁷ / ₈	108-33-17	118
	2 ³ / ₈	108-33-23	129
	2 ⁷ / ₈	108-33-27	140
	3 ³ / ₈	108-33-33	152
	3 ⁷ / ₈	108-33-37	163
	4 ⁷ / ₈	108-33-47	185
	5 ⁷ / ₈	108-33-57	208
	7 ⁷ / ₈	108-37-7	107
3 ³ / ₈	1 ³ / ₈	108-37-13	118
	1 ⁷ / ₈	108-37-17	129
	2 ³ / ₈	108-37-23	140
	2 ⁷ / ₈	108-37-27	152
	3 ³ / ₈	108-37-33	163
	3 ⁷ / ₈	108-37-37	174
	4 ⁷ / ₈	108-37-47	196
	5 ⁷ / ₈	108-37-57	219
	7 ⁷ / ₈	108-47-7	129
	1 ³ / ₈	108-47-13	140
4 ⁷ / ₈	1 ⁷ / ₈	108-47-17	152
	2 ³ / ₈	108-47-23	163
	2 ⁷ / ₈	108-47-27	174
	3 ³ / ₈	108-47-33	185
	3 ⁷ / ₈	108-47-37	196
	4 ⁷ / ₈	108-47-47	219
	5 ⁷ / ₈	108-47-57	241
	7 ⁷ / ₈	108-57-7	152
	1 ³ / ₈	108-57-13	163
	1 ⁷ / ₈	108-57-17	174
5 ⁷ / ₈	2 ³ / ₈	108-57-23	185
	2 ⁷ / ₈	108-57-27	196
	3 ³ / ₈	108-57-33	208
	3 ⁷ / ₈	108-57-37	219
	4 ⁷ / ₈	108-57-47	241
	5 ⁷ / ₈	108-57-57	263



A	B	ITEM NUMBER	NET WT.
7 ⁷ / ₈	7 ⁷ / ₈	1012-7-7	59
	1 ³ / ₈	1012-7-13	75
	1 ⁷ / ₈	1012-7-17	92
	2 ³ / ₈	1012-7-23	108
	2 ⁷ / ₈	1012-7-27	125
	3 ³ / ₈	1012-7-33	142
	3 ⁷ / ₈	1012-7-37	158
	4 ⁷ / ₈	1012-7-47	192
	5 ⁷ / ₈	1012-7-57	225
	7 ⁷ / ₈	1012-13-7	75
1 ³ / ₈	1 ³ / ₈	1012-13-13	92
	1 ⁷ / ₈	1012-13-17	108
	2 ³ / ₈	1012-13-23	125
	2 ⁷ / ₈	1012-13-27	142
	3 ³ / ₈	1012-13-33	158
	3 ⁷ / ₈	1012-13-37	175
	4 ⁷ / ₈	1012-13-47	208
	5 ⁷ / ₈	1012-13-57	241
	7 ⁷ / ₈	1012-17-7	92
	1 ³ / ₈	1012-17-13	108
1 ⁷ / ₈	1 ⁷ / ₈	1012-17-17	125
	2 ³ / ₈	1012-17-23	142
	2 ⁷ / ₈	1012-17-27	158
	3 ³ / ₈	1012-17-33	175
	3 ⁷ / ₈	1012-17-37	192
	4 ⁷ / ₈	1012-17-47	225
	5 ⁷ / ₈	1012-17-57	258
	7 ⁷ / ₈	1012-23-7	108
	1 ³ / ₈	1012-23-13	125
	1 ⁷ / ₈	1012-23-17	142
2 ³ / ₈	2 ³ / ₈	1012-23-23	158
	2 ⁷ / ₈	1012-23-27	175
	3 ³ / ₈	1012-23-33	192
	3 ⁷ / ₈	1012-23-37	208
	4 ⁷ / ₈	1012-23-47	241
	5 ⁷ / ₈	1012-23-57	275

A	B	ITEM NUMBER	NET WT.
2 ⁷ / ₈	7 ⁷ / ₈	1012-27-7	125
	1 ³ / ₈	1012-27-13	142
	1 ⁷ / ₈	1012-27-17	158
	2 ³ / ₈	1012-27-23	175
	2 ⁷ / ₈	1012-27-27	192
	3 ³ / ₈	1012-27-33	208
	3 ⁷ / ₈	1012-27-37	225
	4 ⁷ / ₈	1012-27-47	258
	5 ⁷ / ₈	1012-27-57	291
	7 ⁷ / ₈	1012-33-7	142
3 ³ / ₈	1 ³ / ₈	1012-33-13	158
	1 ⁷ / ₈	1012-33-17	175
	2 ³ / ₈	1012-33-23	192
	2 ⁷ / ₈	1012-33-27	208
	3 ³ / ₈	1012-33-33	225
	3 ⁷ / ₈	1012-33-37	241
	4 ⁷ / ₈	1012-33-47	275
	5 ⁷ / ₈	1012-33-57	308
	7 ⁷ / ₈	1012-37-7	158
	1 ³ / ₈	1012-37-13	175
3 ⁷ / ₈	1 ⁷ / ₈	1012-37-17	192
	2 ³ / ₈	1012-37-23	208
	2 ⁷ / ₈	1012-37-27	225
	3 ³ / ₈	1012-37-33	241
	3 ⁷ / ₈	1012-37-37	258
	4 ⁷ / ₈	1012-37-47	291
	5 ⁷ / ₈	1012-37-57	324
	7 ⁷ / ₈	1012-47-7	192
	1 ³ / ₈	1012-47-13	208
	1 ⁷ / ₈	1012-47-17	225
4 ⁷ / ₈	2 ³ / ₈	1012-47-23	241
	2 ⁷ / ₈	1012-47-27	258
	3 ³ / ₈	1012-47-33	275
	3 ⁷ / ₈	1012-47-37	291
	4 ⁷ / ₈	1012-47-47	324
	5 ⁷ / ₈	1012-47-57	358
	7 ⁷ / ₈	1012-57-7	225
	1 ³ / ₈	1012-57-13	241
	1 ⁷ / ₈	1012-57-17	258
	2 ³ / ₈	1012-57-23	275
5 ⁷ / ₈	2 ⁷ / ₈	1012-57-27	291
	3 ³ / ₈	1012-57-33	308
	3 ⁷ / ₈	1012-57-37	324
	4 ⁷ / ₈	1012-57-47	358
	5 ⁷ / ₈	1012-57-57	391
	7 ⁷ / ₈	1012-57-57	391



Thickness of each plate is finish ground $\pm .001"$. Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

9 7/8" x 16" and 9 7/8" x 20"



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1016-7-7	79
	1 1/8	1016-7-13	101
	1 1/4	1016-7-17	124
	2 1/8	1016-7-23	146
	2 1/2	1016-7-27	168
	3 1/8	1016-7-33	191
	3 1/4	1016-7-37	213
	4 1/8	1016-7-47	258
1 3/8	5 1/8	1016-7-57	303
	7/8	1016-13-7	101
	1 1/8	1016-13-13	124
	1 1/4	1016-13-17	146
	2 1/8	1016-13-23	168
	2 1/2	1016-13-27	191
	3 1/8	1016-13-33	213
	3 1/4	1016-13-37	235
1 7/8	4 1/8	1016-13-47	280
	5 1/8	1016-13-57	325
	7/8	1016-17-7	124
	1 1/8	1016-17-13	146
	1 1/4	1016-17-17	168
	2 1/8	1016-17-23	191
	2 1/2	1016-17-27	213
	3 1/8	1016-17-33	235
2 3/8	3 1/4	1016-17-37	258
	4 1/8	1016-17-47	303
	5 1/8	1016-17-57	347
	7/8	1016-23-7	146
	1 1/8	1016-23-13	168
	1 1/4	1016-23-17	191
	2 1/8	1016-23-23	213
	2 1/2	1016-23-27	235
2 7/8	3 1/8	1016-23-33	258
	3 1/4	1016-23-37	280
	4 1/8	1016-23-47	325
	5 1/8	1016-23-57	370
	7/8	1016-27-7	168
	1 1/8	1016-27-13	191
	1 1/4	1016-27-17	213
	2 1/8	1016-27-23	235
2 7/8	2 1/2	1016-27-27	258
	3 1/8	1016-27-33	280
	3 1/4	1016-27-37	303
	4 1/8	1016-27-47	347
	5 1/8	1016-27-57	392
	7/8	1016-27-7	168
	1 1/8	1016-27-13	191
	1 1/4	1016-27-17	213

A	B	ITEM NUMBER	NET WT.
3 3/8	7/8	1016-33-7	191
	1 1/8	1016-33-13	213
	1 1/4	1016-33-17	235
	2 1/8	1016-33-23	258
	2 1/2	1016-33-27	280
	3 1/8	1016-33-33	303
	3 1/4	1016-33-37	325
	4 1/8	1016-33-47	370
3 7/8	5 1/8	1016-33-57	415
	7/8	1016-37-7	213
	1 1/8	1016-37-13	235
	1 1/4	1016-37-17	258
	2 1/8	1016-37-23	280
	2 1/2	1016-37-27	303
	3 1/8	1016-37-33	325
	3 1/4	1016-37-37	347
4 7/8	4 1/8	1016-37-47	392
	5 1/8	1016-37-57	437
	7/8	1016-47-7	258
	1 1/8	1016-47-13	280
	1 1/4	1016-47-17	303
	2 1/8	1016-47-23	325
	2 1/2	1016-47-27	347
	3 1/8	1016-47-33	370
5 7/8	3 1/4	1016-47-37	392
	4 1/8	1016-47-47	437
	5 1/8	1016-47-57	482
	7/8	1016-57-7	303
	1 1/8	1016-57-13	325
	1 1/4	1016-57-17	347
	2 1/8	1016-57-23	370
	2 1/2	1016-57-27	392
	3 1/8	1016-57-33	415
	3 1/4	1016-57-37	437
	4 1/8	1016-57-47	482
	5 1/8	1016-57-57	526

A	B	ITEM NUMBER	NET WT.
7/8	7/8	1020-7-7	98
	1 1/8	1020-7-13	126
	1 1/4	1020-7-17	154
	2 1/8	1020-7-23	182
	2 1/2	1020-7-27	210
	3 1/8	1020-7-33	238
	3 1/4	1020-7-37	266
	4 1/8	1020-7-47	322
1 3/8	5 1/8	1020-7-57	378
	7/8	1020-13-7	126
	1 1/8	1020-13-13	154
	1 1/4	1020-13-17	182
	2 1/8	1020-13-23	210
	2 1/2	1020-13-27	238
	3 1/8	1020-13-33	266
	3 1/4	1020-13-37	294
1 7/8	4 1/8	1020-13-47	350
	5 1/8	1020-13-57	406
	7/8	1020-17-7	154
	1 1/8	1020-17-13	182
	1 1/4	1020-17-17	210
	2 1/8	1020-17-23	238
	2 1/2	1020-17-27	266
	3 1/8	1020-17-33	294
2 3/8	3 1/4	1020-17-37	322
	4 1/8	1020-17-47	378
	5 1/8	1020-17-57	434
	7/8	1020-23-7	182
	1 1/8	1020-23-13	210
	1 1/4	1020-23-17	238
	2 1/8	1020-23-23	266
	2 1/2	1020-23-27	294
	3 1/8	1020-23-33	322
	3 1/4	1020-23-37	350
	4 1/8	1020-23-47	406
	5 1/8	1020-23-57	462

A	B	ITEM NUMBER	NET WT.
2 7/8	7/8	1020-27-7	210
	1 1/8	1020-27-13	238
	1 1/4	1020-27-17	266
	2 1/8	1020-27-23	294
	2 1/2	1020-27-27	322
	3 1/8	1020-27-33	350
	3 1/4	1020-27-37	378
	4 1/8	1020-27-47	434
3 3/8	5 1/8	1020-27-57	490
	7/8	1020-33-7	238
	1 1/8	1020-33-13	266
	1 1/4	1020-33-17	294
	2 1/8	1020-33-23	322
	2 1/2	1020-33-27	350
	3 1/8	1020-33-33	378
	3 1/4	1020-33-37	406
3 7/8	4 1/8	1020-33-47	462
	5 1/8	1020-33-57	518
	7/8	1020-37-7	266
	1 1/8	1020-37-13	294
	1 1/4	1020-37-17	322
	2 1/8	1020-37-23	350
	2 1/2	1020-37-27	378
	3 1/8	1020-37-33	406
4 7/8	3 1/4	1020-37-37	434
	4 1/8	1020-37-47	490
	5 1/8	1020-37-57	546
	7/8	1020-47-7	322
	1 1/8	1020-47-13	350
	1 1/4	1020-47-17	378
	2 1/8	1020-47-23	406
	2 1/2	1020-47-27	434
5 7/8	3 1/8	1020-47-33	462
	3 1/4	1020-47-37	490
	4 1/8	1020-47-47	546
	5 1/8	1020-47-57	602
	7/8	1020-57-7	378
	1 1/8	1020-57-13	406
	1 1/4	1020-57-17	434
	2 1/8	1020-57-23	462
	2 1/2	1020-57-27	490
	3 1/8	1020-57-33	518
	3 1/4	1020-57-37	546
	4 1/8	1020-57-47	602
	5 1/8	1020-57-57	658



Thickness of each plate is finish ground $\pm .001"$. Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2 1/2" thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

10⁷/₈ × 12 and 10⁷/₈ × 14



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1112-7-7	65
	1 3/8	1112-7-13	84
	1 7/8	1112-7-17	102
	2 3/8	1112-7-23	121
	2 7/8	1112-7-27	139
	3 3/8	1112-7-33	158
	3 7/8	1112-7-37	176
	4 7/8	1112-7-47	213
1 1/8	5 7/8	1112-7-57	250
	7/8	1112-13-7	84
	1 3/8	1112-13-13	102
	1 7/8	1112-13-17	121
	2 3/8	1112-13-23	139
	2 7/8	1112-13-27	158
	3 3/8	1112-13-33	176
	3 7/8	1112-13-37	195
1 7/8	4 7/8	1112-13-47	232
	5 7/8	1112-13-57	269
	7/8	1112-17-7	102
	1 3/8	1112-17-13	121
	1 7/8	1112-17-17	139
	2 3/8	1112-17-23	158
	2 7/8	1112-17-27	176
	3 3/8	1112-17-33	195
2 3/8	3 7/8	1112-17-37	213
	4 7/8	1112-17-47	250
	5 7/8	1112-17-57	287
	7/8	1112-23-7	121
	1 3/8	1112-23-13	139
	1 7/8	1112-23-17	158
	2 3/8	1112-23-23	176
	2 7/8	1112-23-27	195
2 7/8	3 3/8	1112-23-33	213
	3 7/8	1112-23-37	232
	4 7/8	1112-23-47	269
	5 7/8	1112-23-57	306
	7/8	1112-27-7	139
	1 3/8	1112-27-13	158
	1 7/8	1112-27-17	176
	2 3/8	1112-27-23	195

A	B	ITEM NUMBER	NET WT.
3 7/8	7/8	1112-33-7	158
	1 3/8	1112-33-13	176
	1 7/8	1112-33-17	195
	2 3/8	1112-33-23	213
	2 7/8	1112-33-27	232
	3 3/8	1112-33-33	250
	3 7/8	1112-33-37	269
	4 7/8	1112-33-47	306
3 3/8	5 7/8	1112-33-57	343
	7/8	1112-37-7	176
	1 3/8	1112-37-13	195
	1 7/8	1112-37-17	213
	2 3/8	1112-37-23	232
	2 7/8	1112-37-27	250
	3 3/8	1112-37-33	269
	3 7/8	1112-37-37	287
4 7/8	4 7/8	1112-37-47	324
	5 7/8	1112-37-57	361
	7/8	1112-47-7	213
	1 3/8	1112-47-13	232
	1 7/8	1112-47-17	250
	2 3/8	1112-47-23	269
	2 7/8	1112-47-27	287
	3 3/8	1112-47-33	306
5 7/8	3 7/8	1112-47-37	324
	4 7/8	1112-47-47	361
	5 7/8	1112-47-57	398
	7/8	1112-57-7	250
	1 3/8	1112-57-13	269
	1 7/8	1112-57-17	287
	2 3/8	1112-57-23	306
	2 7/8	1112-57-27	324
	3 3/8	1112-57-33	343
	3 7/8	1112-57-37	361
	4 7/8	1112-57-47	398
	5 7/8	1112-57-57	435

A	B	ITEM NUMBER	NET WT.
7/8	7/8	1114-7-7	76
	1 3/8	1114-7-13	98
	1 7/8	1114-7-17	119
	2 3/8	1114-7-23	141
	2 7/8	1114-7-27	162
	3 3/8	1114-7-33	184
	3 7/8	1114-7-37	205
	4 7/8	1114-7-47	249
1 3/8	5 7/8	1114-7-57	292
	7/8	1114-13-7	98
	1 3/8	1114-13-13	119
	1 7/8	1114-13-17	141
	2 3/8	1114-13-23	162
	2 7/8	1114-13-27	184
	3 3/8	1114-13-33	205
	3 7/8	1114-13-37	227
1 7/8	4 7/8	1114-13-47	270
	5 7/8	1114-13-57	313
	7/8	1114-17-7	119
	1 3/8	1114-17-13	141
	1 7/8	1114-17-17	162
	2 3/8	1114-17-23	184
	2 7/8	1114-17-27	205
	3 3/8	1114-17-33	227
2 3/8	3 7/8	1114-17-37	249
	4 7/8	1114-17-47	292
	5 7/8	1114-17-57	335
	7/8	1114-23-7	141
	1 3/8	1114-23-13	162
	1 7/8	1114-23-17	184
	2 3/8	1114-23-23	205
	2 7/8	1114-23-27	227
	3 3/8	1114-23-33	249
	3 7/8	1114-23-37	270
	4 7/8	1114-23-47	313
	5 7/8	1114-23-57	356

A	B	ITEM NUMBER	NET WT.
2 7/8	7/8	1114-27-7	162
	1 3/8	1114-27-13	184
	1 7/8	1114-27-17	205
	2 3/8	1114-27-23	227
	2 7/8	1114-27-27	249
	3 3/8	1114-27-33	270
	3 7/8	1114-27-37	292
	4 7/8	1114-27-47	335
3 3/8	5 7/8	1114-27-57	378
	7/8	1114-33-7	184
	1 3/8	1114-33-13	205
	1 7/8	1114-33-17	227
	2 3/8	1114-33-23	249
	2 7/8	1114-33-27	270
	3 3/8	1114-33-33	292
	3 7/8	1114-33-37	313
3 7/8	4 7/8	1114-33-47	356
	5 7/8	1114-33-57	400
	7/8	1114-37-7	205
	1 3/8	1114-37-13	227
	1 7/8	1114-37-17	249
	2 3/8	1114-37-23	270
	2 7/8	1114-37-27	292
	3 3/8	1114-37-33	313
4 7/8	3 7/8	1114-37-37	335
	4 7/8	1114-37-47	378
	5 7/8	1114-37-57	421
	7/8	1114-47-7	249
	1 3/8	1114-47-13	270
	1 7/8	1114-47-17	292
	2 3/8	1114-47-23	313
	2 7/8	1114-47-27	335
5 7/8	3 3/8	1114-47-33	356
	3 7/8	1114-47-37	378
	4 7/8	1114-47-47	421
	5 7/8	1114-47-57	464
	7/8	1114-57-7	292
	1 3/8	1114-57-13	313
	1 7/8	1114-57-17	335
	2 3/8	1114-57-23	356
	2 7/8	1114-57-27	378
	3 3/8	1114-57-33	400
	3 7/8	1114-57-37	421
	4 7/8	1114-57-47	464
	5 7/8	1114-57-57	507


Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:


- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2 7/8 thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

10⁷/₈ × 18 and 10⁷/₈ × 23¹/₂



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1118-7-7	98
	1 3/8	1118-7-13	125
	1 7/8	1118-7-17	153
	2 3/8	1118-7-23	181
	2 7/8	1118-7-27	208
	3 3/8	1118-7-33	236
	3 7/8	1118-7-37	264
	4 7/8	1118-7-47	319
1 3/8	5 7/8	1118-7-57	375
	7/8	1118-13-7	125
	1 3/8	1118-13-13	153
	1 7/8	1118-13-17	181
	2 3/8	1118-13-23	208
	2 7/8	1118-13-27	236
	3 3/8	1118-13-33	264
	3 7/8	1118-13-37	292
1 7/8	4 7/8	1118-13-47	347
	5 7/8	1118-13-57	403
	7/8	1118-17-7	153
	1 3/8	1118-17-13	181
	1 7/8	1118-17-17	208
	2 3/8	1118-17-23	236
	2 7/8	1118-17-27	264
	3 3/8	1118-17-33	292
2 3/8	3 7/8	1118-17-37	319
	4 7/8	1118-17-47	375
	5 7/8	1118-17-57	430
	7/8	1118-23-7	181
	1 3/8	1118-23-13	208
	1 7/8	1118-23-17	236
	2 3/8	1118-23-23	264
	2 7/8	1118-23-27	292
2 7/8	3 3/8	1118-23-33	319
	3 7/8	1118-23-37	347
	4 7/8	1118-23-47	403
	5 7/8	1118-23-57	458
	7/8	1118-27-7	208
	1 3/8	1118-27-13	236
	1 7/8	1118-27-17	264
	2 3/8	1118-27-23	292
3 3/8	2 7/8	1118-27-27	319
	3 3/8	1118-27-33	347
	3 7/8	1118-27-37	375
	4 7/8	1118-27-47	430
	5 7/8	1118-27-57	486
	7/8	1118-33-7	236
	1 3/8	1118-33-13	264
	1 7/8	1118-33-17	292
3 7/8	2 3/8	1118-33-23	319
	2 7/8	1118-33-27	347
	3 3/8	1118-33-33	375
	3 7/8	1118-33-37	403
	4 7/8	1118-33-47	458
	5 7/8	1118-33-57	513
	7/8	1118-37-7	264
	1 3/8	1118-37-13	292
4 3/8	1 7/8	1118-37-17	319
	2 3/8	1118-37-23	347
	2 7/8	1118-37-27	375
	3 3/8	1118-37-33	403
	3 7/8	1118-37-37	430
	4 7/8	1118-37-47	486
	5 7/8	1118-37-57	541
	7/8	1118-47-7	319
4 7/8	1 3/8	1118-47-13	347
	1 7/8	1118-47-17	375
	2 3/8	1118-47-23	403
	2 7/8	1118-47-27	430
	3 3/8	1118-47-33	458
	3 7/8	1118-47-37	486
	4 7/8	1118-47-47	541
	5 7/8	1118-47-57	597
5 3/8	7/8	1118-57-7	375
	1 3/8	1118-57-13	403
	1 7/8	1118-57-17	430
	2 3/8	1118-57-23	458
	2 7/8	1118-57-27	486
	3 3/8	1118-57-33	513
	3 7/8	1118-57-37	541
	4 7/8	1118-57-47	597
5 7/8	5 7/8	1118-57-57	652



A	B	ITEM NUMBER	NET WT.
1 3/8	1 3/8	1123-13-13	200
	1 7/8	1123-13-17	236
	2 3/8	1123-13-23	272
	2 7/8	1123-13-27	308
	3 3/8	1123-13-33	344
	3 7/8	1123-13-37	381
	4 7/8	1123-13-47	453
	5 7/8	1123-13-57	525
1 7/8	1 3/8	1123-17-13	236
	1 7/8	1123-17-17	272
	2 3/8	1123-17-23	308
	2 7/8	1123-17-27	344
	3 3/8	1123-17-33	381
	3 7/8	1123-17-37	417
	4 7/8	1123-17-47	489
	5 7/8	1123-17-57	562
2 3/8	1 3/8	1123-23-13	272
	1 7/8	1123-23-17	308
	2 3/8	1123-23-23	344
	2 7/8	1123-23-27	381
	3 3/8	1123-23-33	417
	3 7/8	1123-23-37	453
	4 7/8	1123-23-47	525
	5 7/8	1123-23-57	598
2 7/8	1 3/8	1123-27-13	308
	1 7/8	1123-27-17	344
	2 3/8	1123-27-23	381
	2 7/8	1123-27-27	417
	3 3/8	1123-27-33	453
	3 7/8	1123-27-37	489
	4 7/8	1123-27-47	562
	5 7/8	1123-27-57	634
3 3/8	1 3/8	1123-33-13	344
	1 7/8	1123-33-17	381
	2 3/8	1123-33-23	417
	2 7/8	1123-33-27	453
	3 3/8	1123-33-33	489
	3 7/8	1123-33-37	525
	4 7/8	1123-33-47	598
	5 7/8	1123-33-57	670
3 7/8	1 3/8	1123-37-13	381
	1 7/8	1123-37-17	417
	2 3/8	1123-37-23	453
	2 7/8	1123-37-27	489
	3 3/8	1123-37-33	525
	3 7/8	1123-37-37	562
	4 7/8	1123-37-47	634
	5 7/8	1123-37-57	706
4 3/8	1 3/8	1123-47-13	453
	1 7/8	1123-47-17	489
	2 3/8	1123-47-23	525
	2 7/8	1123-47-27	562
	3 3/8	1123-47-33	598
	3 7/8	1123-47-37	634
	4 7/8	1123-47-47	706
	5 7/8	1123-47-57	779
4 7/8	1 3/8	1123-57-13	525
	1 7/8	1123-57-17	562
	2 3/8	1123-57-23	598
	2 7/8	1123-57-27	634
	3 3/8	1123-57-33	670
	3 7/8	1123-57-37	706
	4 7/8	1123-57-47	779
	5 7/8	1123-57-57	851


Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel (No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

11 $\frac{7}{8}$ x 12 and 11 $\frac{7}{8}$ x 15




A	B	ITEM NUMBER	NET WT.
$\frac{7}{8}$	$\frac{7}{8}$	1212-7-7	71
	1 $\frac{1}{8}$	1212-7-13	91
	1 $\frac{7}{8}$	1212-7-17	112
	2 $\frac{1}{8}$	1212-7-23	132
	2 $\frac{7}{8}$	1212-7-27	152
	3 $\frac{1}{8}$	1212-7-33	172
	3 $\frac{7}{8}$	1212-7-37	192
	4 $\frac{7}{8}$	1212-7-47	233
$1\frac{3}{8}$	5 $\frac{1}{8}$	1212-7-57	273
	$\frac{7}{8}$	1212-13-7	91
	1 $\frac{1}{8}$	1212-13-13	112
	1 $\frac{7}{8}$	1212-13-17	132
	2 $\frac{1}{8}$	1212-13-23	152
	2 $\frac{7}{8}$	1212-13-27	172
	3 $\frac{1}{8}$	1212-13-33	192
	3 $\frac{7}{8}$	1212-13-37	212
$1\frac{7}{8}$	4 $\frac{1}{8}$	1212-13-47	253
	5 $\frac{1}{8}$	1212-13-57	293
	$\frac{7}{8}$	1212-17-7	112
	1 $\frac{1}{8}$	1212-17-13	132
	1 $\frac{7}{8}$	1212-17-17	152
	2 $\frac{1}{8}$	1212-17-23	172
	2 $\frac{7}{8}$	1212-17-27	192
	3 $\frac{1}{8}$	1212-17-33	212
$2\frac{3}{8}$	3 $\frac{7}{8}$	1212-17-37	233
	4 $\frac{1}{8}$	1212-17-47	273
	5 $\frac{1}{8}$	1212-17-57	313
	$\frac{7}{8}$	1212-23-7	132
	1 $\frac{1}{8}$	1212-23-13	152
	1 $\frac{7}{8}$	1212-23-17	172
	2 $\frac{1}{8}$	1212-23-23	192
	2 $\frac{7}{8}$	1212-23-27	212
$2\frac{7}{8}$	3 $\frac{1}{8}$	1212-23-33	233
	3 $\frac{7}{8}$	1212-23-37	253
	4 $\frac{1}{8}$	1212-23-47	293
	5 $\frac{1}{8}$	1212-23-57	334
	$\frac{7}{8}$	1212-27-7	152
	1 $\frac{1}{8}$	1212-27-13	172
	1 $\frac{7}{8}$	1212-27-17	192
	2 $\frac{1}{8}$	1212-27-23	212
$2\frac{1}{2}$	2 $\frac{7}{8}$	1212-27-27	233
	3 $\frac{1}{8}$	1212-27-33	253
	3 $\frac{7}{8}$	1212-27-37	273
	4 $\frac{1}{8}$	1212-27-47	313
	5 $\frac{1}{8}$	1212-27-57	354

A	B	ITEM NUMBER	NET WT.
$3\frac{3}{8}$	$\frac{7}{8}$	1212-33-7	172
	1 $\frac{1}{8}$	1212-33-13	192
	1 $\frac{7}{8}$	1212-33-17	212
	2 $\frac{1}{8}$	1212-33-23	233
	2 $\frac{7}{8}$	1212-33-27	253
	3 $\frac{1}{8}$	1212-33-33	273
	3 $\frac{7}{8}$	1212-33-37	293
	4 $\frac{1}{8}$	1212-33-47	334
$3\frac{7}{8}$	5 $\frac{1}{8}$	1212-33-57	374
	$\frac{7}{8}$	1212-37-7	192
	1 $\frac{1}{8}$	1212-37-13	212
	1 $\frac{7}{8}$	1212-37-17	233
	2 $\frac{1}{8}$	1212-37-23	253
	2 $\frac{7}{8}$	1212-37-27	273
	3 $\frac{1}{8}$	1212-37-33	293
	3 $\frac{7}{8}$	1212-37-37	313
$4\frac{1}{8}$	4 $\frac{1}{8}$	1212-37-47	354
	5 $\frac{1}{8}$	1212-37-57	394
	$\frac{7}{8}$	1212-47-7	233
	1 $\frac{1}{8}$	1212-47-13	253
	1 $\frac{7}{8}$	1212-47-17	273
	2 $\frac{1}{8}$	1212-47-23	293
	2 $\frac{7}{8}$	1212-47-27	313
	3 $\frac{1}{8}$	1212-47-33	334
$5\frac{1}{8}$	3 $\frac{7}{8}$	1212-47-37	354
	4 $\frac{1}{8}$	1212-47-47	394
	5 $\frac{1}{8}$	1212-47-57	435
	$\frac{7}{8}$	1212-57-7	273
	1 $\frac{1}{8}$	1212-57-13	293
	1 $\frac{7}{8}$	1212-57-17	313
	2 $\frac{1}{8}$	1212-57-23	334
	2 $\frac{7}{8}$	1212-57-27	354
$5\frac{7}{8}$	3 $\frac{1}{8}$	1212-57-33	374
	3 $\frac{7}{8}$	1212-57-37	394
	4 $\frac{1}{8}$	1212-57-47	435
	5 $\frac{1}{8}$	1212-57-57	475

Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:


- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2 $\frac{1}{2}$ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment



A	B	ITEM NUMBER	NET WT.
$\frac{7}{8}$	$\frac{7}{8}$	1215-7-7	89
	1 $\frac{1}{8}$	1215-7-13	114
	1 $\frac{7}{8}$	1215-7-17	139
	2 $\frac{1}{8}$	1215-7-23	164
	2 $\frac{7}{8}$	1215-7-27	190
	3 $\frac{1}{8}$	1215-7-33	215
	3 $\frac{7}{8}$	1215-7-37	240
	4 $\frac{1}{8}$	1215-7-47	291
$1\frac{3}{8}$	5 $\frac{1}{8}$	1215-7-57	341
	$\frac{7}{8}$	1215-13-7	114
	1 $\frac{1}{8}$	1215-13-13	139
	1 $\frac{7}{8}$	1215-13-17	164
	2 $\frac{1}{8}$	1215-13-23	190
	2 $\frac{7}{8}$	1215-13-27	215
	3 $\frac{1}{8}$	1215-13-33	240
	3 $\frac{7}{8}$	1215-13-37	265
$1\frac{7}{8}$	4 $\frac{1}{8}$	1215-13-47	316
	5 $\frac{1}{8}$	1215-13-57	366
	$\frac{7}{8}$	1215-17-7	139
	1 $\frac{1}{8}$	1215-17-13	164
	1 $\frac{7}{8}$	1215-17-17	190
	2 $\frac{1}{8}$	1215-17-23	215
	2 $\frac{7}{8}$	1215-17-27	240
	3 $\frac{1}{8}$	1215-17-33	265
$2\frac{3}{8}$	3 $\frac{7}{8}$	1215-17-37	291
	4 $\frac{1}{8}$	1215-17-47	341
	5 $\frac{1}{8}$	1215-17-57	392
	$\frac{7}{8}$	1215-23-7	164
	1 $\frac{1}{8}$	1215-23-13	190
	1 $\frac{7}{8}$	1215-23-17	215
	2 $\frac{1}{8}$	1215-23-23	240
	2 $\frac{7}{8}$	1215-23-27	265
$2\frac{1}{2}$	3 $\frac{1}{8}$	1215-23-33	291
	3 $\frac{7}{8}$	1215-23-37	316
	4 $\frac{1}{8}$	1215-23-47	366
	5 $\frac{1}{8}$	1215-23-57	417

A	B	ITEM NUMBER	NET WT.
$2\frac{7}{8}$	$\frac{7}{8}$	1215-27-7	190
	1 $\frac{1}{8}$	1215-27-13	215
	1 $\frac{7}{8}$	1215-27-17	240
	2 $\frac{1}{8}$	1215-27-23	265
	2 $\frac{7}{8}$	1215-27-27	291
	3 $\frac{1}{8}$	1215-27-33	316
	3 $\frac{7}{8}$	1215-27-37	341
	4 $\frac{1}{8}$	1215-27-47	392
$3\frac{3}{8}$	5 $\frac{1}{8}$	1215-27-57	442
	$\frac{7}{8}$	1215-33-7	215
	1 $\frac{1}{8}$	1215-33-13	240
	1 $\frac{7}{8}$	1215-33-17	265
	2 $\frac{1}{8}$	1215-33-23	291
	2 $\frac{7}{8}$	1215-33-27	316
	3 $\frac{1}{8}$	1215-33-33	341
	3 $\frac{7}{8}$	1215-33-37	366
$3\frac{7}{8}$	4 $\frac{1}{8}$	1215-33-47	417
	5 $\frac{1}{8}$	1215-33-57	467
	$\frac{7}{8}$	1215-37-7	240
	1 $\frac{1}{8}$	1215-37-13	265
	1 $\frac{7}{8}$	1215-37-17	291
	2 $\frac{1}{8}$	1215-37-23	316
	2 $\frac{7}{8}$	1215-37-27	341
	3 $\frac{1}{8}$	1215-37-33	366
$4\frac{1}{8}$	3 $\frac{7}{8}$	1215-37-37	392
	4 $\frac{1}{8}$	1215-37-47	442
	5 $\frac{1}{8}$	1215-37-57	492
	$\frac{7}{8}$	1215-47-7	291
	1 $\frac{1}{8}$	1215-47-13	316
	1 $\frac{7}{8}$	1215-47-17	341
	2 $\frac{1}{8}$	1215-47-23	366
	2 $\frac{7}{8}$	1215-47-27	392
$5\frac{1}{8}$	3 $\frac{1}{8}$	1215-47-33	417
	3 $\frac{7}{8}$	1215-47-37	442
	4 $\frac{1}{8}$	1215-47-47	492
	5 $\frac{1}{8}$	1215-47-57	543
	$\frac{7}{8}$	1215-57-7	341
	1 $\frac{1}{8}$	1215-57-13	366
	1 $\frac{7}{8}$	1215-57-17	392
	2 $\frac{1}{8}$	1215-57-23	417
$5\frac{7}{8}$	2 $\frac{7}{8}$	1215-57-27	442
	3 $\frac{1}{8}$	1215-57-33	467
	3 $\frac{7}{8}$	1215-57-37	492
	4 $\frac{1}{8}$	1215-57-47	543
	5 $\frac{1}{8}$	1215-57-57	593

Cavity Retainer Sets



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1220-7-7	118
	1 3/8	1220-7-13	152
	1 7/8	1220-7-17	186
	2 3/8	1220-7-23	219
	2 7/8	1220-7-27	253
	3 3/8	1220-7-33	286
	3 7/8	1220-7-37	320
	4 7/8	1220-7-47	387
	5 7/8	1220-7-57	455

1³/₈	7₈	1220-13-7	152
	1³/₈	1220-13-13	186
	1⁷/₈	1220-13-17	219
	2³/₈	1220-13-23	253
	2⁷/₈	1220-13-27	286
	3³/₈	1220-13-33	320
	3⁷/₈	1220-13-37	354
	4⁷/₈	1220-13-47	421
	5⁷/₈	1220-13-57	488

1 ⁷ / ₈	7 ⁵ / ₈	1220-17-7	186
	1 ³ / ₈	1220-17-13	219
	1 ¹ / ₈	1220-17-17	253
	2 ³ / ₈	1220-17-23	286
	2 ¹ / ₈	1220-17-27	320
	3 ³ / ₈	1220-17-33	354
	3 ¹ / ₈	1220-17-37	387
	4 ¹ / ₈	1220-17-47	455
5 ¹ / ₈	1220-17-57	522	

2³/₈	7/8	1220-23-7	219
	13/8	1220-23-13	253
	17/8	1220-23-17	286
	23/8	1220-23-23	320
	27/8	1220-23-27	354
	33/8	1220-23-33	387
	37/8	1220-23-37	421
	47/8	1220-23-47	488
	57/8	1220-23-57	556


2 ⁷ / ₈	7 ₈	1220-27-7	253
	1 ³ / ₈	1220-27-13	286
	1 ⁵ / ₈	1220-27-17	320
	2 ³ / ₈	1220-27-23	354
	2 ⁵ / ₈	1220-27-27	387
	3 ³ / ₈	1220-27-33	421
	3 ⁵ / ₈	1220-27-37	455
	4 ⁷ / ₈	1220-27-47	522
5 ⁷ / ₈	1220-27-57	589	

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	7⁄8	1220-33-7	286
	1 ³ / ₈	1220-33-13	320
	1 ⁷ / ₈	1220-33-17	354
	2 ³ / ₈	1220-33-23	387
	2 ⁷ / ₈	1220-33-27	421
	3 ³ / ₈	1220-33-33	455
	3 ⁷ / ₈	1220-33-37	488
	4 ⁷ / ₈	1220-33-47	556
5 ⁷ / ₈	1220-33-57	623	

3⁷/₈	7⁸/₈	1220-37-7	320
	1³/₈	1220-37-13	354
	1⁷/₈	1220-37-17	387
	2³/₈	1220-37-23	421
	2⁷/₈	1220-37-27	455
	3³/₈	1220-37-33	488
	3⁷/₈	1220-37-37	522
	4⁷/₈	1220-37-47	589
	5⁷/₈	1220-37-57	656

4⁷/₈	7₈	1220-47-7	387
	1³/₈	1220-47-13	421
	1⁵/₈	1220-47-17	455
	2³/₈	1220-47-23	488
	2⁵/₈	1220-47-27	522
	3³/₈	1220-47-33	556
	3⁵/₈	1220-47-37	589
	4¹/₈	1220-47-47	656
	5¹/₈	1220-47-57	724

5 7/8	7/8	1220-57-7	455
	1 3/8	1220-57-13	488
	1 7/8	1220-57-17	522
	2 3/8	1220-57-23	556
	2 7/8	1220-57-27	589
	3 3/8	1220-57-33	623
	3 7/8	1220-57-37	656
	4 7/8	1220-57-47	724
	5 7/8	1220-57-57	791



A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1%	1223-13-13	218
	1%	1223-13-17	257
	2%	1223-13-23	297
	2%	1223-13-27	336
	3%	1223-13-33	376
	3%	1223-13-37	416
	4%	1223-13-47	495
	5%	1223-13-57	574

1⁷/₈	1%	1223-17-13	257
	1%	1223-17-17	297
	2%	1223-17-23	336
	2%	1223-17-27	376
	3%	1223-17-33	416
	3%	1223-17-37	455
	4%	1223-17-47	534
	5%	1223-17-57	613

2³/₈	1%	1223-23-13	297
	1%	1223-23-17	336
	2%	1223-23-23	376
	2%	1223-23-27	416
	3%	1223-23-33	455
	3%	1223-23-37	495
	4%	1223-23-47	574
	5%	1223-23-57	653

2⁷/₈	1 ¹ / ₈	1223-27-13	336
	1 ⁷ / ₈	1223-27-17	376
	2 ¹ / ₈	1223-27-23	416
	2 ⁷ / ₈	1223-27-27	455
	3 ¹ / ₈	1223-27-33	495
	3 ⁷ / ₈	1223-27-37	534
	4 ¹ / ₈	1223-27-47	613
	5 ¹ / ₈	1223-27-57	692

A	B	ITEM NUMBER	NET WT.
3^{3/8}	1 ^{3/8}	1223-33-13	376
	1 ^{7/8}	1223-33-17	416
	2 ^{3/8}	1223-33-23	455
	2 ^{7/8}	1223-33-27	495
	3 ^{3/8}	1223-33-33	534
	3 ^{7/8}	1223-33-37	574
	4 ^{7/8}	1223-33-47	653
	5 ^{7/8}	1223-33-57	732

3⁷/₈	1 ³ / ₈	1223-37-13	416
	1 ⁷ / ₈	1223-37-17	455
	2 ³ / ₈	1223-37-23	495
	2 ⁷ / ₈	1223-37-27	534
	3 ³ / ₈	1223-37-33	574
	3 ⁷ / ₈	1223-37-37	613
	4 ³ / ₈	1223-37-47	692
	5 ⁷ / ₈	1223-37-57	771

47₈	1 $\frac{1}{8}$	1223-47-13	495
	1 $\frac{7}{8}$	1223-47-17	534
	2 $\frac{3}{8}$	1223-47-23	574
	2 $\frac{7}{8}$	1223-47-27	613
	3 $\frac{3}{8}$	1223-47-33	653
	3 $\frac{7}{8}$	1223-47-37	692
	4 $\frac{7}{8}$	1223-47-47	771
	5 $\frac{7}{8}$	1223-47-57	850

5/8	1 3/8	1223-57-13	574
	1 7/8	1223-57-17	613
	2 3/8	1223-57-23	653
	2 7/8	1223-57-27	692
	3 3/8	1223-57-33	732
	3 7/8	1223-57-37	771
	4 7/8	1223-57-47	850
	5 7/8	1223-57-57	929



Thickness of each plate is finish ground $\pm .001"$. Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2 $\frac{7}{8}$ thick)
3. L Dimension (Guide Pin Length)
4. Method of Shipment

Cavity Retainer Sets

13³/₈ × 15 and 13³/₈ × 18



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1315-7-7	100
	1 1/8	1315-7-13	128
	1 1/4	1315-7-17	157
	2 1/8	1315-7-23	185
	2 1/4	1315-7-27	214
	3 1/8	1315-7-33	242
	3 1/4	1315-7-37	270
	4 1/8	1315-7-47	327
1 3/8	5 1/8	1315-7-57	384
	7/8	1315-13-7	128
	1 1/8	1315-13-13	157
	1 1/4	1315-13-17	185
	2 1/8	1315-13-23	214
	2 1/4	1315-13-27	242
	3 1/8	1315-13-33	270
	3 1/4	1315-13-37	299
1 7/8	4 1/8	1315-13-47	356
	5 1/8	1315-13-57	413
	7/8	1315-17-7	157
	1 1/8	1315-17-13	185
	1 1/4	1315-17-17	214
	2 1/8	1315-17-23	242
	2 1/4	1315-17-27	270
	3 1/8	1315-17-33	299
2 3/8	3 1/4	1315-17-37	327
	4 1/8	1315-17-47	384
	5 1/8	1315-17-57	441
	7/8	1315-23-7	185
	1 1/8	1315-23-13	214
	1 1/4	1315-23-17	242
	2 1/8	1315-23-23	270
	2 1/4	1315-23-27	299
2 7/8	3 1/8	1315-23-33	327
	3 1/4	1315-23-37	356
	4 1/8	1315-23-47	413
	5 1/8	1315-23-57	469
	7/8	1315-27-7	214
	1 1/8	1315-27-13	242
	1 1/4	1315-27-17	270
	2 1/8	1315-27-23	299

A	B	ITEM NUMBER	NET WT.
3 3/8	7/8	1315-33-7	242
	1 1/8	1315-33-13	270
	1 1/4	1315-33-17	299
	2 1/8	1315-33-23	327
	2 1/4	1315-33-27	356
	3 1/8	1315-33-33	384
	3 1/4	1315-33-37	413
	4 1/8	1315-33-47	469
3 7/8	5 1/8	1315-33-57	526
	7/8	1315-37-7	270
	1 1/8	1315-37-13	299
	1 1/4	1315-37-17	327
	2 1/8	1315-37-23	356
	2 1/4	1315-37-27	384
	3 1/8	1315-37-33	413
	3 1/4	1315-37-37	441
4 3/8	4 1/8	1315-37-47	498
	5 1/8	1315-37-57	555
	7/8	1315-47-7	327
	1 1/8	1315-47-13	356
	1 1/4	1315-47-17	384
	2 1/8	1315-47-23	413
	2 1/4	1315-47-27	441
	3 1/8	1315-47-33	469
5 3/8	3 1/4	1315-47-37	498
	4 1/8	1315-47-47	555
	5 1/8	1315-47-57	612
	7/8	1315-57-7	384
	1 1/8	1315-57-13	413
	1 1/4	1315-57-17	441
	2 1/8	1315-57-23	469
	2 1/4	1315-57-27	498
5 7/8	3 1/8	1315-57-33	526
	3 1/4	1315-57-37	555
	4 1/8	1315-57-47	612
	5 1/8	1315-57-57	668

A	B	ITEM NUMBER	NET WT.
7/8	7/8	1318-7-7	120
	1 1/8	1318-7-13	154
	1 1/4	1318-7-17	188
	2 1/8	1318-7-23	222
	2 1/4	1318-7-27	256
	3 1/8	1318-7-33	290
	3 1/4	1318-7-37	324
	4 1/8	1318-7-47	393
1 3/8	5 1/8	1318-7-57	461
	7/8	1318-13-7	154
	1 1/8	1318-13-13	188
	1 1/4	1318-13-17	222
	2 1/8	1318-13-23	256
	2 1/4	1318-13-27	290
	3 1/8	1318-13-33	324
	3 1/4	1318-13-37	359
1 7/8	4 1/8	1318-13-47	427
	5 1/8	1318-13-57	495
	7/8	1318-17-7	188
	1 1/8	1318-17-13	222
	1 1/4	1318-17-17	256
	2 1/8	1318-17-23	290
	2 1/4	1318-17-27	324
	3 1/8	1318-17-33	359
2 3/8	3 1/4	1318-17-37	393
	4 1/8	1318-17-47	461
	5 1/8	1318-17-57	529
	7/8	1318-23-7	222
	1 1/8	1318-23-13	256
	1 1/4	1318-23-17	290
	2 1/8	1318-23-23	324
	2 1/4	1318-23-27	359
2 7/8	3 1/8	1318-23-33	393
	3 1/4	1318-23-37	427
	4 1/8	1318-23-47	495
	5 1/8	1318-23-57	563

A	B	ITEM NUMBER	NET WT.
2 1/8	7/8	1318-27-7	256
	1 1/8	1318-27-13	290
	1 1/4	1318-27-17	324
	2 1/8	1318-27-23	359
	2 1/4	1318-27-27	393
	3 1/8	1318-27-33	427
	3 1/4	1318-27-37	461
	4 1/8	1318-27-47	529
3 3/8	5 1/8	1318-27-57	597
	7/8	1318-33-7	290
	1 1/8	1318-33-13	324
	1 1/4	1318-33-17	359
	2 1/8	1318-33-23	393
	2 1/4	1318-33-27	427
	3 1/8	1318-33-33	461
	3 1/4	1318-33-37	495
3 7/8	4 1/8	1318-33-47	563
	5 1/8	1318-33-57	631
	7/8	1318-37-7	324
	1 1/8	1318-37-13	359
	1 1/4	1318-37-17	393
	2 1/8	1318-37-23	427
	2 1/4	1318-37-27	461
	3 1/8	1318-37-33	495
4 3/8	3 1/4	1318-37-37	529
	4 1/8	1318-37-47	597
	5 1/8	1318-37-57	665
	7/8	1318-47-7	393
	1 1/8	1318-47-13	427
	1 1/4	1318-47-17	461
	2 1/8	1318-47-23	495
	2 1/4	1318-47-27	529
4 7/8	3 1/8	1318-47-33	563
	3 1/4	1318-47-37	597
	4 1/8	1318-47-47	665
	5 1/8	1318-47-57	734
5 3/8	7/8	1318-57-7	461
	1 1/8	1318-57-13	495
	1 1/4	1318-57-17	529
	2 1/8	1318-57-23	563
	2 1/4	1318-57-27	597
	3 1/8	1318-57-33	631
	3 1/4	1318-57-37	665
	4 1/8	1318-57-47	734
5 7/8	5 1/8	1318-57-57	802

Thickness of each plate is finish ground $\pm .001$ ".


Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
 - No. 1, No. 3 or No. 7 Steel
 - L Dimension (Guide Pin Length)
 - Method of Shipment
- (No. 7 Steel available standard only for plates up to and including 2 1/2" thick)


Cavity Retainer Sets

13³/₈ × 20³/₄ and 13³/₈ × 23¹/₂



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1321-7-7	138
	1 1/8	1321-7-13	177
	1 1/4	1321-7-17	217
	2 3/8	1321-7-23	256
	2 7/8	1321-7-27	295
	3 3/8	1321-7-33	335
	3 7/8	1321-7-37	374
	4 7/8	1321-7-47	453
	5 7/8	1321-7-57	531
1 3/8	7/8	1321-13-7	177
	1 1/8	1321-13-13	217
	1 1/4	1321-13-17	256
	2 3/8	1321-13-23	295
	2 7/8	1321-13-27	335
	3 3/8	1321-13-33	374
	3 7/8	1321-13-37	413
	4 7/8	1321-13-47	492
	5 7/8	1321-13-57	570
1 7/8	7/8	1321-17-7	217
	1 1/8	1321-17-13	256
	1 1/4	1321-17-17	295
	2 3/8	1321-17-23	335
	2 7/8	1321-17-27	374
	3 3/8	1321-17-33	413
	3 7/8	1321-17-37	453
	4 7/8	1321-17-47	531
	5 7/8	1321-17-57	610
2 3/8	7/8	1321-23-7	256
	1 1/8	1321-23-13	295
	1 1/4	1321-23-17	335
	2 3/8	1321-23-23	374
	2 7/8	1321-23-27	413
	3 3/8	1321-23-33	453
	3 7/8	1321-23-37	492
	4 7/8	1321-23-47	570
	5 7/8	1321-23-57	649
2 7/8	7/8	1321-27-7	295
	1 1/8	1321-27-13	335
	1 1/4	1321-27-17	374
	2 3/8	1321-27-23	413
	2 7/8	1321-27-27	453
	3 3/8	1321-27-33	492
	3 7/8	1321-27-37	531
	4 7/8	1321-27-47	610
	5 7/8	1321-27-57	688

A	B	ITEM NUMBER	NET WT.
2 7/8	7/8	1321-27-7	295
	1 1/8	1321-27-13	335
	1 1/4	1321-27-17	374
	2 3/8	1321-27-23	413
	2 7/8	1321-27-27	453
	3 3/8	1321-27-33	492
	3 7/8	1321-27-37	531
	4 7/8	1321-27-47	610
	5 7/8	1321-27-57	688
3 3/8	7/8	1321-33-7	335
	1 1/8	1321-33-13	374
	1 1/4	1321-33-17	413
	2 3/8	1321-33-23	453
	2 7/8	1321-33-27	492
	3 3/8	1321-33-33	531
	3 7/8	1321-33-37	570
	4 7/8	1321-33-47	649
	5 7/8	1321-33-57	728
3 7/8	7/8	1321-37-7	374
	1 1/8	1321-37-13	413
	1 1/4	1321-37-17	453
	2 3/8	1321-37-23	492
	2 7/8	1321-37-27	531
	3 3/8	1321-37-33	570
	3 7/8	1321-37-37	610
	4 7/8	1321-37-47	688
	5 7/8	1321-37-57	767
4 7/8	7/8	1321-47-7	453
	1 1/8	1321-47-13	492
	1 1/4	1321-47-17	531
	2 3/8	1321-47-23	570
	2 7/8	1321-47-27	610
	3 3/8	1321-47-33	649
	3 7/8	1321-47-37	688
	4 7/8	1321-47-47	767
	5 7/8	1321-47-57	846
5 7/8	7/8	1321-57-7	531
	1 1/8	1321-57-13	570
	1 1/4	1321-57-17	610
	2 3/8	1321-57-23	649
	2 7/8	1321-57-27	688
	3 3/8	1321-57-33	728
	3 7/8	1321-57-37	767
	4 7/8	1321-57-47	846
	5 7/8	1321-57-57	924



A	B	ITEM NUMBER	NET WT.
1 3/8	1 3/8	1323-13-13	245
	1 7/8	1323-13-17	290
	2 3/8	1323-13-23	334
	2 7/8	1323-13-27	379
	3 3/8	1323-13-33	423
	3 7/8	1323-13-37	468
	4 7/8	1323-13-47	557
	5 7/8	1323-13-57	646
	1 3/8	1323-17-13	290
1 7/8	1 7/8	1323-17-17	334
	2 3/8	1323-17-23	379
	2 7/8	1323-17-27	423
	3 3/8	1323-17-33	468
	3 7/8	1323-17-37	512
	4 7/8	1323-17-47	602
	5 7/8	1323-17-57	691
	1 3/8	1323-23-13	334
2 3/8	1 7/8	1323-23-17	379
	2 3/8	1323-23-23	423
	2 7/8	1323-23-27	468
	3 3/8	1323-23-33	512
	3 7/8	1323-23-37	557
	4 7/8	1323-23-47	646
	5 7/8	1323-23-57	735
	1 3/8	1323-27-13	379
2 7/8	1 7/8	1323-27-17	423
	2 3/8	1323-27-23	468
	2 7/8	1323-27-27	512
	3 3/8	1323-27-33	557
	3 7/8	1323-27-37	602
	4 7/8	1323-27-47	691
	5 7/8	1323-27-57	780

A	B	ITEM NUMBER	NET WT.
3 3/8	1 3/8	1323-33-13	423
	1 7/8	1323-33-17	468
	2 3/8	1323-33-23	512
	2 7/8	1323-33-27	557
	3 3/8	1323-33-33	602
	3 7/8	1323-33-37	646
	4 7/8	1323-33-47	735
	5 7/8	1323-33-57	824
	1 3/8	1323-37-13	468
3 7/8	1 7/8	1323-37-17	512
	2 3/8	1323-37-23	557
	2 7/8	1323-37-27	602
	3 3/8	1323-37-33	646
	3 7/8	1323-37-37	691
	4 7/8	1323-37-47	780
	5 7/8	1323-37-57	869
	1 3/8	1323-47-13	557
4 7/8	1 7/8	1323-47-17	602
	2 3/8	1323-47-23	646
	2 7/8	1323-47-27	691
	3 3/8	1323-47-33	735
	3 7/8	1323-47-37	780
	4 7/8	1323-47-47	869
	5 7/8	1323-47-57	958
	1 3/8	1323-57-13	646
5 7/8	1 7/8	1323-57-17	691
	2 3/8	1323-57-23	735
	2 7/8	1323-57-27	780
	3 3/8	1323-57-33	824
	3 7/8	1323-57-37	869
	4 7/8	1323-57-47	958
	5 7/8	1323-57-57	1047



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
 - No. 1, No. 3 or No. 7 Steel
 - L Dimension (Guide Pin Length)
 - Method of Shipment
- (No. 7 Steel available standard only for plates up to and including 2% thick)

Cavity Retainer Sets

13³/₈ × 26" and 13³/₈ × 29¹/₂"



A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1326-13-13	271
	1 ⁷ / ₈	1326-13-17	321
	2 ³ / ₈	1326-13-23	370
	2 ⁷ / ₈	1326-13-27	419
	3 ³ / ₈	1326-13-33	468
	3 ⁷ / ₈	1326-13-37	518
	4 ⁷ / ₈	1326-13-47	616
	5 ⁷ / ₈	1326-13-57	715
1 ⁷ / ₈	1 ³ / ₈	1326-17-13	321
	1 ⁷ / ₈	1326-17-17	370
	2 ³ / ₈	1326-17-23	419
	2 ⁷ / ₈	1326-17-27	468
	3 ³ / ₈	1326-17-33	518
	3 ⁷ / ₈	1326-17-37	567
	4 ⁷ / ₈	1326-17-47	666
	5 ⁷ / ₈	1326-17-57	764
2 ³ / ₈	1 ³ / ₈	1326-23-13	370
	1 ⁷ / ₈	1326-23-17	419
	2 ³ / ₈	1326-23-23	468
	2 ⁷ / ₈	1326-23-27	518
	3 ³ / ₈	1326-23-33	567
	3 ⁷ / ₈	1326-23-37	616
	4 ⁷ / ₈	1326-23-47	715
	5 ⁷ / ₈	1326-23-57	813
2 ⁷ / ₈	1 ³ / ₈	1326-27-13	419
	1 ⁷ / ₈	1326-27-17	468
	2 ³ / ₈	1326-27-23	518
	2 ⁷ / ₈	1326-27-27	567
	3 ³ / ₈	1326-27-33	616
	3 ⁷ / ₈	1326-27-37	666
	4 ⁷ / ₈	1326-27-47	764
	5 ⁷ / ₈	1326-27-57	863

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1326-33-13	468
	1 ⁷ / ₈	1326-33-17	518
	2 ³ / ₈	1326-33-23	567
	2 ⁷ / ₈	1326-33-27	616
	3 ³ / ₈	1326-33-33	666
	3 ⁷ / ₈	1326-33-37	715
	4 ⁷ / ₈	1326-33-47	813
	5 ⁷ / ₈	1326-33-57	912
3 ⁷ / ₈	1 ³ / ₈	1326-37-13	518
	1 ⁷ / ₈	1326-37-17	567
	2 ³ / ₈	1326-37-23	616
	2 ⁷ / ₈	1326-37-27	666
	3 ³ / ₈	1326-37-33	715
	3 ⁷ / ₈	1326-37-37	764
	4 ⁷ / ₈	1326-37-47	863
	5 ⁷ / ₈	1326-37-57	961
4 ⁷ / ₈	1 ³ / ₈	1326-47-13	616
	1 ⁷ / ₈	1326-47-17	666
	2 ³ / ₈	1326-47-23	715
	2 ⁷ / ₈	1326-47-27	764
	3 ³ / ₈	1326-47-33	813
	3 ⁷ / ₈	1326-47-37	863
	4 ⁷ / ₈	1326-47-47	961
	5 ⁷ / ₈	1326-47-57	1060
5 ⁷ / ₈	1 ³ / ₈	1326-57-13	715
	1 ⁷ / ₈	1326-57-17	764
	2 ³ / ₈	1326-57-23	813
	2 ⁷ / ₈	1326-57-27	863
	3 ³ / ₈	1326-57-33	912
	3 ⁷ / ₈	1326-57-37	961
	4 ⁷ / ₈	1326-57-47	1060
	5 ⁷ / ₈	1326-57-57	1158

A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1329-13-13	308
	1 ⁷ / ₈	1329-13-17	364
	2 ³ / ₈	1329-13-23	420
	2 ⁷ / ₈	1329-13-27	476
	3 ³ / ₈	1329-13-33	531
	3 ⁷ / ₈	1329-13-37	587
	4 ⁷ / ₈	1329-13-47	699
	5 ⁷ / ₈	1329-13-57	811
1 ⁷ / ₈	1 ³ / ₈	1329-17-13	364
	1 ⁷ / ₈	1329-17-17	420
	2 ³ / ₈	1329-17-23	476
	2 ⁷ / ₈	1329-17-27	531
	3 ³ / ₈	1329-17-33	587
	3 ⁷ / ₈	1329-17-37	643
	4 ⁷ / ₈	1329-17-47	755
	5 ⁷ / ₈	1329-17-57	867
2 ³ / ₈	1 ³ / ₈	1329-23-13	420
	1 ⁷ / ₈	1329-23-17	476
	2 ³ / ₈	1329-23-23	531
	2 ⁷ / ₈	1329-23-27	587
	3 ³ / ₈	1329-23-33	643
	3 ⁷ / ₈	1329-23-37	699
	4 ⁷ / ₈	1329-23-47	811
	5 ⁷ / ₈	1329-23-57	923
2 ⁷ / ₈	1 ³ / ₈	1329-27-13	476
	1 ⁷ / ₈	1329-27-17	531
	2 ³ / ₈	1329-27-23	587
	2 ⁷ / ₈	1329-27-27	643
	3 ³ / ₈	1329-27-33	699
	3 ⁷ / ₈	1329-27-37	755
	4 ⁷ / ₈	1329-27-47	867
	5 ⁷ / ₈	1329-27-57	979

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1329-33-13	531
	1 ⁷ / ₈	1329-33-17	587
	2 ³ / ₈	1329-33-23	643
	2 ⁷ / ₈	1329-33-27	699
	3 ³ / ₈	1329-33-33	755
	3 ⁷ / ₈	1329-33-37	811
	4 ⁷ / ₈	1329-33-47	923
	5 ⁷ / ₈	1329-33-57	1034
3 ⁷ / ₈	1 ³ / ₈	1329-37-13	587
	1 ⁷ / ₈	1329-37-17	643
	2 ³ / ₈	1329-37-23	699
	2 ⁷ / ₈	1329-37-27	755
	3 ³ / ₈	1329-37-33	811
	3 ⁷ / ₈	1329-37-37	867
	4 ⁷ / ₈	1329-37-47	979
	5 ⁷ / ₈	1329-37-57	1090
4 ⁷ / ₈	1 ³ / ₈	1329-47-13	699
	1 ⁷ / ₈	1329-47-17	755
	2 ³ / ₈	1329-47-23	811
	2 ⁷ / ₈	1329-47-27	867
	3 ³ / ₈	1329-47-33	923
	3 ⁷ / ₈	1329-47-37	979
	4 ⁷ / ₈	1329-47-47	1090
	5 ⁷ / ₈	1329-47-57	1202
5 ⁷ / ₈	1 ³ / ₈	1329-57-13	811
	1 ⁷ / ₈	1329-57-17	867
	2 ³ / ₈	1329-57-23	923
	2 ⁷ / ₈	1329-57-27	979
	3 ³ / ₈	1329-57-33	1034
	3 ⁷ / ₈	1329-57-37	1090
	4 ⁷ / ₈	1329-57-47	1202
	5 ⁷ / ₈	1329-57-57	1314



Thickness of each plate is finish ground $\pm .001"$. Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

13³/₈ × 23¹/₂ and 13³/₈ × 26"



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1518-7-7	132
	1 1/8	1518-7-13	170
	1 3/8	1518-7-17	208
	2 1/8	1518-7-23	245
	2 3/8	1518-7-27	283
	3 1/8	1518-7-33	321
	3 3/8	1518-7-37	358
	4 1/8	1518-7-47	434
1 3/8	5 1/8	1518-7-57	509
	7/8	1518-13-7	170
	1 1/8	1518-13-13	208
	1 3/8	1518-13-17	245
	2 1/8	1518-13-23	283
	2 3/8	1518-13-27	321
	3 1/8	1518-13-33	358
	3 3/8	1518-13-37	396
1 7/8	4 1/8	1518-13-47	471
	5 1/8	1518-13-57	547
	7/8	1518-17-7	208
	1 1/8	1518-17-13	245
	1 3/8	1518-17-17	283
	2 1/8	1518-17-23	321
	2 3/8	1518-17-27	358
	3 1/8	1518-17-33	396
2 3/8	3 3/8	1518-17-37	434
	4 1/8	1518-17-47	509
	5 1/8	1518-17-57	584
	7/8	1518-23-7	245
	1 1/8	1518-23-13	283
	1 3/8	1518-23-17	321
	2 1/8	1518-23-23	358
	2 3/8	1518-23-27	396
2 7/8	3 1/8	1518-23-33	434
	3 3/8	1518-23-37	471
	4 1/8	1518-23-47	547
	5 1/8	1518-23-57	622
	7/8	1518-27-7	283
	1 1/8	1518-27-13	321
	1 3/8	1518-27-17	358
	2 1/8	1518-27-23	396
2 7/8	2 3/8	1518-27-27	434
	3 1/8	1518-27-33	471
	3 3/8	1518-27-37	509
	4 1/8	1518-27-47	584
	5 1/8	1518-27-57	660

A	B	ITEM NUMBER	NET WT.
3 3/8	7/8	1518-33-7	321
	1 1/8	1518-33-13	358
	1 3/8	1518-33-17	396
	2 1/8	1518-33-23	434
	2 3/8	1518-33-27	471
	3 1/8	1518-33-33	509
	3 3/8	1518-33-37	547
	4 1/8	1518-33-47	622
3 7/8	5 1/8	1518-33-57	697
	7/8	1518-37-7	358
	1 1/8	1518-37-13	396
	1 3/8	1518-37-17	434
	2 1/8	1518-37-23	471
	2 3/8	1518-37-27	509
	3 1/8	1518-37-33	547
	3 3/8	1518-37-37	584
4 7/8	4 1/8	1518-37-47	660
	5 1/8	1518-37-57	735
	7/8	1518-47-7	434
	1 1/8	1518-47-13	471
	1 3/8	1518-47-17	509
	2 1/8	1518-47-23	547
	2 3/8	1518-47-27	584
	3 1/8	1518-47-33	622
5 7/8	3 3/8	1518-47-37	660
	4 1/8	1518-47-47	735
	5 1/8	1518-47-57	810
	7/8	1518-57-7	509
	1 1/8	1518-57-13	547
	1 3/8	1518-57-17	584
	2 1/8	1518-57-23	622
	2 3/8	1518-57-27	660
5 7/8	3 1/8	1518-57-33	697
	3 3/8	1518-57-37	735
	4 1/8	1518-57-47	810
	5 1/8	1518-57-57	886

A	B	ITEM NUMBER	NET WT.
1 3/8	1 3/8	1524-13-13	276
	1 7/8	1524-13-17	326
	2 3/8	1524-13-23	376
	2 7/8	1524-13-27	426
	3 3/8	1524-13-33	476
	3 7/8	1524-13-37	526
	4 3/8	1524-13-47	626
	5 3/8	1524-13-57	726
1 7/8	1 3/8	1524-17-13	326
	1 7/8	1524-17-17	376
	2 3/8	1524-17-23	426
	2 7/8	1524-17-27	476
	3 3/8	1524-17-33	526
	3 7/8	1524-17-37	576
	4 3/8	1524-17-47	676
	5 3/8	1524-17-57	776
2 3/8	1 3/8	1524-23-13	376
	1 7/8	1524-23-17	426
	2 3/8	1524-23-23	476
	2 7/8	1524-23-27	526
	3 3/8	1524-23-33	576
	3 7/8	1524-23-37	626
	4 3/8	1524-23-47	726
	5 3/8	1524-23-57	826
2 7/8	1 3/8	1524-27-13	426
	1 7/8	1524-27-17	476
	2 3/8	1524-27-23	526
	2 7/8	1524-27-27	576
	3 3/8	1524-27-33	626
	3 7/8	1524-27-37	676
	4 3/8	1524-27-47	776
	5 3/8	1524-27-57	876

A	B	ITEM NUMBER	NET WT.
3 3/8	1 3/8	1524-33-13	476
	1 7/8	1524-33-17	526
	2 3/8	1524-33-23	576
	2 7/8	1524-33-27	626
	3 3/8	1524-33-33	676
	3 7/8	1524-33-37	726
	4 3/8	1524-33-47	826
	5 3/8	1524-33-57	926
3 7/8	1 3/8	1524-37-13	526
	1 7/8	1524-37-17	576
	2 3/8	1524-37-23	626
	2 7/8	1524-37-27	676
	3 3/8	1524-37-33	726
	3 7/8	1524-37-37	776
	4 3/8	1524-37-47	876
	5 3/8	1524-37-57	976
4 7/8	1 3/8	1524-47-13	626
	1 7/8	1524-47-17	676
	2 3/8	1524-47-23	726
	2 7/8	1524-47-27	776
	3 3/8	1524-47-33	826
	3 7/8	1524-47-37	876
	4 3/8	1524-47-47	976
	5 3/8	1524-47-57	1076
5 7/8	1 3/8	1524-57-13	726
	1 7/8	1524-57-17	776
	2 3/8	1524-57-23	826
	2 7/8	1524-57-27	876
	3 3/8	1524-57-33	926
	3 7/8	1524-57-37	976
	4 3/8	1524-57-47	1076
	5 3/8	1524-57-57	1176



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
 - No. 1, No. 3 or No. 7 Steel
 - L Dimension (Guide Pin Length)
 - Method of Shipment
- (No. 7 Steel available standard only for plates up to and including 2 7/8" thick)

Cavity Retainer Sets

14⁷/₈ × 29¹/₂ and 15⁷/₈ × 16"



A	B	ITEM NUMBER	NET WT.	A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1529-13-13	342	3 ³ / ₈	1 ³ / ₈	1529-33-13	591
	1 ⁷ / ₈	1529-13-17	405		1 ⁷ / ₈	1529-33-17	653
	2 ³ / ₈	1529-13-23	467		2 ³ / ₈	1529-33-23	715
	2 ⁷ / ₈	1529-13-27	529		2 ⁷ / ₈	1529-33-27	777
	3 ³ / ₈	1529-13-33	591		3 ³ / ₈	1529-33-33	840
	3 ⁷ / ₈	1529-13-37	653		3 ⁷ / ₈	1529-33-37	902
	4 ⁷ / ₈	1529-13-47	777		4 ⁷ / ₈	1529-33-47	1026
	5 ⁷ / ₈	1529-13-57	902		5 ⁷ / ₈	1529-33-57	1150
1 ⁷ / ₈	1 ³ / ₈	1529-17-13	405	3 ⁷ / ₈	1 ³ / ₈	1529-37-13	653
	1 ⁷ / ₈	1529-17-17	467		1 ⁷ / ₈	1529-37-17	715
	2 ³ / ₈	1529-17-23	529		2 ³ / ₈	1529-37-23	777
	2 ⁷ / ₈	1529-17-27	591		2 ⁷ / ₈	1529-37-27	840
	3 ³ / ₈	1529-17-33	653		3 ³ / ₈	1529-37-33	902
	3 ⁷ / ₈	1529-17-37	715		3 ⁷ / ₈	1529-37-37	964
	4 ⁷ / ₈	1529-17-47	840		4 ⁷ / ₈	1529-37-47	1088
	5 ⁷ / ₈	1529-17-57	964		5 ⁷ / ₈	1529-37-57	1213
2 ³ / ₈	1 ³ / ₈	1529-23-13	467	4 ⁷ / ₈	1 ³ / ₈	1529-47-13	777
	1 ⁷ / ₈	1529-23-17	529		1 ⁷ / ₈	1529-47-17	840
	2 ³ / ₈	1529-23-23	591		2 ³ / ₈	1529-47-23	902
	2 ⁷ / ₈	1529-23-27	653		2 ⁷ / ₈	1529-47-27	964
	3 ³ / ₈	1529-23-33	715		3 ³ / ₈	1529-47-33	1026
	3 ⁷ / ₈	1529-23-37	777		3 ⁷ / ₈	1529-47-37	1088
	4 ⁷ / ₈	1529-23-47	902		4 ⁷ / ₈	1529-47-47	1213
	5 ⁷ / ₈	1529-23-57	1026		5 ⁷ / ₈	1529-47-57	1337
2 ⁷ / ₈	1 ³ / ₈	1529-27-13	529	5 ⁷ / ₈	1 ³ / ₈	1529-57-13	902
	1 ⁷ / ₈	1529-27-17	591		1 ⁷ / ₈	1529-57-17	964
	2 ³ / ₈	1529-27-23	653		2 ³ / ₈	1529-57-23	1026
	2 ⁷ / ₈	1529-27-27	715		2 ⁷ / ₈	1529-57-27	1088
	3 ³ / ₈	1529-27-33	777		3 ³ / ₈	1529-57-33	1150
	3 ⁷ / ₈	1529-27-37	840		3 ⁷ / ₈	1529-57-37	1213
	4 ⁷ / ₈	1529-27-47	964		4 ⁷ / ₈	1529-57-47	1337
	5 ⁷ / ₈	1529-27-57	1088		5 ⁷ / ₈	1529-57-57	1461

A	B	ITEM NUMBER	NET WT.
7 ⁷ / ₈	7 ⁷ / ₈	1616-7-7	126
	1 ³ / ₈	1616-7-13	162
	1 ⁷ / ₈	1616-7-17	198
	2 ³ / ₈	1616-7-23	234
	2 ⁷ / ₈	1616-7-27	270
	3 ³ / ₈	1616-7-33	306
	3 ⁷ / ₈	1616-7-37	342
	4 ⁷ / ₈	1616-7-47	414
1 ³ / ₈	5 ⁷ / ₈	1616-7-57	486
	7 ⁷ / ₈	1616-13-7	162
	1 ³ / ₈	1616-13-13	198
	1 ⁷ / ₈	1616-13-17	234
	2 ³ / ₈	1616-13-23	270
	2 ⁷ / ₈	1616-13-27	306
	3 ³ / ₈	1616-13-33	342
	3 ⁷ / ₈	1616-13-37	378
1 ⁷ / ₈	4 ⁷ / ₈	1616-13-47	450
	5 ⁷ / ₈	1616-13-57	522
	7 ⁷ / ₈	1616-17-7	198
	1 ³ / ₈	1616-17-13	234
	1 ⁷ / ₈	1616-17-17	270
	2 ³ / ₈	1616-17-23	306
	2 ⁷ / ₈	1616-17-27	342
	3 ³ / ₈	1616-17-33	378
2 ³ / ₈	3 ⁷ / ₈	1616-17-37	414
	4 ⁷ / ₈	1616-17-47	486
	5 ⁷ / ₈	1616-17-57	558
	7 ⁷ / ₈	1616-23-7	234
	1 ³ / ₈	1616-23-13	270
	1 ⁷ / ₈	1616-23-17	306
	2 ³ / ₈	1616-23-23	342
	2 ⁷ / ₈	1616-23-27	378
	3 ³ / ₈	1616-23-33	414
	3 ⁷ / ₈	1616-23-37	450
	4 ⁷ / ₈	1616-23-47	522
	5 ⁷ / ₈	1616-23-57	594

A	B	ITEM NUMBER	NET WT.
2 ⁷ / ₈	7 ⁷ / ₈	1616-27-7	270
	1 ³ / ₈	1616-27-13	306
	1 ⁷ / ₈	1616-27-17	342
	2 ³ / ₈	1616-27-23	378
	2 ⁷ / ₈	1616-27-27	414
	3 ³ / ₈	1616-27-33	450
	3 ⁷ / ₈	1616-27-37	486
	4 ⁷ / ₈	1616-27-47	558
3 ³ / ₈	5 ⁷ / ₈	1616-27-57	630
	7 ⁷ / ₈	1616-33-7	306
	1 ³ / ₈	1616-33-13	342
	1 ⁷ / ₈	1616-33-17	378
	2 ³ / ₈	1616-33-23	414
	2 ⁷ / ₈	1616-33-27	450
	3 ³ / ₈	1616-33-33	486
	3 ⁷ / ₈	1616-33-37	522
3 ⁷ / ₈	4 ⁷ / ₈	1616-33-47	594
	5 ⁷ / ₈	1616-33-57	666
	7 ⁷ / ₈	1616-37-7	342
	1 ³ / ₈	1616-37-13	378
	1 ⁷ / ₈	1616-37-17	414
	2 ³ / ₈	1616-37-23	450
	2 ⁷ / ₈	1616-37-27	486
	3 ³ / ₈	1616-37-33	522
4 ⁷ / ₈	3 ⁷ / ₈	1616-37-37	558
	4 ⁷ / ₈	1616-37-47	630
	5 ⁷ / ₈	1616-37-57	702
	7 ⁷ / ₈	1616-47-7	414
	1 ³ / ₈	1616-47-13	450
	1 ⁷ / ₈	1616-47-17	486
	2 ³ / ₈	1616-47-23	522
	2 ⁷ / ₈	1616-47-27	558
5 ⁷ / ₈	3 ³ / ₈	1616-47-33	594
	3 ⁷ / ₈	1616-47-37	630
	4 ⁷ / ₈	1616-47-47	702
	5 ⁷ / ₈	1616-47-57	774
	7 ⁷ / ₈	1616-57-7	486
	1 ³ / ₈	1616-57-13	522
	1 ⁷ / ₈	1616-57-17	558
	2 ³ / ₈	1616-57-23	594
	2 ⁷ / ₈	1616-57-27	630
	3 ³ / ₈	1616-57-33	666
	3 ⁷ / ₈	1616-57-37	702
	4 ⁷ / ₈	1616-57-47	774
	5 ⁷ / ₈	1616-57-57	846



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2% thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

15⁷/₈ × 20" and 15⁷/₈ × 23¹/₂



A	B	ITEM NUMBER	NET WT.
7/8	7/8	1620-7-7	158
	1 1/8	1620-7-13	203
	1 1/8	1620-7-17	248
	2 3/8	1620-7-23	293
	2 3/8	1620-7-27	338
	3 3/8	1620-7-33	383
	3 3/8	1620-7-37	428
	4 7/8	1620-7-47	518
1 1/8	5 7/8	1620-7-57	608
	7/8	1620-13-7	203
	1 1/8	1620-13-13	248
	1 1/8	1620-13-17	293
	2 3/8	1620-13-23	338
	2 3/8	1620-13-27	383
	3 3/8	1620-13-33	428
	3 3/8	1620-13-37	473
1 7/8	4 7/8	1620-13-47	563
	5 7/8	1620-13-57	653
	7/8	1620-17-7	248
	1 1/8	1620-17-13	293
	1 1/8	1620-17-17	338
	2 3/8	1620-17-23	383
	2 3/8	1620-17-27	428
	3 3/8	1620-17-33	473
2 3/8	3 3/8	1620-17-37	518
	4 7/8	1620-17-47	608
	5 7/8	1620-17-57	698
	7/8	1620-23-7	293
	1 1/8	1620-23-13	338
	1 1/8	1620-23-17	383
	2 3/8	1620-23-23	428
	2 3/8	1620-23-27	473
2 7/8	3 3/8	1620-23-33	518
	3 3/8	1620-23-37	563
	4 7/8	1620-23-47	653
	5 7/8	1620-23-57	743
	7/8	1620-27-7	338
	1 1/8	1620-27-13	383
	1 1/8	1620-27-17	428
	2 3/8	1620-27-23	473
2 7/8	2 3/8	1620-27-27	518
	3 3/8	1620-27-33	563
	3 3/8	1620-27-37	608
	4 7/8	1620-27-47	698
	5 7/8	1620-27-57	787
	7/8	1620-27-7	338
	1 1/8	1620-27-13	383
	1 1/8	1620-27-17	428

A	B	ITEM NUMBER	NET WT.
3 3/8	7/8	1620-33-7	383
	1 1/8	1620-33-13	428
	1 1/8	1620-33-17	473
	2 3/8	1620-33-23	518
	2 3/8	1620-33-27	563
	3 3/8	1620-33-33	608
	3 3/8	1620-33-37	653
	4 7/8	1620-33-47	743
3 7/8	5 7/8	1620-33-57	832
	7/8	1620-37-7	428
	1 1/8	1620-37-13	473
	1 1/8	1620-37-17	518
	2 3/8	1620-37-23	563
	2 3/8	1620-37-27	608
	3 3/8	1620-37-33	653
	3 3/8	1620-37-37	698
4 7/8	4 7/8	1620-37-47	787
	5 7/8	1620-37-57	877
	7/8	1620-47-7	518
	1 1/8	1620-47-13	563
	1 1/8	1620-47-17	608
	2 3/8	1620-47-23	653
	2 3/8	1620-47-27	698
	3 3/8	1620-47-33	743
5 7/8	3 3/8	1620-47-37	787
	4 7/8	1620-47-47	877
	5 7/8	1620-47-57	967
	7/8	1620-57-7	608
	1 1/8	1620-57-13	653
	1 1/8	1620-57-17	698
	2 3/8	1620-57-23	743
	2 3/8	1620-57-27	787
5 7/8	3 3/8	1620-57-33	832
	3 3/8	1620-57-37	877
	4 7/8	1620-57-47	967
	5 7/8	1620-57-57	1057

A	B	ITEM NUMBER	NET WT.
1 3/8	1 3/8	1623-13-13	291
	1 7/8	1623-13-17	344
	2 3/8	1623-13-23	397
	2 7/8	1623-13-27	450
	3 3/8	1623-13-33	503
	3 7/8	1623-13-37	555
	4 7/8	1623-13-47	661
	5 7/8	1623-13-57	767
1 7/8	1 3/8	1623-17-13	344
	1 7/8	1623-17-17	397
	2 3/8	1623-17-23	450
	2 7/8	1623-17-27	502
	3 3/8	1623-17-33	555
	3 7/8	1623-17-37	608
	4 7/8	1623-17-47	714
	5 7/8	1623-17-57	820
2 3/8	1 3/8	1623-23-13	397
	1 7/8	1623-23-17	450
	2 3/8	1623-23-23	502
	2 7/8	1623-23-27	555
	3 3/8	1623-23-33	608
	3 7/8	1623-23-37	661
	4 7/8	1623-23-47	767
	5 7/8	1623-23-57	872
2 7/8	1 3/8	1623-27-13	450
	1 7/8	1623-27-17	502
	2 3/8	1623-27-23	555
	2 7/8	1623-27-27	608
	3 3/8	1623-27-33	661
	3 7/8	1623-27-37	714
	4 7/8	1623-27-47	820
	5 7/8	1623-27-57	925

A	B	ITEM NUMBER	NET WT.
3 3/8	1 3/8	1623-33-13	502
	1 7/8	1623-33-17	555
	2 3/8	1623-33-23	608
	2 7/8	1623-33-27	661
	3 3/8	1623-33-33	714
	3 7/8	1623-33-37	767
	4 7/8	1623-33-47	872
	5 7/8	1623-33-57	978
3 7/8	1 3/8	1623-37-13	555
	1 7/8	1623-37-17	608
	2 3/8	1623-37-23	661
	2 7/8	1623-37-27	714
	3 3/8	1623-37-33	767
	3 7/8	1623-37-37	820
	4 7/8	1623-37-47	925
	5 7/8	1623-37-57	1031
4 7/8	1 3/8	1623-47-13	661
	1 7/8	1623-47-17	714
	2 3/8	1623-47-23	767
	2 7/8	1623-47-27	820
	3 3/8	1623-47-33	872
	3 7/8	1623-47-37	925
	4 7/8	1623-47-47	1031
	5 7/8	1623-47-57	1137
5 7/8	1 3/8	1623-57-13	767
	1 7/8	1623-57-17	820
	2 3/8	1623-57-23	872
	2 7/8	1623-57-27	925
	3 3/8	1623-57-33	978
	3 7/8	1623-57-37	1031
	4 7/8	1623-57-47	1137
	5 7/8	1623-57-57	1242



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
 - No. 1, No. 3 or No. 7 Steel
 - L Dimension (Guide Pin Length)
 - Method of Shipment
- (No. 7 Steel available standard only for plates up to and including 2 7/8" thick)

Cavity Retainer Sets

15 $\frac{7}{8}$ × 26" and 15 $\frac{7}{8}$ × 29 $\frac{1}{2}$ "



A	B	ITEM NUMBER	NET WT.
1 $\frac{3}{8}$	1 $\frac{3}{8}$	1626-13-13	322
	1 $\frac{7}{8}$	1626-13-17	381
	2 $\frac{3}{8}$	1626-13-23	439
	2 $\frac{7}{8}$	1626-13-27	497
	3 $\frac{3}{8}$	1626-13-33	556
	3 $\frac{7}{8}$	1626-13-37	614
	4 $\frac{7}{8}$	1626-13-47	731
1 $\frac{7}{8}$	5 $\frac{7}{8}$	1626-13-57	848
	1 $\frac{3}{8}$	1626-17-13	381
	1 $\frac{7}{8}$	1626-17-17	439
	2 $\frac{3}{8}$	1626-17-23	497
	2 $\frac{7}{8}$	1626-17-27	556
	3 $\frac{3}{8}$	1626-17-33	614
	3 $\frac{7}{8}$	1626-17-37	673
2 $\frac{3}{8}$	4 $\frac{7}{8}$	1626-17-47	790
	5 $\frac{7}{8}$	1626-17-57	907
	1 $\frac{3}{8}$	1626-23-13	439
	1 $\frac{7}{8}$	1626-23-17	497
	2 $\frac{3}{8}$	1626-23-23	556
	2 $\frac{7}{8}$	1626-23-27	614
	3 $\frac{3}{8}$	1626-23-33	673
2 $\frac{7}{8}$	3 $\frac{7}{8}$	1626-23-37	731
	4 $\frac{7}{8}$	1626-23-47	848
	5 $\frac{7}{8}$	1626-23-57	965
	1 $\frac{3}{8}$	1626-27-13	497
	1 $\frac{7}{8}$	1626-27-17	556
	2 $\frac{3}{8}$	1626-27-23	614
	2 $\frac{7}{8}$	1626-27-27	673
2 $\frac{7}{8}$	3 $\frac{3}{8}$	1626-27-33	731
	3 $\frac{7}{8}$	1626-27-37	790
	4 $\frac{7}{8}$	1626-27-47	907
	5 $\frac{7}{8}$	1626-27-57	1024

A	B	ITEM NUMBER	NET WT.
3 $\frac{3}{8}$	1 $\frac{3}{8}$	1626-33-13	556
	1 $\frac{7}{8}$	1626-33-17	614
	2 $\frac{3}{8}$	1626-33-23	673
	2 $\frac{7}{8}$	1626-33-27	731
	3 $\frac{3}{8}$	1626-33-33	790
	3 $\frac{7}{8}$	1626-33-37	848
	4 $\frac{7}{8}$	1626-33-47	965
3 $\frac{7}{8}$	5 $\frac{7}{8}$	1626-33-57	1082
	1 $\frac{3}{8}$	1626-37-13	614
	1 $\frac{7}{8}$	1626-37-17	673
	2 $\frac{3}{8}$	1626-37-23	731
	2 $\frac{7}{8}$	1626-37-27	790
	3 $\frac{3}{8}$	1626-37-33	848
	3 $\frac{7}{8}$	1626-37-37	907
4 $\frac{7}{8}$	4 $\frac{7}{8}$	1626-37-47	1024
	5 $\frac{7}{8}$	1626-37-57	1141
	1 $\frac{3}{8}$	1626-47-13	731
	1 $\frac{7}{8}$	1626-47-17	790
	2 $\frac{3}{8}$	1626-47-23	848
	2 $\frac{7}{8}$	1626-47-27	907
	3 $\frac{3}{8}$	1626-47-33	965
5 $\frac{7}{8}$	3 $\frac{7}{8}$	1626-47-37	1024
	4 $\frac{7}{8}$	1626-47-47	1141
	5 $\frac{7}{8}$	1626-47-57	1258
	1 $\frac{3}{8}$	1626-57-13	848
	1 $\frac{7}{8}$	1626-57-17	907
	2 $\frac{3}{8}$	1626-57-23	965
	2 $\frac{7}{8}$	1626-57-27	1024
5 $\frac{7}{8}$	3 $\frac{3}{8}$	1626-57-33	1082
	3 $\frac{7}{8}$	1626-57-37	1141
	4 $\frac{7}{8}$	1626-57-47	1258
5 $\frac{7}{8}$	5 $\frac{7}{8}$	1626-57-57	1375

A	B	ITEM NUMBER	NET WT.
1 $\frac{3}{8}$	1 $\frac{3}{8}$	1629-13-13	365
	1 $\frac{7}{8}$	1629-13-17	432
	2 $\frac{3}{8}$	1629-13-23	498
	2 $\frac{7}{8}$	1629-13-27	564
	3 $\frac{3}{8}$	1629-13-33	631
	3 $\frac{7}{8}$	1629-13-37	697
	4 $\frac{7}{8}$	1629-13-47	830
1 $\frac{7}{8}$	5 $\frac{7}{8}$	1629-13-57	962
	1 $\frac{3}{8}$	1629-17-13	432
	1 $\frac{7}{8}$	1629-17-17	498
	2 $\frac{3}{8}$	1629-17-23	564
	2 $\frac{7}{8}$	1629-17-27	631
	3 $\frac{3}{8}$	1629-17-33	697
	3 $\frac{7}{8}$	1629-17-37	763
2 $\frac{3}{8}$	4 $\frac{7}{8}$	1629-17-47	896
	5 $\frac{7}{8}$	1629-17-57	1029
	1 $\frac{3}{8}$	1629-23-13	498
	1 $\frac{7}{8}$	1629-23-17	564
	2 $\frac{3}{8}$	1629-23-23	631
	2 $\frac{7}{8}$	1629-23-27	697
	3 $\frac{3}{8}$	1629-23-33	763
2 $\frac{7}{8}$	3 $\frac{7}{8}$	1629-23-37	830
	4 $\frac{7}{8}$	1629-23-47	962
	5 $\frac{7}{8}$	1629-23-57	1095
	1 $\frac{3}{8}$	1629-27-13	564
	1 $\frac{7}{8}$	1629-27-17	631
	2 $\frac{3}{8}$	1629-27-23	697
	2 $\frac{7}{8}$	1629-27-27	763
2 $\frac{7}{8}$	3 $\frac{3}{8}$	1629-27-33	830
	3 $\frac{7}{8}$	1629-27-37	896
	4 $\frac{7}{8}$	1629-27-47	1029
	5 $\frac{7}{8}$	1629-27-57	1161

A	B	ITEM NUMBER	NET WT.
3 $\frac{3}{8}$	1 $\frac{3}{8}$	1629-33-13	631
	1 $\frac{7}{8}$	1629-33-17	697
	2 $\frac{3}{8}$	1629-33-23	763
	2 $\frac{7}{8}$	1629-33-27	830
	3 $\frac{3}{8}$	1629-33-33	896
	3 $\frac{7}{8}$	1629-33-37	962
	4 $\frac{7}{8}$	1629-33-47	1095
3 $\frac{7}{8}$	5 $\frac{7}{8}$	1629-33-57	1228
	1 $\frac{3}{8}$	1629-37-13	697
	1 $\frac{7}{8}$	1629-37-17	763
	2 $\frac{3}{8}$	1629-37-23	830
	2 $\frac{7}{8}$	1629-37-27	896
	3 $\frac{3}{8}$	1629-37-33	962
	3 $\frac{7}{8}$	1629-37-37	1029
4 $\frac{7}{8}$	4 $\frac{7}{8}$	1629-37-47	1161
	5 $\frac{7}{8}$	1629-37-57	1294
	1 $\frac{3}{8}$	1629-47-13	830
	1 $\frac{7}{8}$	1629-47-17	896
	2 $\frac{3}{8}$	1629-47-23	962
	2 $\frac{7}{8}$	1629-47-27	1029
	3 $\frac{3}{8}$	1629-47-33	1095
5 $\frac{7}{8}$	3 $\frac{7}{8}$	1629-47-37	1161
	4 $\frac{7}{8}$	1629-47-47	1294
	5 $\frac{7}{8}$	1629-47-57	1427
	1 $\frac{3}{8}$	1629-57-13	962
	1 $\frac{7}{8}$	1629-57-17	1029
	2 $\frac{3}{8}$	1629-57-23	1095
	2 $\frac{7}{8}$	1629-57-27	1161
5 $\frac{7}{8}$	3 $\frac{3}{8}$	1629-57-33	1228
	3 $\frac{7}{8}$	1629-57-37	1294
	4 $\frac{7}{8}$	1629-57-47	1427
	5 $\frac{7}{8}$	1629-57-57	1559



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
 - No. 1, No. 3 or No. 7 Steel
 - L Dimension (Guide Pin Length)
 - Method of Shipment
- (No. 7 Steel available standard only for plates up to and including 2 $\frac{7}{8}$ thick)

Cavity Retainer Sets

15⁷/₈ × 35¹/₂ and 16¹/₂ × 23³/₄"



A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1635-13-13	440
	1 ⁷ / ₈	1635-13-17	519
	2 ³ / ₈	1635-13-23	599
	2 ⁷ / ₈	1635-13-27	679
	3 ³ / ₈	1635-13-33	759
	3 ⁷ / ₈	1635-13-37	839
	4 ³ / ₈	1635-13-47	998
	5 ³ / ₈	1635-13-57	1158
1 ⁷ / ₈	1 ³ / ₈	1635-17-13	519
	1 ⁷ / ₈	1635-17-17	599
	2 ³ / ₈	1635-17-23	679
	2 ⁷ / ₈	1635-17-27	759
	3 ³ / ₈	1635-17-33	839
	3 ⁷ / ₈	1635-17-37	919
	4 ³ / ₈	1635-17-47	1078
	5 ³ / ₈	1635-17-57	1238
2 ³ / ₈	1 ³ / ₈	1635-23-13	599
	1 ⁷ / ₈	1635-23-17	679
	2 ³ / ₈	1635-23-23	759
	2 ⁷ / ₈	1635-23-27	839
	3 ³ / ₈	1635-23-33	919
	3 ⁷ / ₈	1635-23-37	998
	4 ³ / ₈	1635-23-47	1158
	5 ³ / ₈	1635-23-57	1318
2 ⁷ / ₈	1 ³ / ₈	1635-27-13	679
	1 ⁷ / ₈	1635-27-17	759
	2 ³ / ₈	1635-27-23	839
	2 ⁷ / ₈	1635-27-27	919
	3 ³ / ₈	1635-27-33	998
	3 ⁷ / ₈	1635-27-37	1078
	4 ³ / ₈	1635-27-47	1238
	5 ³ / ₈	1635-27-57	1398

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1635-33-13	759
	1 ⁷ / ₈	1635-33-17	839
	2 ³ / ₈	1635-33-23	919
	2 ⁷ / ₈	1635-33-27	998
	3 ³ / ₈	1635-33-33	1078
	3 ⁷ / ₈	1635-33-37	1158
	4 ³ / ₈	1635-33-47	1318
	5 ³ / ₈	1635-33-57	1477
3 ⁷ / ₈	1 ³ / ₈	1635-37-13	839
	1 ⁷ / ₈	1635-37-17	919
	2 ³ / ₈	1635-37-23	998
	2 ⁷ / ₈	1635-37-27	1078
	3 ³ / ₈	1635-37-33	1158
	3 ⁷ / ₈	1635-37-37	1238
	4 ³ / ₈	1635-37-47	1398
	5 ³ / ₈	1635-37-57	1557
4 ⁷ / ₈	1 ³ / ₈	1635-47-13	998
	1 ⁷ / ₈	1635-47-17	1078
	2 ³ / ₈	1635-47-23	1158
	2 ⁷ / ₈	1635-47-27	1238
	3 ³ / ₈	1635-47-33	1318
	3 ⁷ / ₈	1635-47-37	1398
	4 ³ / ₈	1635-47-47	1557
	5 ³ / ₈	1635-47-57	1717
5 ⁷ / ₈	1 ³ / ₈	1635-57-13	1158
	1 ⁷ / ₈	1635-57-17	1238
	2 ³ / ₈	1635-57-23	1318
	2 ⁷ / ₈	1635-57-27	1398
	3 ³ / ₈	1635-57-33	1477
	3 ⁷ / ₈	1635-57-37	1557
	4 ³ / ₈	1635-57-47	1717
	5 ³ / ₈	1635-57-57	1877

A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1724-13-13	306
	1 ⁷ / ₈	1724-13-17	361
	2 ³ / ₈	1724-13-23	417
	2 ⁷ / ₈	1724-13-27	472
	3 ³ / ₈	1724-13-33	528
	3 ⁷ / ₈	1724-13-37	583
	4 ³ / ₈	1724-13-47	694
	5 ³ / ₈	1724-13-57	805
1 ⁷ / ₈	1 ³ / ₈	1724-17-13	361
	1 ⁷ / ₈	1724-17-17	417
	2 ³ / ₈	1724-17-23	472
	2 ⁷ / ₈	1724-17-27	528
	3 ³ / ₈	1724-17-33	583
	3 ⁷ / ₈	1724-17-37	639
	4 ³ / ₈	1724-17-47	750
	5 ³ / ₈	1724-17-57	861
2 ³ / ₈	1 ³ / ₈	1724-23-13	417
	1 ⁷ / ₈	1724-23-17	472
	2 ³ / ₈	1724-23-23	528
	2 ⁷ / ₈	1724-23-27	583
	3 ³ / ₈	1724-23-33	639
	3 ⁷ / ₈	1724-23-37	694
	4 ³ / ₈	1724-23-47	805
	5 ³ / ₈	1724-23-57	916
2 ⁷ / ₈	1 ³ / ₈	1724-27-13	472
	1 ⁷ / ₈	1724-27-17	528
	2 ³ / ₈	1724-27-23	583
	2 ⁷ / ₈	1724-27-27	639
	3 ³ / ₈	1724-27-33	694
	3 ⁷ / ₈	1724-27-37	750
	4 ³ / ₈	1724-27-47	861
	5 ³ / ₈	1724-27-57	972

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1724-33-13	528
	1 ⁷ / ₈	1724-33-17	583
	2 ³ / ₈	1724-33-23	639
	2 ⁷ / ₈	1724-33-27	694
	3 ³ / ₈	1724-33-33	750
	3 ⁷ / ₈	1724-33-37	805
	4 ³ / ₈	1724-33-47	916
	5 ³ / ₈	1724-33-57	1027
3 ⁷ / ₈	1 ³ / ₈	1724-37-13	583
	1 ⁷ / ₈	1724-37-17	639
	2 ³ / ₈	1724-37-23	694
	2 ⁷ / ₈	1724-37-27	750
	3 ³ / ₈	1724-37-33	805
	3 ⁷ / ₈	1724-37-37	861
	4 ³ / ₈	1724-37-47	972
	5 ³ / ₈	1724-37-57	1083
4 ⁷ / ₈	1 ³ / ₈	1724-47-13	694
	1 ⁷ / ₈	1724-47-17	750
	2 ³ / ₈	1724-47-23	805
	2 ⁷ / ₈	1724-47-27	861
	3 ³ / ₈	1724-47-33	916
	3 ⁷ / ₈	1724-47-37	972
	4 ³ / ₈	1724-47-47	1083
	5 ³ / ₈	1724-47-57	1194
5 ⁷ / ₈	1 ³ / ₈	1724-57-13	805
	1 ⁷ / ₈	1724-57-17	861
	2 ³ / ₈	1724-57-23	916
	2 ⁷ / ₈	1724-57-27	972
	3 ³ / ₈	1724-57-33	1027
	3 ⁷ / ₈	1724-57-37	1083
	4 ³ / ₈	1724-57-47	1194
	5 ³ / ₈	1724-57-57	1305



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
 - No. 1, No. 3 or No. 7 Steel
 - L Dimension (Guide Pin Length)
 - Method of Shipment
- (No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)

Cavity Retainer Sets

16½ × 29½ and 17⅞ × 18"



A	B	ITEM NUMBER	NET WT.
1⅜	1⅞	1729-13-13	380
	1⅞	1729-13-17	449
	2⅞	1729-13-23	518
	2⅞	1729-13-27	587
	3⅞	1729-13-33	656
	3⅞	1729-13-37	724
	4⅞	1729-13-47	862
	5⅞	1729-13-57	1000
1⅞	1⅞	1729-17-13	449
	1⅞	1729-17-17	518
	2⅞	1729-17-23	587
	2⅞	1729-17-27	656
	3⅞	1729-17-33	724
	3⅞	1729-17-37	793
	4⅞	1729-17-47	931
	5⅞	1729-17-57	1069
2⅜	1⅞	1729-23-13	518
	1⅞	1729-23-17	587
	2⅞	1729-23-23	656
	2⅞	1729-23-27	724
	3⅞	1729-23-33	793
	3⅞	1729-23-37	862
	4⅞	1729-23-47	1000
	5⅞	1729-23-57	1138
2⅞	1⅞	1729-27-13	587
	1⅞	1729-27-17	656
	2⅞	1729-27-23	724
	2⅞	1729-27-27	793
	3⅞	1729-27-33	862
	3⅞	1729-27-37	931
	4⅞	1729-27-47	1069
	5⅞	1729-27-57	1207

A	B	ITEM NUMBER	NET WT.
3⅜	1⅞	1729-33-13	656
	1⅞	1729-33-17	724
	2⅞	1729-33-23	793
	2⅞	1729-33-27	862
	3⅞	1729-33-33	931
	3⅞	1729-33-37	1000
	4⅞	1729-33-47	1138
	5⅞	1729-33-57	1276
3⅞	1⅞	1729-37-13	724
	1⅞	1729-37-17	793
	2⅞	1729-37-23	862
	2⅞	1729-37-27	931
	3⅞	1729-37-33	1000
	3⅞	1729-37-37	1069
	4⅞	1729-37-47	1207
	5⅞	1729-37-57	1345
4⅞	1⅞	1729-47-13	862
	1⅞	1729-47-17	931
	2⅞	1729-47-23	1000
	2⅞	1729-47-27	1069
	3⅞	1729-47-33	1138
	3⅞	1729-47-37	1207
	4⅞	1729-47-47	1345
	5⅞	1729-47-57	1483
5⅞	1⅞	1729-57-13	1000
	1⅞	1729-57-17	1069
	2⅞	1729-57-23	1138
	2⅞	1729-57-27	1207
	3⅞	1729-57-33	1276
	3⅞	1729-57-37	1345
	4⅞	1729-57-47	1483
	5⅞	1729-57-57	1621

A	B	ITEM NUMBER	NET WT.
1⅜	1⅞	1818-13-13	251
	1⅞	1818-13-17	297
	2⅞	1818-13-23	342
	2⅞	1818-13-27	388
	3⅞	1818-13-33	434
	3⅞	1818-13-37	479
	4⅞	1818-13-47	570
	5⅞	1818-13-57	661
1⅞	1⅞	1818-17-13	297
	1⅞	1818-17-17	342
	2⅞	1818-17-23	388
	2⅞	1818-17-27	434
	3⅞	1818-17-33	479
	3⅞	1818-17-37	525
	4⅞	1818-17-47	616
	5⅞	1818-17-57	707
2⅜	1⅞	1818-23-13	342
	1⅞	1818-23-17	388
	2⅞	1818-23-23	434
	2⅞	1818-23-27	479
	3⅞	1818-23-33	525
	3⅞	1818-23-37	570
	4⅞	1818-23-47	661
	5⅞	1818-23-57	753
2⅞	1⅞	1818-27-13	388
	1⅞	1818-27-17	434
	2⅞	1818-27-23	479
	2⅞	1818-27-27	525
	3⅞	1818-27-33	570
	3⅞	1818-27-37	616
	4⅞	1818-27-47	707
	5⅞	1818-27-57	798

A	B	ITEM NUMBER	NET WT.
3⅜	1⅞	1818-33-13	434
	1⅞	1818-33-17	479
	2⅞	1818-33-23	525
	2⅞	1818-33-27	570
	3⅞	1818-33-33	616
	3⅞	1818-33-37	661
	4⅞	1818-33-47	753
	5⅞	1818-33-57	844
3⅞	1⅞	1818-37-13	479
	1⅞	1818-37-17	525
	2⅞	1818-37-23	570
	2⅞	1818-37-27	616
	3⅞	1818-37-33	661
	3⅞	1818-37-37	707
	4⅞	1818-37-47	798
	5⅞	1818-37-57	889
4⅞	1⅞	1818-47-13	570
	1⅞	1818-47-17	616
	2⅞	1818-47-23	661
	2⅞	1818-47-27	707
	3⅞	1818-47-33	753
	3⅞	1818-47-37	798
	4⅞	1818-47-47	889
	5⅞	1818-47-57	980
5⅞	1⅞	1818-57-13	661
	1⅞	1818-57-17	707
	2⅞	1818-57-23	753
	2⅞	1818-57-27	798
	3⅞	1818-57-33	844
	3⅞	1818-57-37	889
	4⅞	1818-57-47	980
	5⅞	1818-57-57	1072



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2⅞ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

17⁷/₈ × 20" and 17⁷/₈ × 23¹/₂



A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ¹ / ₈	1820-13-13	279
	1 ¹ / ₈	1820-13-17	330
	2 ³ / ₈	1820-13-23	380
	2 ⁷ / ₈	1820-13-27	431
	3 ³ / ₈	1820-13-33	482
	3 ⁷ / ₈	1820-13-37	532
	4 ⁷ / ₈	1820-13-47	633
	5 ⁷ / ₈	1820-13-57	735
1 ⁷ / ₈	1 ¹ / ₈	1820-17-13	330
	1 ¹ / ₈	1820-17-17	380
	2 ³ / ₈	1820-17-23	431
	2 ⁷ / ₈	1820-17-27	482
	3 ³ / ₈	1820-17-33	532
	3 ⁷ / ₈	1820-17-37	583
	4 ⁷ / ₈	1820-17-47	684
	5 ⁷ / ₈	1820-17-57	785
2 ³ / ₈	1 ¹ / ₈	1820-23-13	380
	1 ¹ / ₈	1820-23-17	431
	2 ³ / ₈	1820-23-23	482
	2 ⁷ / ₈	1820-23-27	532
	3 ³ / ₈	1820-23-33	583
	3 ⁷ / ₈	1820-23-37	633
	4 ⁷ / ₈	1820-23-47	735
	5 ⁷ / ₈	1820-23-57	836
2 ⁷ / ₈	1 ¹ / ₈	1820-27-13	431
	1 ¹ / ₈	1820-27-17	482
	2 ³ / ₈	1820-27-23	532
	2 ⁷ / ₈	1820-27-27	583
	3 ³ / ₈	1820-27-33	633
	3 ⁷ / ₈	1820-27-37	684
	4 ⁷ / ₈	1820-27-47	785
	5 ⁷ / ₈	1820-27-57	887

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ¹ / ₈	1820-33-13	482
	1 ¹ / ₈	1820-33-17	532
	2 ³ / ₈	1820-33-23	583
	2 ⁷ / ₈	1820-33-27	633
	3 ³ / ₈	1820-33-33	684
	3 ⁷ / ₈	1820-33-37	735
	4 ⁷ / ₈	1820-33-47	836
	5 ⁷ / ₈	1820-33-57	937
3 ⁷ / ₈	1 ¹ / ₈	1820-37-13	532
	1 ¹ / ₈	1820-37-17	583
	2 ³ / ₈	1820-37-23	633
	2 ⁷ / ₈	1820-37-27	684
	3 ³ / ₈	1820-37-33	735
	3 ⁷ / ₈	1820-37-37	785
	4 ⁷ / ₈	1820-37-47	887
	5 ⁷ / ₈	1820-37-57	988
4 ⁷ / ₈	1 ¹ / ₈	1820-47-13	633
	1 ¹ / ₈	1820-47-17	684
	2 ³ / ₈	1820-47-23	735
	2 ⁷ / ₈	1820-47-27	785
	3 ³ / ₈	1820-47-33	836
	3 ⁷ / ₈	1820-47-37	887
	4 ⁷ / ₈	1820-47-47	988
	5 ⁷ / ₈	1820-47-57	1089
5 ⁷ / ₈	1 ¹ / ₈	1820-57-13	735
	1 ¹ / ₈	1820-57-17	785
	2 ³ / ₈	1820-57-23	836
	2 ⁷ / ₈	1820-57-27	887
	3 ³ / ₈	1820-57-33	937
	3 ⁷ / ₈	1820-57-37	988
	4 ⁷ / ₈	1820-57-47	1089
	5 ⁷ / ₈	1820-57-57	1191

A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ¹ / ₈	1823-13-13	328
	1 ¹ / ₈	1823-13-17	387
	2 ³ / ₈	1823-13-23	447
	2 ⁷ / ₈	1823-13-27	506
	3 ³ / ₈	1823-13-33	566
	3 ⁷ / ₈	1823-13-37	625
	4 ⁷ / ₈	1823-13-47	744
	5 ⁷ / ₈	1823-13-57	863
1 ⁷ / ₈	1 ¹ / ₈	1823-17-13	387
	1 ¹ / ₈	1823-17-17	447
	2 ³ / ₈	1823-17-23	506
	2 ⁷ / ₈	1823-17-27	566
	3 ³ / ₈	1823-17-33	625
	3 ⁷ / ₈	1823-17-37	685
	4 ⁷ / ₈	1823-17-47	804
	5 ⁷ / ₈	1823-17-57	923
2 ³ / ₈	1 ¹ / ₈	1823-23-13	447
	1 ¹ / ₈	1823-23-17	506
	2 ³ / ₈	1823-23-23	566
	2 ⁷ / ₈	1823-23-27	625
	3 ³ / ₈	1823-23-33	685
	3 ⁷ / ₈	1823-23-37	744
	4 ⁷ / ₈	1823-23-47	863
	5 ⁷ / ₈	1823-23-57	982
2 ⁷ / ₈	1 ¹ / ₈	1823-27-13	506
	1 ¹ / ₈	1823-27-17	566
	2 ³ / ₈	1823-27-23	625
	2 ⁷ / ₈	1823-27-27	685
	3 ³ / ₈	1823-27-33	744
	3 ⁷ / ₈	1823-27-37	804
	4 ⁷ / ₈	1823-27-47	923
	5 ⁷ / ₈	1823-27-57	1042

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ¹ / ₈	1823-33-13	566
	1 ¹ / ₈	1823-33-17	625
	2 ³ / ₈	1823-33-23	685
	2 ⁷ / ₈	1823-33-27	744
	3 ³ / ₈	1823-33-33	804
	3 ⁷ / ₈	1823-33-37	863
	4 ⁷ / ₈	1823-33-47	982
	5 ⁷ / ₈	1823-33-57	1101
3 ⁷ / ₈	1 ¹ / ₈	1823-37-13	625
	1 ¹ / ₈	1823-37-17	685
	2 ³ / ₈	1823-37-23	744
	2 ⁷ / ₈	1823-37-27	804
	3 ³ / ₈	1823-37-33	863
	3 ⁷ / ₈	1823-37-37	923
	4 ⁷ / ₈	1823-37-47	1042
	5 ⁷ / ₈	1823-37-57	1161
4 ⁷ / ₈	1 ¹ / ₈	1823-47-13	744
	1 ¹ / ₈	1823-47-17	804
	2 ³ / ₈	1823-47-23	863
	2 ⁷ / ₈	1823-47-27	923
	3 ³ / ₈	1823-47-33	982
	3 ⁷ / ₈	1823-47-37	1042
	4 ⁷ / ₈	1823-47-47	1161
	5 ⁷ / ₈	1823-47-57	1280
5 ⁷ / ₈	1 ¹ / ₈	1823-57-13	863
	1 ¹ / ₈	1823-57-17	923
	2 ³ / ₈	1823-57-23	982
	2 ⁷ / ₈	1823-57-27	1042
	3 ³ / ₈	1823-57-33	1101
	3 ⁷ / ₈	1823-57-37	1161
	4 ⁷ / ₈	1823-57-47	1280
	5 ⁷ / ₈	1823-57-57	1399



Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
 - No. 1, No. 3 or No. 7 Steel
 - L Dimension (Guide Pin Length)
 - Method of Shipment
- (No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)

Cavity Retainer Sets

17⁷/₈ × 26" and 17⁷/₈ × 29¹/₂"



A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1826-13-13	363
	1 ⁷ / ₈	1826-13-17	428
	2 ³ / ₈	1826-13-23	494
	2 ⁷ / ₈	1826-13-27	560
	3 ³ / ₈	1826-13-33	626
	3 ⁷ / ₈	1826-13-37	692
	4 ³ / ₈	1826-13-47	823
	5 ³ / ₈	1826-13-57	955
1 ⁷ / ₈	1 ³ / ₈	1826-17-13	428
	1 ⁷ / ₈	1826-17-17	494
	2 ³ / ₈	1826-17-23	560
	2 ⁷ / ₈	1826-17-27	626
	3 ³ / ₈	1826-17-33	692
	3 ⁷ / ₈	1826-17-37	758
	4 ³ / ₈	1826-17-47	889
	5 ³ / ₈	1826-17-57	1021
2 ³ / ₈	1 ³ / ₈	1826-23-13	494
	1 ⁷ / ₈	1826-23-17	560
	2 ³ / ₈	1826-23-23	626
	2 ⁷ / ₈	1826-23-27	692
	3 ³ / ₈	1826-23-33	758
	3 ⁷ / ₈	1826-23-37	823
	4 ³ / ₈	1826-23-47	955
	5 ³ / ₈	1826-23-57	1087
2 ⁷ / ₈	1 ³ / ₈	1826-27-13	560
	1 ⁷ / ₈	1826-27-17	626
	2 ³ / ₈	1826-27-23	692
	2 ⁷ / ₈	1826-27-27	758
	3 ³ / ₈	1826-27-33	823
	3 ⁷ / ₈	1826-27-37	889
	4 ³ / ₈	1826-27-47	1021
	5 ³ / ₈	1826-27-57	1153

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1826-33-13	626
	1 ⁷ / ₈	1826-33-17	692
	2 ³ / ₈	1826-33-23	758
	2 ⁷ / ₈	1826-33-27	823
	3 ³ / ₈	1826-33-33	889
	3 ⁷ / ₈	1826-33-37	955
	4 ³ / ₈	1826-33-47	1087
	5 ³ / ₈	1826-33-57	1218
3 ⁷ / ₈	1 ³ / ₈	1826-37-13	692
	1 ⁷ / ₈	1826-37-17	758
	2 ³ / ₈	1826-37-23	823
	2 ⁷ / ₈	1826-37-27	889
	3 ³ / ₈	1826-37-33	955
	3 ⁷ / ₈	1826-37-37	1021
	4 ³ / ₈	1826-37-47	1153
	5 ³ / ₈	1826-37-57	1284
4 ⁷ / ₈	1 ³ / ₈	1826-47-13	823
	1 ⁷ / ₈	1826-47-17	889
	2 ³ / ₈	1826-47-23	955
	2 ⁷ / ₈	1826-47-27	1021
	3 ³ / ₈	1826-47-33	1087
	3 ⁷ / ₈	1826-47-37	1153
	4 ³ / ₈	1826-47-47	1284
	5 ³ / ₈	1826-47-57	1416
5 ⁷ / ₈	1 ³ / ₈	1826-57-13	955
	1 ⁷ / ₈	1826-57-17	1021
	2 ³ / ₈	1826-57-23	1087
	2 ⁷ / ₈	1826-57-27	1153
	3 ³ / ₈	1826-57-33	1218
	3 ⁷ / ₈	1826-57-37	1284
	4 ³ / ₈	1826-57-47	1416
	5 ³ / ₈	1826-57-57	1548

A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1829-13-13	411
	1 ⁷ / ₈	1829-13-17	486
	2 ³ / ₈	1829-13-23	561
	2 ⁷ / ₈	1829-13-27	635
	3 ³ / ₈	1829-13-33	710
	3 ⁷ / ₈	1829-13-37	785
	4 ³ / ₈	1829-13-47	934
	5 ³ / ₈	1829-13-57	1084
1 ⁷ / ₈	1 ³ / ₈	1829-17-13	486
	1 ⁷ / ₈	1829-17-17	561
	2 ³ / ₈	1829-17-23	635
	2 ⁷ / ₈	1829-17-27	710
	3 ³ / ₈	1829-17-33	785
	3 ⁷ / ₈	1829-17-37	859
	4 ³ / ₈	1829-17-47	1009
	5 ³ / ₈	1829-17-57	1158
2 ³ / ₈	1 ³ / ₈	1829-23-13	561
	1 ⁷ / ₈	1829-23-17	635
	2 ³ / ₈	1829-23-23	710
	2 ⁷ / ₈	1829-23-27	785
	3 ³ / ₈	1829-23-33	859
	3 ⁷ / ₈	1829-23-37	934
	4 ³ / ₈	1829-23-47	1084
	5 ³ / ₈	1829-23-57	1233
2 ⁷ / ₈	1 ³ / ₈	1829-27-13	635
	1 ⁷ / ₈	1829-27-17	710
	2 ³ / ₈	1829-27-23	785
	2 ⁷ / ₈	1829-27-27	859
	3 ³ / ₈	1829-27-33	934
	3 ⁷ / ₈	1829-27-37	1009
	4 ³ / ₈	1829-27-47	1158
	5 ³ / ₈	1829-27-57	1308

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1829-33-13	710
	1 ⁷ / ₈	1829-33-17	785
	2 ³ / ₈	1829-33-23	859
	2 ⁷ / ₈	1829-33-27	934
	3 ³ / ₈	1829-33-33	1009
	3 ⁷ / ₈	1829-33-37	1084
	4 ³ / ₈	1829-33-47	1233
	5 ³ / ₈	1829-33-57	1382
3 ⁷ / ₈	1 ³ / ₈	1829-37-13	785
	1 ⁷ / ₈	1829-37-17	859
	2 ³ / ₈	1829-37-23	934
	2 ⁷ / ₈	1829-37-27	1009
	3 ³ / ₈	1829-37-33	1084
	3 ⁷ / ₈	1829-37-37	1158
	4 ³ / ₈	1829-37-47	1308
	5 ³ / ₈	1829-37-57	1457
4 ⁷ / ₈	1 ³ / ₈	1829-47-13	934
	1 ⁷ / ₈	1829-47-17	1009
	2 ³ / ₈	1829-47-23	1084
	2 ⁷ / ₈	1829-47-27	1158
	3 ³ / ₈	1829-47-33	1233
	3 ⁷ / ₈	1829-47-37	1308
	4 ³ / ₈	1829-47-47	1457
	5 ³ / ₈	1829-47-57	1606
5 ⁷ / ₈	1 ³ / ₈	1829-57-13	1084
	1 ⁷ / ₈	1829-57-17	1158
	2 ³ / ₈	1829-57-23	1233
	2 ⁷ / ₈	1829-57-27	1308
	3 ³ / ₈	1829-57-33	1382
	3 ⁷ / ₈	1829-57-37	1457
	4 ³ / ₈	1829-57-47	1606
	5 ³ / ₈	1829-57-57	1756



Thickness of each plate is finish ground $\pm .001"$. Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Cavity Retainer Sets

17⁷/₈ × 35¹/₂ and 19¹/₂ × 23³/₄"



A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1835-13-13	495
	1 ⁷ / ₈	1835-13-17	585
	2 ³ / ₈	1835-13-23	675
	2 ⁷ / ₈	1835-13-27	765
	3 ³ / ₈	1835-13-33	854
	3 ⁷ / ₈	1835-13-37	944
	4 ⁷ / ₈	1835-13-47	1124
	5 ⁷ / ₈	1835-13-57	1304
1 ⁷ / ₈	1 ³ / ₈	1835-17-13	585
	1 ⁷ / ₈	1835-17-17	675
	2 ³ / ₈	1835-17-23	765
	2 ⁷ / ₈	1835-17-27	854
	3 ³ / ₈	1835-17-33	944
	3 ⁷ / ₈	1835-17-37	1034
	4 ⁷ / ₈	1835-17-47	1214
	5 ⁷ / ₈	1835-17-57	1394
2 ³ / ₈	1 ³ / ₈	1835-23-13	675
	1 ⁷ / ₈	1835-23-17	765
	2 ³ / ₈	1835-23-23	854
	2 ⁷ / ₈	1835-23-27	944
	3 ³ / ₈	1835-23-33	1034
	3 ⁷ / ₈	1835-23-37	1124
	4 ⁷ / ₈	1835-23-47	1304
	5 ⁷ / ₈	1835-23-57	1484
2 ⁷ / ₈	1 ³ / ₈	1835-27-13	765
	1 ⁷ / ₈	1835-27-17	854
	2 ³ / ₈	1835-27-23	944
	2 ⁷ / ₈	1835-27-27	1034
	3 ³ / ₈	1835-27-33	1124
	3 ⁷ / ₈	1835-27-37	1214
	4 ⁷ / ₈	1835-27-47	1394
	5 ⁷ / ₈	1835-27-57	1574

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1835-33-13	854
	1 ⁷ / ₈	1835-33-17	944
	2 ³ / ₈	1835-33-23	1034
	2 ⁷ / ₈	1835-33-27	1124
	3 ³ / ₈	1835-33-33	1214
	3 ⁷ / ₈	1835-33-37	1304
	4 ⁷ / ₈	1835-33-47	1484
	5 ⁷ / ₈	1835-33-57	1663
3 ⁷ / ₈	1 ³ / ₈	1835-37-13	944
	1 ⁷ / ₈	1835-37-17	1034
	2 ³ / ₈	1835-37-23	1124
	2 ⁷ / ₈	1835-37-27	1214
	3 ³ / ₈	1835-37-33	1304
	3 ⁷ / ₈	1835-37-37	1394
	4 ⁷ / ₈	1835-37-47	1574
	5 ⁷ / ₈	1835-37-57	1753
4 ⁷ / ₈	1 ³ / ₈	1835-47-13	1124
	1 ⁷ / ₈	1835-47-17	1214
	2 ³ / ₈	1835-47-23	1304
	2 ⁷ / ₈	1835-47-27	1394
	3 ³ / ₈	1835-47-33	1484
	3 ⁷ / ₈	1835-47-37	1574
	4 ⁷ / ₈	1835-47-47	1753
	5 ⁷ / ₈	1835-47-57	1933
5 ⁷ / ₈	1 ³ / ₈	1835-57-13	1304
	1 ⁷ / ₈	1835-57-17	1394
	2 ³ / ₈	1835-57-23	1484
	2 ⁷ / ₈	1835-57-27	1574
	3 ³ / ₈	1835-57-33	1663
	3 ⁷ / ₈	1835-57-37	1753
	4 ⁷ / ₈	1835-57-47	1933
	5 ⁷ / ₈	1835-57-57	2113


A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	1924-13-13	361
	1 ⁷ / ₈	1924-13-17	427
	2 ³ / ₈	1924-13-23	493
	2 ⁷ / ₈	1924-13-27	558
	3 ³ / ₈	1924-13-33	624
	3 ⁷ / ₈	1924-13-37	689
	4 ⁷ / ₈	1924-13-47	821
	5 ⁷ / ₈	1924-13-57	952
1 ⁷ / ₈	1 ³ / ₈	1924-17-13	427
	1 ⁷ / ₈	1924-17-17	493
	2 ³ / ₈	1924-17-23	558
	2 ⁷ / ₈	1924-17-27	624
	3 ³ / ₈	1924-17-33	689
	3 ⁷ / ₈	1924-17-37	755
	4 ⁷ / ₈	1924-17-47	886
	5 ⁷ / ₈	1924-17-57	1017
2 ³ / ₈	1 ³ / ₈	1924-23-13	493
	1 ⁷ / ₈	1924-23-17	558
	2 ³ / ₈	1924-23-23	624
	2 ⁷ / ₈	1924-23-27	689
	3 ³ / ₈	1924-23-33	755
	3 ⁷ / ₈	1924-23-37	821
	4 ⁷ / ₈	1924-23-47	952
	5 ⁷ / ₈	1924-23-57	1083
2 ⁷ / ₈	1 ³ / ₈	1924-27-13	558
	1 ⁷ / ₈	1924-27-17	624
	2 ³ / ₈	1924-27-23	689
	2 ⁷ / ₈	1924-27-27	755
	3 ³ / ₈	1924-27-33	821
	3 ⁷ / ₈	1924-27-37	886
	4 ⁷ / ₈	1924-27-47	1017
	5 ⁷ / ₈	1924-27-57	1149

A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	1924-33-13	624
	1 ⁷ / ₈	1924-33-17	689
	2 ³ / ₈	1924-33-23	755
	2 ⁷ / ₈	1924-33-27	821
	3 ³ / ₈	1924-33-33	886
	3 ⁷ / ₈	1924-33-37	952
	4 ⁷ / ₈	1924-33-47	1083
	5 ⁷ / ₈	1924-33-57	1214
3 ⁷ / ₈	1 ³ / ₈	1924-37-13	689
	1 ⁷ / ₈	1924-37-17	755
	2 ³ / ₈	1924-37-23	821
	2 ⁷ / ₈	1924-37-27	886
	3 ³ / ₈	1924-37-33	952
	3 ⁷ / ₈	1924-37-37	1017
	4 ⁷ / ₈	1924-37-47	1149
	5 ⁷ / ₈	1924-37-57	1280
4 ⁷ / ₈	1 ³ / ₈	1924-47-13	821
	1 ⁷ / ₈	1924-47-17	886
	2 ³ / ₈	1924-47-23	952
	2 ⁷ / ₈	1924-47-27	1017
	3 ³ / ₈	1924-47-33	1083
	3 ⁷ / ₈	1924-47-37	1149
	4 ⁷ / ₈	1924-47-47	1280
	5 ⁷ / ₈	1924-47-57	1411
5 ⁷ / ₈	1 ³ / ₈	1924-57-13	952
	1 ⁷ / ₈	1924-57-17	1017
	2 ³ / ₈	1924-57-23	1083
	2 ⁷ / ₈	1924-57-27	1149
	3 ³ / ₈	1924-57-33	1214
	3 ⁷ / ₈	1924-57-37	1280
	4 ⁷ / ₈	1924-57-47	1411
	5 ⁷ / ₈	1924-57-57	1542

Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:



- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment



A	B	ITEM NUMBER	NET WT.
3 ^{3⁄8}	1 ^{3⁄8}	1935-33-13	932
	1 ^{7⁄8}	1935-33-17	1030
	2 ^{3⁄8}	1935-33-23	1128
	2 ^{7⁄8}	1935-33-27	1226
	3 ^{3⁄8}	1935-33-33	1324
	3 ^{7⁄8}	1935-33-37	1422
	4 ^{7⁄8}	1935-33-47	1618
	5 ^{7⁄8}	1935-33-57	1815
3 ^{7⁄8}	1 ^{3⁄8}	1935-37-13	1030
	1 ^{7⁄8}	1935-37-17	1128
	2 ^{3⁄8}	1935-37-23	1226
	2 ^{7⁄8}	1935-37-27	1324
	3 ^{3⁄8}	1935-37-33	1422
	3 ^{7⁄8}	1935-37-37	1520
	4 ^{7⁄8}	1935-37-47	1717
4 ^{7⁄8}	5 ^{7⁄8}	1935-37-57	1913
	1 ^{3⁄8}	1935-47-13	1226
	1 ^{7⁄8}	1935-47-17	1324
	2 ^{3⁄8}	1935-47-23	1422
	2 ^{7⁄8}	1935-47-27	1520
	3 ^{3⁄8}	1935-47-33	1618
	3 ^{7⁄8}	1935-47-37	1717
	4 ^{7⁄8}	1935-47-47	1913
5 ^{7⁄8}	5 ^{7⁄8}	1935-47-57	2109
	1 ^{3⁄8}	1935-57-13	1422
	1 ^{7⁄8}	1935-57-17	1520
	2 ^{3⁄8}	1935-57-23	1618
	2 ^{7⁄8}	1935-57-27	1717
	3 ^{3⁄8}	1935-57-33	1815
	3 ^{7⁄8}	1935-57-37	1913
	4 ^{7⁄8}	1935-57-47	2109
	5 ^{7⁄8}	1935-57-57	2305

U.S. 800-626-6653 ■ Canada 800-387-6600 ■ dme.net ■ store.dme.net

Cavity Retainer Sets



A	B	ITEM NUMBER	NET WT.	A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	2424-13-13	440	3 ³ / ₈	1 ³ / ₈	2424-33-13	760
	1 ⁷ / ₈	2424-13-17	520		1 ⁷ / ₈	2424-33-17	839
	2 ³ / ₈	2424-13-23	600		2 ³ / ₈	2424-33-23	919
	2 ⁷ / ₈	2424-13-27	680		2 ⁷ / ₈	2424-33-27	999
	3 ³ / ₈	2424-13-33	760		3 ³ / ₈	2424-33-33	1079
	3 ⁷ / ₈	2424-13-37	839		3 ⁷ / ₈	2424-33-37	1159
	4 ³ / ₈	2424-13-47	999		4 ³ / ₈	2424-33-47	1319
1 ⁷ / ₈	5 ³ / ₈	2424-13-57	1159	3 ⁷ / ₈	5 ³ / ₈	2424-33-57	1479
	1 ³ / ₈	2424-17-13	520		1 ³ / ₈	2424-37-13	839
	1 ⁷ / ₈	2424-17-17	600		1 ⁷ / ₈	2424-37-17	919
	2 ³ / ₈	2424-17-23	680		2 ³ / ₈	2424-37-23	999
	2 ⁷ / ₈	2424-17-27	760		2 ⁷ / ₈	2424-37-27	1079
	3 ³ / ₈	2424-17-33	839		3 ³ / ₈	2424-37-33	1159
	3 ⁷ / ₈	2424-17-37	919		3 ⁷ / ₈	2424-37-37	1239
2 ³ / ₈	4 ³ / ₈	2424-17-47	1079	4 ³ / ₈	4 ³ / ₈	2424-37-47	1399
	5 ³ / ₈	2424-17-57	1239		5 ³ / ₈	2424-37-57	1559
	1 ³ / ₈	2424-23-13	600		1 ³ / ₈	2424-47-13	999
	1 ⁷ / ₈	2424-23-17	680		1 ⁷ / ₈	2424-47-17	1079
	2 ³ / ₈	2424-23-23	760		2 ³ / ₈	2424-47-23	1159
	2 ⁷ / ₈	2424-23-27	839		2 ⁷ / ₈	2424-47-27	1239
	3 ³ / ₈	2424-23-33	919		3 ³ / ₈	2424-47-33	1319
2 ⁷ / ₈	3 ⁷ / ₈	2424-23-37	999	5 ³ / ₈	3 ³ / ₈	2424-47-37	1399
	4 ³ / ₈	2424-23-47	1159		4 ³ / ₈	2424-47-47	1559
	5 ³ / ₈	2424-23-57	1319		5 ³ / ₈	2424-47-57	1718
	1 ³ / ₈	2424-27-13	680		1 ³ / ₈	2424-57-13	1159
	1 ⁷ / ₈	2424-27-17	760		1 ⁷ / ₈	2424-57-17	1239
	2 ³ / ₈	2424-27-23	839		2 ³ / ₈	2424-57-23	1319
	2 ⁷ / ₈	2424-27-27	919		2 ⁷ / ₈	2424-57-27	1399
2 ⁷ / ₈	3 ³ / ₈	2424-27-33	999	5 ⁷ / ₈	3 ³ / ₈	2424-57-33	1479
	3 ⁷ / ₈	2424-27-37	1079		3 ⁷ / ₈	2424-57-37	1559
	4 ³ / ₈	2424-27-47	1239		4 ³ / ₈	2424-57-47	1718
	5 ³ / ₈	2424-27-57	1399		5 ³ / ₈	2424-57-57	1878

A	B	ITEM NUMBER	NET WT.	A	B	ITEM NUMBER	NET WT.
1 3/8	1 3/8	2429-13-13	546	3 3/8	1 3/8	2429-33-13	943
	1 7/8	2429-13-17	646		1 7/8	2429-33-17	1043
	2 3/8	2429-13-23	745		2 3/8	2429-33-23	1142
	2 7/8	2429-13-27	844		2 7/8	2429-33-27	1241
	3 3/8	2429-13-33	943		3 3/8	2429-33-33	1340
	3 7/8	2429-13-37	1043		3 7/8	2429-33-37	1439
	4 7/8	2429-13-47	1241		4 7/8	2429-33-47	1638
	5 7/8	2429-13-57	1439		5 7/8	2429-33-57	1836
1 7/8	1 3/8	2429-17-13	646	3 7/8	1 3/8	2429-37-13	1043
	1 7/8	2429-17-17	745		1 7/8	2429-37-17	1142
	2 3/8	2429-17-23	844		2 3/8	2429-37-23	1241
	2 7/8	2429-17-27	943		2 7/8	2429-37-27	1340
	3 3/8	2429-17-33	1043		3 3/8	2429-37-33	1439
	3 7/8	2429-17-37	1142		3 7/8	2429-37-37	1539
	4 7/8	2429-17-47	1340		4 7/8	2429-37-47	1737
	5 7/8	2429-17-57	1539		5 7/8	2429-37-57	1936
2 3/8	1 3/8	2429-23-13	745	4 7/8	1 3/8	2429-47-13	1241
	1 7/8	2429-23-17	844		1 7/8	2429-47-17	1340
	2 3/8	2429-23-23	943		2 3/8	2429-47-23	1439
	2 7/8	2429-23-27	1043		2 7/8	2429-47-27	1539
	3 3/8	2429-23-33	1142		3 3/8	2429-47-33	1638
	3 7/8	2429-23-37	1241		3 7/8	2429-47-37	1737
	4 7/8	2429-23-47	1439		4 7/8	2429-47-47	1936
	5 7/8	2429-23-57	1638		5 7/8	2429-47-57	2134
2 7/8	1 3/8	2429-27-13	844	5 7/8	1 3/8	2429-57-13	1439
	1 7/8	2429-27-17	943		1 7/8	2429-57-17	1539
	2 3/8	2429-27-23	1043		2 3/8	2429-57-23	1638
	2 7/8	2429-27-27	1142		2 7/8	2429-57-27	1737
	3 3/8	2429-27-33	1241		3 3/8	2429-57-33	1836
	3 7/8	2429-27-37	1340		3 7/8	2429-57-37	1936
	4 7/8	2429-27-47	1539		4 7/8	2429-57-47	2134
	5 7/8	2429-27-57	1737		5 7/8	2429-57-57	2333


Thickness of each plate is finish ground $\pm .001"$. Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2 $\frac{7}{8}$ thick)
3. L Dimension (Guide Pin Length)
4. Method of Shipment

Cavity Retainer Sets

23³/₄ × 35¹/₂



A	B	ITEM NUMBER	NET WT.
1 ³ / ₈	1 ³ / ₈	2435-13-13	657
	1 ⁷ / ₈	2435-13-17	777
	2 ³ / ₈	2435-13-23	896
	2 ⁷ / ₈	2435-13-27	1016
	3 ³ / ₈	2435-13-33	1135
	3 ⁷ / ₈	2435-13-37	1255
	4 ³ / ₈	2435-13-47	1493
1 ⁷ / ₈	5 ³ / ₈	2435-13-57	1732
	1 ³ / ₈	2435-17-13	777
	1 ⁷ / ₈	2435-17-17	896
	2 ³ / ₈	2435-17-23	1016
	2 ⁷ / ₈	2435-17-27	1135
	3 ³ / ₈	2435-17-33	1255
	3 ⁷ / ₈	2435-17-37	1374
2 ³ / ₈	4 ³ / ₈	2435-17-47	1613
	5 ³ / ₈	2435-17-57	1852
	1 ³ / ₈	2435-23-13	896
	1 ⁷ / ₈	2435-23-17	1016
	2 ³ / ₈	2435-23-23	1135
	2 ⁷ / ₈	2435-23-27	1255
	3 ³ / ₈	2435-23-33	1374
2 ⁷ / ₈	3 ⁷ / ₈	2435-23-37	1493
	4 ³ / ₈	2435-23-47	1732
	5 ³ / ₈	2435-23-57	1971
	1 ³ / ₈	2435-27-13	1016
	1 ⁷ / ₈	2435-27-17	1135
	2 ³ / ₈	2435-27-23	1255
	2 ⁷ / ₈	2435-27-27	1374
2 ⁷ / ₈	3 ³ / ₈	2435-27-33	1493
	3 ⁷ / ₈	2435-27-37	1613
	4 ³ / ₈	2435-27-47	1852
	5 ³ / ₈	2435-27-57	2091


A	B	ITEM NUMBER	NET WT.
3 ³ / ₈	1 ³ / ₈	2435-33-13	1135
	1 ⁷ / ₈	2435-33-17	1255
	2 ³ / ₈	2435-33-23	1374
	2 ⁷ / ₈	2435-33-27	1493
	3 ³ / ₈	2435-33-33	1613
	3 ⁷ / ₈	2435-33-37	1732
	4 ³ / ₈	2435-33-47	1971
3 ⁷ / ₈	5 ³ / ₈	2435-33-57	2210
	1 ³ / ₈	2435-37-13	1255
	1 ⁷ / ₈	2435-37-17	1374
	2 ³ / ₈	2435-37-23	1493
	2 ⁷ / ₈	2435-37-27	1613
	3 ³ / ₈	2435-37-33	1732
	3 ⁷ / ₈	2435-37-37	1852
4 ⁷ / ₈	4 ³ / ₈	2435-37-47	2091
	5 ³ / ₈	2435-37-57	2329
	1 ³ / ₈	2435-47-13	1493
	1 ⁷ / ₈	2435-47-17	1613
	2 ³ / ₈	2435-47-23	1732
	2 ⁷ / ₈	2435-47-27	1852
	3 ³ / ₈	2435-47-33	1971
5 ⁷ / ₈	3 ⁷ / ₈	2435-47-37	2091
	4 ³ / ₈	2435-47-47	2329
	5 ³ / ₈	2435-47-57	2568
	1 ³ / ₈	2435-57-13	1732
	1 ⁷ / ₈	2435-57-17	1852
	2 ³ / ₈	2435-57-23	1971
	2 ⁷ / ₈	2435-57-27	2091
5 ⁷ / ₈	3 ³ / ₈	2435-57-33	2210
	3 ⁷ / ₈	2435-57-37	2329
	4 ³ / ₈	2435-57-47	2568
	5 ³ / ₈	2435-57-57	2807

Thickness of each plate is finish ground $\pm .001$ ". Width and length finished square and parallel.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 or No. 7 Steel
(No. 7 Steel available standard only for plates up to and including 2⁷/₈ thick)
- L Dimension (Guide Pin Length)
- Method of Shipment

Over 400 Standard Mold Plate Sizes
3 Steel Types
2 Plate Finishes



DME Steel

STEEL DESCRIPTIONS

Three Steels for Structural Sections

DME NO. 1 STEEL

No. 1 Steel is a medium carbon (SAE 1030) or equivalent, silicon-killed forging quality steel with approximately 25% greater tensile strength than typical low-carbon warehouse steels. It machines easily, but is not "sticky," permitting a faster and smoother cut.

DME NO. 2 STEEL

No. 2 Steel is an AISI 4130 or equivalent type steel. It is supplied pre-heat treated to 28-34 HRC (271-321 Bhn). A high strength steel, it is ideal for cavity and core retainer plates, clamping plates and support plates in molds and dies. *(Available as a special order)*



DME NO. 7 STEEL

No. 7 Steel is a modified AISI 400 or equivalent series stainless steel for holder block applications. It is supplied pre-heat treated to 32-36 HRC (302-340 Bhn). This stainless steel offers corrosion-resistance and exceptional machinability but cannot be further hardened (see DME No. 6). For humid environments, corrosive plastics, "clean room" or "100% stainless" applications, it is an ideal choice for all structural (non-cavity/core) mold plates.

Three Steels for Cavities and Cores

DME NO. 3 STEEL

No. 3 Steel is a P-20 AISI 4130 (modified) type cavity steel. Exceptionally clean, it is pre-heat treated to 28-34 HRC (271-321 Bhn). It provides high hardness, good machinability and exceptional polishability for both plastics molds and die cast dies.

DME NO. 5 STEEL

No. 5 Steel is a thermal shock resistant, hotwork die steel (AISI-SAE H-13 type) or equivalent. Supplied fully annealed 13-20 HRC (approx. 200 Bhn) for easy machinability, it can be subsequently heat treated to the desired hardness with a minimum of deformation.

Mainly used for die cast dies, it is also suitable for plastics molds with exceptional hardness or polishability requirements.

DME NO. 5 Steel meets or exceeds the acceptance criteria established by the NADCA as detailed in Technical Digest Number 01-80-01D

DME NO. 6 STEEL

No. 6 Steel is T-420 type or equivalent stainless steel. It is supplied fully annealed to 8-23 HRC (179-241 Bhn), making it readily machinable. It can be used for injection, compression or transfer molds where the properties of the plastics materials or excessive condensation require a highly corrosion resistant cavity steel.

OTHER TYPES OF STEEL AVAILABLE ON SPECIAL ORDER. CONTACT DME.

DME Standard Plates

Mold Plates and Plate Items

Mold Plates are available in over 400 standard sizes, from 6" × 7" to 23¾ × 35½ in DME No. 1, No. 3 Steel. Plates from 7⅞ × 7⅞ to 23¾ × 35½ are also available in DME No. 7 Steel (up to 2⅞ thick).

In addition, they are offered in the following two conditions:

FINISH GROUND PLATES

Thickness is finish ground top and bottom to a tolerance of ± .001" with all edges finished square and parallel.

ROTARY GROUND/MILLED PLATES

Thickness is rotary ground/milled to a tolerance of +.015/+.020 or +.025/+.030 depending on plate width. Length and width are milled (+.000/+.005).




Additional standard plate items include:

EJECTOR AND EJECTOR RETAINER PLATES
PLATE ITEMS FOR SMALL MOLD BASES


Spacer Blocks

Plain, Slotted and Angle Spacers are made from DME No. 1 or No. 7 Steel. Riser height (C dimension) is finish ground to plus or minus .001".



Ejector Housings

Modular three-piece construction is made from DME No. 1 Steel. Available in over 150 standard sizes, corresponding to DME Standard "A" Series Mold Bases. The riser height (C dimension) is finish ground to plus or minus .001".




Die Blocks and Plates – No. 5 Steel


Available in over 300 special order sizes from 7⅞ × 7⅞ to 23¾ × 35½; 1⅜ to 11⅞ thick (depending on length and width). They are supplied in milled condition, with approximately .060" stock allowance.

DME No. 5 Steel meets or exceeds the acceptance criteria established by the NADCA as detailed in Technical Digest Number 01-80-01D.

SPECIAL ORDER SIZES: Please contact DME.



Finish Ground Mold Plates 7 $\frac{7}{8}$ through 11 $\frac{7}{8}$ wide



Thickness (A) of plate is finish ground $\pm .001$
Width and length are finished square and parallel.

ALL PLATE THICKNESSES AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type
- DME No. 3 Steel – P-20 type, pre-heat treated (271-321 Bhn; 28-34 HRC)

THICKNESSES FROM $\frac{7}{8}$ TO 2 $\frac{7}{8}$ ALSO AVAILABLE IN:

- DME No. 7 Steel – Modified AISI 400 series stainless steel pre-heat treated (302-340 Bhn; 32-36 HRC)

THICKER PLATES IN DME NO. 7 STEEL ARE AVAILABLE ON SPECIAL ORDER

A	7 $\frac{7}{8}$ x 7 $\frac{7}{8}$		7 $\frac{7}{8}$ x 11 $\frac{7}{8}$		A	9 $\frac{7}{8}$ x 8"		9 $\frac{7}{8}$ x 11 $\frac{7}{8}$	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.		ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
$\frac{7}{8}$	88-7	16	812-7	24	$\frac{7}{8}$	108-7	20	1012-7	30
1 $\frac{1}{8}$	88-13	25	812-13	37	1 $\frac{1}{8}$	108-13	31	1012-13	46
1 $\frac{1}{2}$	88-17	33	812-17	50	1 $\frac{1}{2}$	108-17	42	1012-17	63
2 $\frac{1}{8}$	88-23	42	812-23	63	2 $\frac{1}{8}$	108-23	54	1012-23	79
2 $\frac{1}{2}$	88-27	51	812-27	76	2 $\frac{1}{2}$	108-27	65	1012-27	96
3 $\frac{1}{8}$	88-33	60	812-33	89	3 $\frac{1}{8}$	108-33	76	1012-33	113
3 $\frac{1}{2}$	88-37	69	812-37	102	3 $\frac{1}{2}$	108-37	87	1012-37	129
4 $\frac{1}{8}$	88-47	86	812-47	129	4 $\frac{1}{8}$	108-47	110	1012-47	162
5 $\frac{1}{8}$	88-57	104	812-57	155	5 $\frac{1}{8}$	108-57	132	1012-57	196

A	9 $\frac{7}{8}$ 16"		9 $\frac{7}{8}$ 20"		10 $\frac{7}{8}$ 12"		10 $\frac{7}{8}$ 14"		10 $\frac{7}{8}$ 18"		10 $\frac{7}{8}$ 23 $\frac{1}{2}$ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
$\frac{7}{8}$	1016-7	40	1020-7	49	1112-7	33	1114-7	38	1118-7	49	1123-7	64	$\frac{7}{8}$
1 $\frac{1}{8}$	1016-13	62	1020-13	77	1112-13	51	1114-13	60	1118-13	77	1123-13	100	1 $\frac{1}{8}$
1 $\frac{1}{2}$	1016-17	84	1020-17	105	1112-17	70	1114-17	81	1118-17	104	1123-17	136	1 $\frac{1}{2}$
2 $\frac{1}{8}$	1016-23	107	1020-23	133	1112-23	88	1114-23	103	1118-23	132	1123-23	172	2 $\frac{1}{8}$
2 $\frac{1}{2}$	1016-27	129	1020-27	161	1112-27	107	1114-27	125	1118-27	160	1123-27	209	2 $\frac{1}{2}$
3 $\frac{1}{8}$	1016-33	152	1020-33	189	1112-33	125	1114-33	146	1118-33	188	1123-33	245	3 $\frac{1}{8}$
3 $\frac{1}{2}$	1016-37	174	1020-37	217	1112-37	144	1114-37	168	1118-37	215	1123-37	281	3 $\frac{1}{2}$
4 $\frac{1}{8}$	1016-47	219	1020-47	273	1112-47	181	1114-47	211	1118-47	271	1123-47	353	4 $\frac{1}{8}$
5 $\frac{1}{8}$	1016-57	263	1020-57	329	1112-57	218	1114-57	254	1118-57	326	1123-57	426	5 $\frac{1}{8}$

A	11 $\frac{7}{8}$ 12"		11 $\frac{7}{8}$ 15"		11 $\frac{7}{8}$ 20"		11 $\frac{7}{8}$ 23 $\frac{1}{2}$ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
$\frac{7}{8}$	1212-7	36	1215-7	45	1220-7	59	1223-7	70	$\frac{7}{8}$
1 $\frac{1}{8}$	1212-13	56	1215-13	70	1220-13	93	1223-13	109	1 $\frac{1}{8}$
1 $\frac{1}{2}$	1212-17	76	1215-17	95	1220-17	127	1223-17	149	1 $\frac{1}{2}$
2 $\frac{1}{8}$	1212-23	96	1215-23	120	1220-23	160	1223-23	188	2 $\frac{1}{8}$
2 $\frac{1}{2}$	1212-27	117	1215-27	146	1220-27	194	1223-27	228	2 $\frac{1}{2}$
3 $\frac{1}{8}$	1212-33	137	1215-33	171	1220-33	228	1223-33	267	3 $\frac{1}{8}$
3 $\frac{1}{2}$	1212-37	157	1215-37	196	1220-37	261	1223-37	307	3 $\frac{1}{2}$
4 $\frac{1}{8}$	1212-47	197	1215-47	247	1220-47	329	1223-47	386	4 $\frac{1}{8}$
5 $\frac{1}{8}$	1212-57	238	1215-57	297	1220-57	396	1223-57	465	5 $\frac{1}{8}$

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Method of Shipment

Rotary Ground/Milled Mold Plates 7⁷/₈ through 11⁷/₈ wide

TOLERANCES	88, 812, 108, 1012, 1016, 1112, 1114, 1118, 1212, 1215	1020, 1024, 1123, 1217, 1220, 1223, 1229
Thickness (A)	+0.015 to +0.020	+0.025 to +0.030
Width (W) Nominal +0.0025	+0.000/+0.005	
Length (L) Nominal +0.0025	+0.000/+0.005	

Thickness (A) of plate is rotary ground/milled.
Width and length are milled.

ALL THICKNESSES AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type)
- DME No. 3 Steel – P-20 type, pre-heat treated (271-321 Bhn; 28-34 HRC)

THICKNESSES FROM 7⁷/₈ TO 2⁷/₈ ALSO AVAILABLE IN:

- DME No. 7 Steel – Modified AISI 400 series stainless steel pre-heat treated (302-340 Bhn; 32-36 HRC)

THICKER PLATES IN DME NO. 7 STEEL ARE AVAILABLE ON SPECIAL ORDER

A	7 ⁷ / ₈ × 7 ⁷ / ₈		7 ⁷ / ₈ × 11 ⁷ / ₈		9 ⁷ / ₈ × 8"		9 ⁷ / ₈ × 11 ⁷ / ₈	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
7 ⁷ / ₈	88-7RGM	16	812-7RGM	24	108-7RGM	20	1012-7RGM	30
1 ³ / ₈	88-13RGM	25	812-13RGM	37	108-13RGM	31	1012-13RGM	46
1 ⁷ / ₈	88-17RGM	33	812-17RGM	50	108-17RGM	42	1012-17RGM	63
2 ³ / ₈	88-23RGM	42	812-23RGM	63	108-23RGM	54	1012-23RGM	79
2 ⁷ / ₈	88-27RGM	51	812-27RGM	76	108-27RGM	65	1012-27RGM	96
3 ³ / ₈	88-33RGM	60	812-33RGM	89	108-33RGM	76	1012-33RGM	113
3 ⁷ / ₈	88-37RGM	69	812-37RGM	102	108-37RGM	87	1012-37RGM	129
4 ³ / ₈	88-47RGM	86	812-47RGM	129	108-47RGM	110	1012-47RGM	162
5 ³ / ₈	88-57RGM	104	812-57RGM	155	108-57RGM	132	1012-57RGM	196


A	9 ⁷ / ₈ × 16"		9 ⁷ / ₈ × 23 ³ / ₄		10 ⁷ / ₈ × 12"		10 ⁷ / ₈ × 14"		10 ⁷ / ₈ × 18"		10 ⁷ / ₈ × 23 ¹ / ₂		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
7 ⁷ / ₈	1016-7RGM	40	1024-7RGM	59	1112-7RGM	33	1114-7RGM	38	1118-7RGM	49	1123-7RGM	64	7 ⁷ / ₈
1 ³ / ₈	1016-13RGM	62	1024-13RGM	92	1112-13RGM	51	1114-13RGM	60	1118-13RGM	77	1123-13RGM	100	1 ³ / ₈
1 ⁷ / ₈	1016-17RGM	84	1024-17RGM	125	1112-17RGM	70	1114-17RGM	81	1118-17RGM	104	1123-17RGM	136	1 ⁷ / ₈
2 ³ / ₈	1016-23RGM	107	1024-23RGM	158	1112-23RGM	88	1114-23RGM	103	1118-23RGM	132	1123-23RGM	172	2 ³ / ₈
2 ⁷ / ₈	1016-27RGM	129	1024-27RGM	192	1112-27RGM	107	1114-27RGM	124	1118-27RGM	160	1123-27RGM	209	2 ⁷ / ₈
3 ³ / ₈	1016-33RGM	152	1024-33RGM	225	1112-33RGM	125	1114-33RGM	146	1118-33RGM	188	1123-33RGM	245	3 ³ / ₈
3 ⁷ / ₈	1016-37RGM	174	1024-37RGM	258	1112-37RGM	144	1114-37RGM	168	1118-37RGM	215	1123-37RGM	281	3 ⁷ / ₈
4 ³ / ₈	1016-47RGM	219	1024-47RGM	324	1112-47RGM	181	1114-47RGM	211	1118-47RGM	271	1123-47RGM	353	4 ³ / ₈
5 ³ / ₈	1016-57RGM	263	1024-57RGM	391	1112-57RGM	218	1114-57RGM	254	1118-57RGM	326	1123-57RGM	426	5 ³ / ₈

A	11 ⁷ / ₈ × 12"		11 ⁷ / ₈ × 15"		11 ⁷ / ₈ × 20"		11 ⁷ / ₈ × 23 ¹ / ₂		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
7 ⁷ / ₈	1212-7RGM	36	1215-7RGM	45	1220-7RGM	59	1223-7RGM	70	7 ⁷ / ₈
1 ³ / ₈	1212-13RGM	56	1215-13RGM	70	1220-13RGM	93	1223-13RGM	109	1 ³ / ₈
1 ⁷ / ₈	1212-17RGM	76	1215-17RGM	95	1220-17RGM	127	1223-17RGM	149	1 ⁷ / ₈
2 ³ / ₈	1212-23RGM	96	1215-23RGM	120	1220-23RGM	160	1223-23RGM	188	2 ³ / ₈
2 ⁷ / ₈	1212-27RGM	117	1215-27RGM	146	1220-27RGM	194	1223-27RGM	228	2 ⁷ / ₈
3 ³ / ₈	1212-33RGM	137	1215-33RGM	171	1220-33RGM	228	1223-33RGM	267	3 ³ / ₈
3 ⁷ / ₈	1212-37RGM	157	1215-37RGM	196	1220-37RGM	261	1223-37RGM	307	3 ⁷ / ₈
4 ³ / ₈	1212-47RGM	197	1215-47RGM	247	1220-47RGM	329	1223-47RGM	386	4 ³ / ₈
5 ³ / ₈	1212-57RGM	238	1215-57RGM	297	1220-57RGM	396	1223-57RGM	465	5 ³ / ₈

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Method of Shipment

Finish Ground Mold Plates 13³/₈ through 15⁷/₈ wide



Thickness (A) of plate is finish ground $\pm .001$. Width and length are finished square and parallel.

ALL THICKNESSES AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type
- DME No. 3 Steel – P-20 type, pre-heat treated (271-321 Bhn; 28-34 HRC)

THICKNESSES FROM $\frac{7}{8}$ TO 2 $\frac{7}{8}$ ALSO AVAILABLE IN:

- DME No. 7 Steel – Modified AISI 400 series stainless steel pre-heat treated (302-340 Bhn; 32-36 HRC)

THICKER PLATES IN DME NO. 7 STEEL ARE AVAILABLE ON SPECIAL ORDER

A	13 ³ / ₈ × 15"		13 ³ / ₈ × 18"		13 ³ / ₈ × 20 ³ / ₄ "	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
$\frac{7}{8}$	1315-7	50	1318-7	60	1321-7	69
1 $\frac{1}{8}$	1315-13	79	1318-13	94	1321-13	109
1 $\frac{1}{2}$	1315-17	107	1318-17	128	1321-17	148
2 $\frac{1}{8}$	1315-23	135	1318-23	162	1321-23	187
2 $\frac{1}{2}$	1315-27	164	1318-27	197	1321-27	227
3 $\frac{1}{8}$	1315-33	192	1318-33	231	1321-33	266
3 $\frac{1}{2}$	1315-37	221	1318-37	265	1321-37	305
4 $\frac{1}{8}$	1315-47	278	1318-47	333	1321-47	384
5 $\frac{1}{8}$	1315-57	334	1318-57	401	1321-57	462

A	13 ³ / ₈ × 23 $\frac{1}{2}$ "		13 ³ / ₈ × 26"		13 ³ / ₈ × 29 $\frac{1}{2}$ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
$\frac{7}{8}$	1323-7	78	1326-7	87	1329-7	98	$\frac{7}{8}$
1 $\frac{1}{8}$	1323-13	123	1326-13	136	1329-13	154	1 $\frac{1}{8}$
1 $\frac{1}{2}$	1323-17	167	1326-17	185	1329-17	210	1 $\frac{1}{2}$
2 $\frac{1}{8}$	1323-23	212	1326-23	234	1329-23	266	2 $\frac{1}{8}$
2 $\frac{1}{2}$	1323-27	256	1326-27	284	1329-27	322	2 $\frac{1}{2}$
3 $\frac{1}{8}$	1323-33	301	1326-33	333	1329-33	378	3 $\frac{1}{8}$
3 $\frac{1}{2}$	1323-37	346	1326-37	382	1329-37	434	3 $\frac{1}{2}$
4 $\frac{1}{8}$	1323-47	435	1326-47	481	1329-47	545	4 $\frac{1}{8}$
5 $\frac{1}{8}$	1323-57	524	1326-57	579	1329-57	657	5 $\frac{1}{8}$

A	14 $\frac{7}{8}$ × 17 $\frac{7}{8}$ "		14 $\frac{7}{8}$ × 23 $\frac{3}{4}$ "		14 $\frac{7}{8}$ × 29 $\frac{1}{2}$ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
$\frac{7}{8}$	1518-7	66	1524-7	88	1529-7	109	$\frac{7}{8}$
1 $\frac{1}{8}$	1518-13	104	1524-13	138	1529-13	171	1 $\frac{1}{8}$
1 $\frac{1}{2}$	1518-17	142	1524-17	188	1529-17	233	1 $\frac{1}{2}$
2 $\frac{1}{8}$	1518-23	179	1524-23	238	1529-23	296	2 $\frac{1}{8}$
2 $\frac{1}{2}$	1518-27	217	1524-27	288	1529-27	358	2 $\frac{1}{2}$
3 $\frac{1}{8}$	1518-33	255	1524-33	338	1529-33	420	3 $\frac{1}{8}$
3 $\frac{1}{2}$	1518-37	292	1524-37	388	1529-37	482	3 $\frac{1}{2}$
4 $\frac{1}{8}$	1518-47	368	1524-47	488	1529-47	606	4 $\frac{1}{8}$
5 $\frac{1}{8}$	1518-57	443	1524-57	588	1529-57	731	5 $\frac{1}{8}$

A	15 $\frac{7}{8}$ × 16"		15 $\frac{7}{8}$ × 20"		15 $\frac{7}{8}$ × 23 $\frac{1}{2}$ "		15 $\frac{7}{8}$ × 26"		15 $\frac{7}{8}$ × 29 $\frac{1}{2}$ "		15 $\frac{7}{8}$ × 35 $\frac{1}{2}$ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
$\frac{7}{8}$	1616-7	63	1620-7	79	1623-7	93	1626-7	103	1629-7	116	1635-7	140	$\frac{7}{8}$
1 $\frac{1}{8}$	1616-13	99	1620-13	124	1623-13	146	1626-13	161	1629-13	183	1635-13	220	1 $\frac{1}{8}$
1 $\frac{1}{2}$	1616-17	135	1620-17	169	1623-17	199	1626-17	220	1629-17	249	1635-17	300	1 $\frac{1}{2}$
2 $\frac{1}{8}$	1616-23	171	1620-23	214	1623-23	252	1626-23	278	1629-23	315	1635-23	380	2 $\frac{1}{8}$
2 $\frac{1}{2}$	1616-27	207	1620-27	259	1623-27	304	1626-27	337	1629-27	382	1635-27	459	2 $\frac{1}{2}$
3 $\frac{1}{8}$	1616-33	243	1620-33	304	1623-33	357	1626-33	395	1629-33	448	1635-33	539	3 $\frac{1}{8}$
3 $\frac{1}{2}$	1616-37	279	1620-37	349	1623-37	410	1626-37	454	1629-37	515	1635-37	619	3 $\frac{1}{2}$
4 $\frac{1}{8}$	1616-47	351	1620-47	439	1623-47	516	1626-47	570	1629-47	647	1635-47	779	4 $\frac{1}{8}$
5 $\frac{1}{8}$	1616-57	423	1620-57	529	1623-57	621	1626-57	687	1629-57	780	1635-57	938	5 $\frac{1}{8}$

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Method of Shipment

Rotary Ground/Milled Mold Plates 13³/₈ through 15⁷/₈ wide

Mold Plate Size	TOLERANCES	
	1315, 1318, 1518	1321, 1323, 1326, 1329, 1524, 1529, 1616, 1620, 1623, 1626, 1629, 1635
Thickness (A)	+0.015 to +0.020	+0.025 to +0.030
Width (W) Nominal +.0025	+.000/+.005	
Length (L) Nominal +.0025	+.000/+.005	

Thickness (A) of plate is rotary ground/milled. Width and length are milled.

ALL THICKNESSES AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type
- DME No. 3 Steel – P-20 type, pre-heat treated (271-321 Bhn; 28-34 HRC)

THICKNESSES FROM ⁷/₈ TO 2⁷/₈ ALSO AVAILABLE IN:

- DME No. 7 Steel – Modified AISI 400 series stainless steel pre-heat treated (302-340 Bhn; 32-36 HRC)

THICKER PLATES IN DME NO. 7 STEEL ARE AVAILABLE ON SPECIAL ORDER

A	13 ³ / ₈ × 15"		13 ³ / ₈ × 18"		13 ³ / ₈ × 20 ³ / ₄ "	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
⁷ / ₈	1315-7RGM	50	1318-7RGM	60	1321-7RGM	69
1 ¹ / ₈	1315-13RGM	79	1318-13RGM	94	1321-13RGM	109
1 ¹ / ₂	1315-17RGM	107	1318-17RGM	128	1321-17RGM	148
2 ¹ / ₈	1315-23RGM	135	1318-23RGM	162	1321-23RGM	187
2 ¹ / ₂	1315-27RGM	164	1318-27RGM	197	1321-27RGM	227
3 ¹ / ₈	1315-33RGM	192	1318-33RGM	231	1321-33RGM	266
3 ¹ / ₂	1315-37RGM	221	1318-37RGM	265	1321-37RGM	305
4 ¹ / ₈	1315-47RGM	278	1318-47RGM	333	1321-47RGM	384
5 ¹ / ₈	1315-57RGM	334	1318-57RGM	401	1321-57RGM	462

A	13 ³ / ₈ × 23 ¹ / ₂ "		13 ³ / ₈ × 26"		13 ³ / ₈ × 29 ¹ / ₂ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⁷ / ₈	1323-7RGM	78	1326-7RGM	87	1329-7RGM	98	⁷ / ₈
1 ¹ / ₈	1323-13RGM	123	1326-13RGM	136	1329-13RGM	154	1 ¹ / ₈
1 ¹ / ₂	1323-17RGM	167	1326-17RGM	185	1329-17RGM	210	1 ¹ / ₂
2 ¹ / ₈	1323-23RGM	212	1326-23RGM	234	1329-23RGM	266	2 ¹ / ₈
2 ¹ / ₂	1323-27RGM	256	1326-27RGM	284	1329-27RGM	322	2 ¹ / ₂
3 ¹ / ₈	1323-33RGM	301	1326-33RGM	333	1329-33RGM	378	3 ¹ / ₈
3 ¹ / ₂	1323-37RGM	346	1326-37RGM	382	1329-37RGM	434	3 ¹ / ₂
4 ¹ / ₈	1323-47RGM	435	1326-47RGM	481	1329-47RGM	545	4 ¹ / ₈
5 ¹ / ₈	1323-57RGM	524	1326-57RGM	579	1329-57RGM	657	5 ¹ / ₈


A	14 ¹ / ₈ × 17 ¹ / ₈ "		14 ¹ / ₈ × 23 ¹ / ₄ "		14 ¹ / ₈ × 29"		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⁷ / ₈	1518-7RGM	66	1524-7RGM	88	1529-7RGM	109	⁷ / ₈
1 ¹ / ₈	1518-13RGM	104	1524-13RGM	138	1529-13RGM	171	1 ¹ / ₈
1 ¹ / ₂	1518-17RGM	142	1524-17RGM	188	1529-17RGM	233	1 ¹ / ₂
2 ¹ / ₈	1518-23RGM	179	1524-23RGM	238	1529-23RGM	296	2 ¹ / ₈
2 ¹ / ₂	1518-27RGM	217	1524-27RGM	288	1529-27RGM	358	2 ¹ / ₂
3 ¹ / ₈	1518-33RGM	255	1524-33RGM	338	1529-33RGM	420	3 ¹ / ₈
3 ¹ / ₂	1518-37RGM	292	1524-37RGM	388	1529-37RGM	482	3 ¹ / ₂
4 ¹ / ₈	1518-47RGM	368	1524-47RGM	488	1529-47RGM	606	4 ¹ / ₈
5 ¹ / ₈	1518-57RGM	443	1524-57RGM	588	1529-57RGM	731	5 ¹ / ₈

A	15 ⁷ / ₈ × 16"		15 ⁷ / ₈ × 20"		15 ⁷ / ₈ × 23 ¹ / ₂ "		15 ⁷ / ₈ × 26"		15 ⁷ / ₈ × 29 ¹ / ₂ "		15 ⁷ / ₈ × 35 ¹ / ₂ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⁷ / ₈	1616-7RGM	63	1620-7RGM	79	1623-7RGM	93	1626-7RGM	103	1629-7RGM	116	1635-7RGM	140	⁷ / ₈
1 ¹ / ₈	1616-13RGM	99	1620-13RGM	124	1623-13RGM	146	1626-13RGM	161	1629-13RGM	183	1635-13RGM	220	1 ¹ / ₈
1 ¹ / ₂	1616-17RGM	135	1620-17RGM	169	1623-17RGM	199	1626-17RGM	220	1629-17RGM	249	1635-17RGM	300	1 ¹ / ₂
2 ¹ / ₈	1616-23RGM	171	1620-23RGM	214	1623-23RGM	252	1626-23RGM	278	1629-23RGM	315	1635-23RGM	380	2 ¹ / ₈
2 ¹ / ₂	1616-27RGM	207	1620-27RGM	259	1623-27RGM	304	1626-27RGM	337	1629-27RGM	382	1635-27RGM	459	2 ¹ / ₂
3 ¹ / ₈	1616-33RGM	243	1620-33RGM	304	1623-33RGM	357	1626-33RGM	395	1629-33RGM	448	1635-33RGM	539	3 ¹ / ₈
3 ¹ / ₂	1616-37RGM	279	1620-37RGM	349	1623-37RGM	410	1626-37RGM	454	1629-37RGM	515	1635-37RGM	619	3 ¹ / ₂
4 ¹ / ₈	1616-47RGM	351	1620-47RGM	439	1623-47RGM	516	1626-47RGM	570	1629-47RGM	647	1635-47RGM	779	4 ¹ / ₈
5 ¹ / ₈	1616-57RGM	423	1620-57RGM	529	1623-57RGM	621	1626-57RGM	687	1629-57RGM	780	1635-57RGM	938	5 ¹ / ₈

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Method of Shipment

Finished Mold Plates 16½ through 23¾ wide



Thickness (A) of plate is finish ground ± 0.001 . Width and length are finished square and parallel.

ALL THICKNESSES AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type
- DME No. 3 Steel – P-20 type, pre-heat treated (271-321 Bhn; 28-34 HRC)

THICKNESSES FROM ⅞ TO 2⅞ ALSO AVAILABLE IN:

- DME No. 7 Steel – Modified AISI 400 series stainless steel pre-heat treated (302-340 Bhn; 32-36 HRC)

THICKER PLATES IN DME NO. 7 STEEL ARE AVAILABLE ON SPECIAL ORDER

A	16½ × 23¾		16½ × 29½		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⅞	1724-7	98	1729-7	121	⅞
1⅞	1724-13	153	1729-13	190	1⅞
1⅞	1724-17	209	1729-17	259	1⅞
2⅞	1724-23	264	1729-23	328	2⅞
2⅞	1724-27	320	1729-27	397	2⅞
3⅞	1724-33	375	1729-33	466	3⅞
3⅞	1724-37	431	1729-37	535	3⅞
4⅞	1724-47	542	1729-47	673	4⅞
5⅞	1724-57	653	1729-57	811	5⅞

A	17⅞ × 18"		17⅞ × 20"		17⅞ × 23½		17⅞ × 26"		17⅞ × 29½		17⅞ × 35½		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⅞	1818-7	80	1820-7	89	1823-7	105	1826-7	116	1829-7	131	1835-7	158	⅞
1⅞	1818-13	126	1820-13	140	1823-13	164	1826-13	182	1829-13	206	1835-13	248	1⅞
1⅞	1818-17	171	1820-17	190	1823-17	224	1826-17	247	1829-17	281	1835-17	338	1⅞
2⅞	1818-23	217	1820-23	241	1823-23	283	1826-23	313	1829-23	355	1835-23	427	2⅞
2⅞	1818-27	263	1820-27	292	1823-27	343	1826-27	379	1829-27	430	1835-27	517	2⅞
3⅞	1818-33	308	1820-33	342	1823-33	402	1826-33	445	1829-33	505	1835-33	607	3⅞
3⅞	1818-37	354	1820-37	393	1823-37	462	1826-37	511	1829-37	579	1835-37	697	3⅞
4⅞	1818-47	445	1820-47	494	1823-47	581	1826-47	642	1829-47	729	1835-47	877	4⅞
5⅞	1818-57	536	1820-57	596	1823-57	700	1826-57	774	1829-57	878	1835-57	1057	5⅞

A	19½ × 23¾		19½ × 29½		19½ × 35½		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⅞	1924-7	115	1929-7	143	1935-7	172	⅞
1⅞	1924-13	181	1929-13	224	1935-13	270	1⅞
1⅞	1924-17	246	1929-17	306	1935-17	368	1⅞
2⅞	1924-23	312	1929-23	387	1935-23	466	2⅞
2⅞	1924-27	378	1929-27	469	1935-27	564	2⅞
3⅞	1924-33	443	1929-33	550	1935-33	662	3⅞
3⅞	1924-37	509	1929-37	632	1935-37	760	3⅞
4⅞	1924-47	640	1929-47	795	1935-47	956	4⅞
5⅞	1924-57	771	1929-57	958	1935-57	1153	5⅞

A	23¾ × 23¾		23¾ × 29½		23¾ × 35½		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⅞	2424-7	140	2429-7	174	2435-7	209	⅞
1⅞	2424-13	220	2429-13	273	2435-13	329	1⅞
1⅞	2424-17	300	2429-17	373	2435-17	448	1⅞
2⅞	2424-23	380	2429-23	472	2435-23	568	2⅞
2⅞	2424-27	460	2429-27	571	2435-27	687	2⅞
3⅞	2424-33	540	2429-33	670	2435-33	807	3⅞
3⅞	2424-37	620	2429-37	770	2435-37	926	3⅞
4⅞	2424-47	779	2429-47	968	2435-47	1165	4⅞
5⅞	2424-57	939	2429-57	1167	2435-57	1404	5⅞

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Method of Shipment

Rotary Ground/Milled Mold Plates 16½ through 23¾ wide

Mold Plate Size	TOLERANCES	
	1315, 1318, 1518	1321, 1323, 1326, 1329, 1524, 1529, 1616, 1620, 1623, 1626, 1629, 1635
Thickness (A)	+0.015 to +0.020	+0.025 to +0.030
Width (W) Nominal +0.0025	+0.000/+0.005	
Length (L) Nominal +0.0025	+0.000/+0.005	

Thickness (A) of plate is rotary ground/milled. Width and length are milled.

ALL THICKNESSES AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type
- DME No. 3 Steel – P-20 type, pre-heat treated (271-321 Bhn; 28-34 HRC)

THICKNESSES FROM ⅞ TO 2⅞ ALSO AVAILABLE IN:

- DME No. 7 Steel – Modified AISI 400 series stainless steel pre-heat treated (302-340 Bhn; 32-36 HRC)

THICKER PLATES IN DME NO. 7 STEEL ARE AVAILABLE ON SPECIAL ORDER

A	16½ × 23¾		16½ × 29½		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⅞	1724-7RGM	98	1729-7RGM	121	⅞
1⅞	1724-13RGM	153	1729-13RGM	190	1⅞
1⅞	1724-17RGM	209	1729-17RGM	259	1⅞
2⅞	1724-23RGM	264	1729-23RGM	328	2⅞
2⅞	1724-27RGM	320	1729-27RGM	397	2⅞
3⅞	1724-33RGM	375	1729-33RGM	466	3⅞
3⅞	1724-37RGM	431	1729-37RGM	535	3⅞
4⅞	1724-47RGM	542	1729-47RGM	673	4⅞
5⅞	1724-57RGM	653	1729-57RGM	811	5⅞


A	17⅞ × 18"		17⅞ × 20"		17⅞ × 23½		17⅞ × 26"		17⅞ × 29½		17⅞ × 35½		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⅞	1818-7RGM	80	1820-7RGM	89	1823-7RGM	105	1826-7RGM	116	1829-7RGM	131	1835-7RGM	158	⅞
1⅞	1818-13RGM	126	1820-13RGM	140	1823-13RGM	164	1826-13RGM	182	1829-13RGM	206	1835-13RGM	248	1⅞
1⅞	1818-17RGM	171	1820-17RGM	190	1823-17RGM	224	1826-17RGM	247	1829-17RGM	281	1835-17RGM	338	1⅞
2⅞	1818-23RGM	217	1820-23RGM	241	1823-23RGM	283	1826-23RGM	313	1829-23RGM	355	1835-23RGM	427	2⅞
2⅞	1818-27RGM	263	1820-27RGM	292	1823-27RGM	343	1826-27RGM	379	1829-27RGM	430	1835-27RGM	517	2⅞
3⅞	1818-33RGM	308	1820-33RGM	342	1823-33RGM	402	1826-33RGM	445	1829-33RGM	505	1835-33RGM	607	3⅞
3⅞	1818-37RGM	354	1820-37RGM	393	1823-37RGM	462	1826-37RGM	511	1829-37RGM	579	1835-37RGM	697	3⅞
4⅞	1818-47RGM	445	1820-47RGM	494	1823-47RGM	581	1826-47RGM	642	1829-47RGM	729	1835-47RGM	877	4⅞
5⅞	1818-57RGM	536	1820-57RGM	596	1823-57RGM	700	1826-57RGM	774	1829-57RGM	878	1835-57RGM	1057	5⅞

A	19½ × 23¾		19½ × 29½		19½ × 35½		A	A	23¾ × 23¾		23¾ × 29½		23¾ × 35½		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.			ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
⅞	1924-7RGM	115	1929-7RGM	143	1935-7RGM	172	⅞	⅞	2424-7RGM	140	2429-7RGM	174	2435-7RGM	209	⅞
1⅞	1924-13RGM	181	1929-13RGM	224	1935-13RGM	270	1⅞	1⅞	2424-13RGM	220	2429-13RGM	273	2435-13RGM	329	1⅞
1⅞	1924-17RGM	246	1929-17RGM	306	1935-17RGM	368	1⅞	1⅞	2424-17RGM	300	2429-17RGM	373	2435-17RGM	448	1⅞
2⅞	1924-23RGM	312	1929-23RGM	387	1935-23RGM	466	2⅞	2⅞	2424-23RGM	380	2429-23RGM	472	2435-23RGM	568	2⅞
2⅞	1924-27RGM	378	1929-27RGM	469	1935-27RGM	564	2⅞	2⅞	2424-27RGM	460	2429-27RGM	571	2435-27RGM	687	2⅞
3⅞	1924-33RGM	443	1929-33RGM	550	1935-33RGM	662	3⅞	3⅞	2424-33RGM	540	2429-33RGM	670	2435-33RGM	807	3⅞
3⅞	1924-37RGM	509	1929-37RGM	632	1935-37RGM	760	3⅞	3⅞	2424-37RGM	620	2429-37RGM	770	2435-37RGM	926	3⅞
4⅞	1924-47RGM	640	1929-47RGM	795	1935-47RGM	956	4⅞	4⅞	2424-47RGM	779	2429-47RGM	968	2435-47RGM	1165	4⅞
5⅞	1924-57RGM	771	1929-57RGM	958	1935-57RGM	1153	5⅞	5⅞	2424-57RGM	939	2429-57RGM	1167	2435-57RGM	1404	5⅞

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 or No. 7 Steel
3. Method of Shipment

Ejector Plates DME No. 1 Steel



Thickness of plate is finish ground to a tolerance of plus or minus .001".


WIDTH OF MOLD BASE	A THICK	M WIDTH	E LENGTH	ITEM NUMBER	NET WT.
$7\frac{7}{8}$	1	$5\frac{1}{4}$	$7\frac{7}{8}$	6-88	8
			$11\frac{1}{8}$	6-812	12
			16	6-816	15
			20	6-820	19
$9\frac{7}{8}$	1	$6\frac{7}{8}$	8	6-108	16
			$11\frac{1}{8}$	6-1012	24
			16	6-1016	32
			20	6-1020	39
			$23\frac{1}{2}$	6-1023	46
			$29\frac{1}{2}$	6-1029	58
$10\frac{7}{8}$	1	$7\frac{7}{8}$	12	6-1112	26
			14	6-1114	30
			18	6-1118	38
			$23\frac{1}{2}$	6-1123	50
$11\frac{7}{8}$	$1\frac{1}{8}$	$8\frac{7}{8}$	$29\frac{1}{2}$	6-1129	62
			12	6-1212	33
			15	6-1215	41
			20	6-1220	54
			$23\frac{1}{2}$	6-1223	63

WIDTH OF MOLD BASE	A THICK	M WIDTH	E LENGTH	ITEM NUMBER	NET WT.
$13\frac{3}{8}$	$1\frac{1}{8}$	$9\frac{1}{2}$	15	6-1315	46
			18	6-1318	55
			$18\frac{1}{2}$	6-1319	57
			$20\frac{3}{4}$	6-1321	63
			$23\frac{3}{4}$	6-1323	72
			26	6-1326	79
$14\frac{7}{8}$	$1\frac{1}{8}$	11	$29\frac{1}{2}$	6-1329	90
			$35\frac{1}{2}$	6-1335	108
			$17\frac{7}{8}$	6-1518	63
			$23\frac{3}{4}$	6-1524	84
$15\frac{7}{8}$	$1\frac{1}{8}$	12	$29\frac{1}{2}$	6-1529	104
			$35\frac{1}{2}$	6-1535	125
			16	6-1616	62
			20	6-1620	77
$16\frac{1}{2}$	$1\frac{1}{8}$	$12\frac{5}{8}$	$23\frac{1}{2}$	6-1623	90
			26	6-1626	100
			$29\frac{1}{2}$	6-1629	113
			$35\frac{1}{2}$	6-1635	136
$17\frac{7}{8}$	$1\frac{1}{8}$	14	$23\frac{3}{4}$	6-1724	96
			$29\frac{1}{2}$	6-1729	119
			$35\frac{1}{2}$	6-1735	143
			18	6-1818	81
$19\frac{1}{2}$	$1\frac{1}{8}$	15	20	6-1820	90
			$23\frac{1}{2}$	6-1823	105
			26	6-1826	117
			$29\frac{1}{2}$	6-1829	132
$23\frac{3}{4}$	$1\frac{1}{8}$	19	$35\frac{1}{2}$	6-1835	159
			$23\frac{3}{4}$	6-1924	119
			$29\frac{1}{2}$	6-1929	147
			$35\frac{1}{2}$	6-1935	177
$23\frac{3}{4}$	$1\frac{1}{8}$	19	$23\frac{3}{4}$	6-2424	151
			$29\frac{1}{2}$	6-2429	187
			$35\frac{1}{2}$	6-2435	225

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment

Ejector Retainer Plates DME No. 1 Steel



Thickness of plate tolerance of plus .015", minus .000".



A THICK	M WIDTH	L LENGTH	USED WITH MOLD BASES LISTED BELOW	ITEM NUMBER	NET WT.
1/2	6%	8	9% × 8	7-108	8
		11%	9% × 11%	7-1012	12
		16	9% × 16	7-1016	16
		20	9% × 20	7-1020	20
	7%	12	10% × 12	7-1112	13
		14	10% × 14	7-1114	15
		18	10% × 18	7-1118	19
		23½	10% × 23½	7-1123	25
	8%	12	11% × 12	7-1212	15
		15	11% × 15	7-1215	18
		20	11% × 20	7-1220	24
		23½	11% × 23½	7-1223	28
5/8	9½	15	13% × 15	7-1315	26
		18	13% × 18	7-1318	31
		20¾	13% × 20¾	7-1321	35
		23½	13% × 23½	7-1323	40
		26	13% × 26	7-1326	44
		29½	13% × 29½	7-1329	50
	11	17%	14% × 17%	7-1518	35
		23¾	14% × 23¾	7-1524	47
		29½	14% × 29½	7-1529	58

A THICK	M WIDTH	L LENGTH	USED WITH MOLD BASES LISTED BELOW	ITEM NUMBER	NET WT.
5/8 (cont.)	12	16	15% × 16	7-1616	34
		20	15% × 20	7-1620	43
		23½	15% × 23½	7-1623	50
		26	15% × 26	7-1626	58
		29½	15% × 29½	7-1629	63
		35½	15% × 35½	7-1635	76
	12%	23¾	16% × 23¾	7-1724	54
		29½	16% × 29½	7-1729	66
	14	18	17% × 18	7-1818	45
		20	17% × 20	7-1820	50
		23½	17% × 23½	7-1823	59
		26	17% × 26	7-1826	65
		29½	17% × 29½	7-1829	74
		35½	17% × 35½	7-1835	89
	15%	23¾	19½ × 23¾	7-1924	66
		29½	19½ × 29½	7-1929	82
		35½	19½ × 35½	7-1935	99
	19%	23¾	23¾ × 23¾	7-2424	84
		29½	23¾ × 29½	7-2429	104
		35½	23¾ × 35½	7-2435	125

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment

Spacer Blocks Plain and Slotted – DME No. 1 Steel



Machined all over. Riser height ("C" dimension) is finish ground to a tolerance of plus or minus .001". Width ("P" dimension) is rough ground to a tolerance of - .000, + .015. Finish ground width available on special order.

P	L	C	PLAIN	SLOTTED	
			ITEM NUMBER	NET WT.	ITEM NUMBER
1 ⁵ / ₁₆	11 ¹ / ₈	2 ¹ / ₂	25-912V	8	—
1 ¹ / ₄	7 ¹ / ₈	2 ¹ / ₂	25-408	7	25-508
		3	30-408	9	30-508
1 ⁷ / ₁₆	8	2 ¹ / ₂	25-608	9	25-708
		3	30-608	10	30-708
		4	40-608	14	40-708
		5	50-608	17	50-708
	11 ¹ / ₈	2 ¹ / ₂	25-612	13	25-712
		3	30-612	15	30-712
		4	40-612	20	40-712
		5	50-612	25	50-712
	16	2 ¹ / ₂	25-616	17	25-716
		3	30-616	20	30-716
		4	40-616	27	40-716
		5	50-616	33	50-716
1 ¹ / ₂	20	2 ¹ / ₂	25-620	21	25-720
		3	30-620	25	30-720
		4	40-620	33	40-720
		5	50-620	41	50-720
	12	3	30-112	18	30-212
		4	40-112	23	40-212
		5	50-112	29	50-212
		6	60-112	35	60-212
	15	3	30-115	22	30-215
		4	40-115	29	40-215
		5	50-115	36	50-215
		6	60-115	44	60-215
	18	3	30-118	26	30-218
		4	40-118	35	40-218
		5	50-118	44	50-218
		6	60-118	52	60-218
	20	3	30-120	29	30-220
		4	40-120	39	40-220
		5	50-120	48	50-220
		6	60-120	58	60-220
	23 ¹ / ₂	3	30-123	34	30-223
		4	40-123	45	40-223
		5	50-123	57	50-223
		6	60-123	68	60-223

P	L	C	PLAIN	SLOTTED	
			ITEM NUMBER	NET WT.	ITEM NUMBER
1 ¹ / ₂ (cont.)	26	3	30-126	38	30-226
		4	40-126	50	40-226
		5	50-126	63	50-226
		6	60-126	75	60-226
	29 ¹ / ₂	3	30-129	43	30-229
		4	40-129	57	40-229
		5	50-129	71	50-229
		6	60-129	85	60-229
	35 ¹ / ₂	3	30-135	51	30-235
		4	40-135	68	40-235
		5	50-135	85	50-235
		6	60-135	102	60-235
	18	3	30-418	29	30-518
		4	40-418	39	40-518
		5	50-418	48	50-518
		6	60-418	58	60-518
	20	3	30-420	32	30-520
		4	40-420	43	40-520
		5	50-420	54	50-520
		6	60-420	64	60-520
	23 ³ / ₄	3	30-424	38	30-524
		4	40-424	51	40-524
		5	50-424	64	50-524
		6	60-424	76	60-524
	26	3	30-426	42	30-526
		4	40-426	56	40-526
		5	50-426	70	50-526
		6	60-426	83	60-526
	29 ¹ / ₂	3	30-429	48	30-529
		4	40-429	63	40-529
		5	50-429	79	50-529
		6	60-429	95	60-529
	35 ¹ / ₂	3	30-435	57	30-535
		4	40-435	76	40-535
		5	50-435	95	50-535
		6	60-435	114	60-535

WHEN ORDERING, PLEASE SPECIFY:




1. Quantity
2. Item Number
3. Method of Shipment

A-Slotted Rails – DME No. 1 Steel and No. 7 Steel

A-Slotted Rails

AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type
- DME No. 7 Steel – Modified AISI 400 series stainless steel



STEEL DESCRIPTIONS

DME NO. 1 STEEL

No. 1 Steel is a medium carbon (SAE 1030) or equivalent, silicon-killed forging quality steel with approximately 25% greater tensile strength than typical low-carbon warehouse steels. It machines easily, but is not “sticky,” permitting a faster and smoother cut.

DME NO. 7 STEEL

No. 7 Steel is a modified AISI 400 or equivalent series stainless steel for holder block applications. It is supplied pre-heat treated to 32-36 HRC (302-340 Bhn). This stainless steel offers corrosion-resistance and exceptional machinability but cannot be further hardened (see DME No. 6). For humid environments, corrosive plastics, “clean room” or “100% stainless” applications, it is an ideal choice for all structural (non-cavity/core) mold plates.

For A-Slotted Rails in other steel types please contact DME Customer Service.

HOW TO ORDER: Specify Item Number Prefix (SA), Steel Type (S), Rail Width (P), Rail Length (L), Rail Height (C) and Item Number Suffix (0030).

Item Key:

SA	(S)	(P)	(L)	(C)	0030
----	-----	-----	-----	-----	------

SA : Item Number Prefix

(S) : Enter **1** for #1 steel or **7** for #7 steel

(P) : Rail Width

12 – 1.25 [1 1/4] (mold base series 88 and 812)

14 – 1.4375 [1 7/16] (mold base series 10xx)

16 – 1.6875 [1 11/16] (mold base series 11xx and 12xx)

17 – 1.875 [1 7/8] (mold base series 13xx and larger)

(L) : Rail Length (same as mold base length – examples 7 7/8 = **08**, 11 7/8 = **12**)

(C) : Rail Height (C dimension – do not include decimals – examples 2.5 = **25**, 3.0 = **30**, 3.5 = **35**, 4.0 = **40**, 4.5 = **45**)

0030 : Item Number Suffix

Example:

SA **1**1408**25**0030

Example:

SA **7**1412**30**0030



Do not include dashes or decimals in your item number.

Pre-Drilled A-Slotted Rails – DME No. 1 Steel and No. 7 Steel

Pre-Drilled A-Slotted Rails for 3-Piece Housings

AVAILABLE IN:

- DME No. 1 Steel – SAE 1030 type
- DME No. 7 Steel – Modified AISI 400 series stainless steel



STEEL DESCRIPTIONS

DME NO. 1 STEEL

No. 1 Steel is a medium carbon (SAE 1030) or equivalent, silicon-killed forging quality steel with approximately 25% greater tensile strength than typical low-carbon warehouse steels. It machines easily, but is not "sticky," permitting a faster and smoother cut.

DME NO. 7 STEEL

No. 7 Steel is a modified AISI 400 or equivalent series stainless steel for holder block applications. It is supplied pre-heat treated to 32-36 HRC (302-340 Bhn). This stainless steel offers corrosion-resistance and exceptional machinability but cannot be further hardened (see DME No. 6). For humid environments, corrosive plastics, "clean room" or "100% stainless" applications, it is an ideal choice for all structural (non-cavity/core) mold plates.

For A-Slotted Rails in other steel types please contact DME Customer Service.

HOW TO ORDER: Specify Item Number Prefix (SA), Steel Type (S), Rail Width (P), Rail Length (L), Rail Height (C), Mold Base Width (W) and Item Number Suffix (70).

Item Key:

SA	(S)	(P)	(L)	(C)	(W)	70
----	-----	-----	-----	-----	-----	----

SA : Item Number Prefix

(S) : Enter **1** for #1 steel or **7** for #7 steel

(P) : Rail Width

12 – 1.25 [1 1/4] (mold base series 88 and 812)

14 – 1.4375 [1 7/16] (mold base series 10xx)

16 – 1.6875 [1 11/16] (mold base series 11xx and 12xx)

17 – 1.875 [1 7/8] (mold base series 13xx and larger)

(L) : Rail Length (same as mold base length – examples 7 7/8 = **08**, 11 7/8 = **12**)

(C) : Rail Height (C dimension – do not include decimals – examples 2.5 = **25**, 3.0 = **30**, 3.5 = **35**, 4.0 = **40**, 4.5 = **45**)

(W) : Mold Base Width - examples 7 7/8 = **08**, 19 1/2 = **19**

70 : Item Number Suffix

Example:

SA11208250870

Example:



SA71412301070

Do not include dashes or decimals in your item number.

Spacer Blocks Angle Spacers – DME No. 1 Steel


Riser height ("C" dimension) is finish ground to a tolerance of plus or minus .001".

These Angle Spacers are useful for the buildup of Compression Mold Assemblies.




AUXILIARY SPACER PLATENS

When the use of Auxiliary Spacer Platens becomes necessary to reduce the minimum daylight of the press, the importance of proper rigidity cannot be over-emphasized. The drawing shown here illustrates a typical installation that meets good rigidity requirements. The distance between the parallel spacer blocks is dependent on the location of the knock-out rods on the press.



The drawing shown below illustrates a recommended design that is available from DME on special order. The use of standard DME mold plates and spacer blocks can help keep the cost at a minimum. A detailed drawing should accompany your request for a quotation.





L	C	ITEM NUMBER	NET WT.
12	3	30-312	22
	4	40-312	27
	5	50-312	32
	6	60-312	37
15	3	30-315	28
	4	40-315	34
	5	50-315	40
18	3	30-318	33
	4	40-318	41
	5	50-318	48
	6	60-318	56
20	3	30-320	37
	4	40-320	45
	5	50-320	54
23 $\frac{3}{4}$	6	60-320	62
	3	30-324	43
	4	40-324	53
	5	50-324	64
26	6	60-324	74
	3	30-326	47
	4	40-326	59
	5	50-326	70
29 $\frac{1}{2}$	6	60-326	81
	3	30-329	54
	4	40-329	66
	5	50-329	79
35 $\frac{1}{2}$	6	60-329	91
	3	30-335	65
	4	40-335	80
	5	50-335	95
	6	60-335	110

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment

Ejector Housings

7⁷/₈ to 13³/₈ Wide – DME No. 1 Steel



Three piece construction provides modular capabilities. Easily swap rails with an existing bottom clamp plate to obtain a different riser height.

Riser height ("C" dimension) is finish ground to a tolerance of plus or minus .001". Outer surfaces are finished square and parallel.

NOTES:

Thickness of the base plate (T) is ⁷/₈" for all sizes from 7⁷/₈" to 19¹/₂" wide. The base plate for the 23³/₄" wide series is 1¹/₂" thick.

* ¹/₂" on 88A and 812A Series Mold Bases

Stripper bolt hole locations (4) on the horizontal or "X" axis are 1.0" out board from the standard assembly mounting screws

DETAIL DIMENSIONS

W	7 ⁷ / ₈	9 ¹ / ₈	10 ³ / ₈	11 ¹ / ₈	13 ¹ / ₈	14 ¹ / ₈	15 ¹ / ₈	16 ¹ / ₂	17 ¹ / ₈	19 ¹ / ₂	23 ³ / ₄
P	1 ¹ / ₄	1 ⁷ / ₁₆	1 ¹¹ / ₁₆	1 ¹ / ₁₆	1 ¹ / ₈	1 ¹ / ₈	1 ¹ / ₈	1 ¹ / ₈	1 ¹ / ₈	1 ¹ / ₈	1 ¹ / ₈
Q	5 ⁵ / ₈	7"	7 ¹ / ₂	8 ¹ / ₂	9 ⁵ / ₈	11 ¹ / ₈	12 ¹ / ₈	12 ³ / ₄	14 ¹ / ₈	15 ¹ / ₄	20"

C	Height of Riser	2 ¹ / ₂	3"	3 ¹ / ₂	4"	4 ¹ / ₂
N	7 ⁷ / ₈ to 19 ¹ / ₂ Wide Housings	3 ³ / ₈	3 ⁷ / ₈	4 ¹ / ₈	4 ³ / ₈	5 ¹ / ₈
	23 ³ / ₄ Wide Housings	3 ³ / ₈	4 ¹ / ₈	4 ³ / ₈	5 ¹ / ₈	5 ³ / ₈

W	L	C	ITEM NUMBER	NET WT.
7 ⁷ / ₈	7 ⁷ / ₈	2½	25-88	28
		3	30-88	30
		3½	35-88	33
		4	40-88	36
	11 ⁷ / ₈	4½	45-88	39
		2½	25-812	42
		3	30-812	45
		3½	35-812	50
		4	40-812	54
		4½	45-812	59
9 ⁷ / ₈	7 ⁷ / ₈	2½	25-108R	34
	8	2½	25-108	34
		3	30-108	37
		3½	35-108	41
		4	40-108	44
		4½	45-108	47
	11 ⁷ / ₈	2½	25-1012	50
		3	30-1012	55
		3½	35-1012	60
		4	40-1012	65
		4½	45-1012	70
	16	2½	25-1016	68
		3	30-1016	74
		3½	35-1016	81
		4	40-1016	87
		4½	45-1016	94
	20	2½	25-1020	84
		3	30-1020	93
3½		35-1020	101	
4		40-1020	109	
4½		45-1020	117	

W	L	C	ITEM NUMBER	NET WT.
10 ⁷ / ₈	12	2 ¹ / ₂	25-1112	58
		3	30-1112	64
		3 ¹ / ₂	35-1112	70
		4	40-1112	75
	14	4 ¹ / ₂	45-1112	81
		2 ¹ / ₂	25-1114	68
		3	30-1114	74
		3 ¹ / ₂	35-1114	81
	18	4	40-1114	88
		4 ¹ / ₂	45-1114	94
		2 ¹ / ₂	25-1118	87
		3	30-1118	95
11 ¹ / ₈	23 ¹ / ₂	3 ¹ / ₂	35-1118	104
		4	40-1118	113
		4 ¹ / ₂	45-1118	121
		2 ¹ / ₂	25-1123	113
	12	3	30-1123	124
		3 ¹ / ₂	35-1123	136
		4	40-1123	147
		4 ¹ / ₂	45-1123	158
	15	3	30-1212	67
		3 ¹ / ₂	35-1212	73
		4	40-1212	78
		4 ¹ / ₂	45-1212	84
		3	30-1215	83
		3 ¹ / ₂	35-1215	91
		4	40-1215	98
		4 ¹ / ₂	45-1215	105

W	L	C	ITEM NUMBER	NET WT.
11 ¹ / ₈ (cont.)	20	3	30-1220	111
		3 ¹ / ₂	35-1220	121
		4	40-1220	130
		4 ¹ / ₂	45-1220	140
	23 ¹ / ₂	3	30-1223	130
		3 ¹ / ₂	35-1223	142
		4	40-1223	153
		4 ¹ / ₂	45-1223	164
	15	3	30-1315	94
		3 ¹ / ₂	35-1315	102
		4	40-1315	110
		4 ¹ / ₂	45-1315	118
13 ³ / ₈	18	3	30-1318	112
		3 ¹ / ₂	35-1318	122
		4	40-1318	131
		4 ¹ / ₂	45-1318	141
	20 ³ / ₄	3	30-1321	129
		3 ¹ / ₂	35-1321	140
		4	40-1321	152
		4 ¹ / ₂	45-1321	163
	23 ¹ / ₂	3	30-1323	147
		3 ¹ / ₂	35-1323	159
		4	40-1323	172
		4 ¹ / ₂	45-1323	184
	26	3	30-1326	162
		3 ¹ / ₂	35-1326	176
		4	40-1326	190
		4 ¹ / ₂	45-1326	204


WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment

Ejector Housings 13³/₈ to 23³/₄ wide – DME No. 1 Steel

Three piece construction provides more rigid support for plastics molds or die-cast dies.

Riser height ("C" dimension) is finish ground to a tolerance of plus or minus .001". Outer surfaces are finished square and parallel.



W	L	C	ITEM NUMBER	NET WT.
13 ³ / ₈ (cont.)	29 ¹ / ₂	3	30-1329	184
		3 ¹ / ₂	35-1329	200
		4	40-1329	215
		4 ¹ / ₂	45-1329	231
14 ⁷ / ₈	17 ¹ / ₂	3	30-1518	118
		3 ¹ / ₂	35-1518	128
		4	40-1518	137
		4 ¹ / ₂	45-1518	147
	23 ³ / ₄	3	30-1524	157
		3 ¹ / ₂	35-1524	170
		4	40-1524	182
		4 ¹ / ₂	45-1524	195
	29 ¹ / ₂	3	30-1529	195
		3 ¹ / ₂	35-1529	210
		4	40-1529	226
		4 ¹ / ₂	45-1529	242
15 ⁷ / ₈	16	3	30-1616	110
		3 ¹ / ₂	35-1616	118
		4	40-1616	127
		4 ¹ / ₂	45-1616	135
	20	3	30-1620	137
		3 ¹ / ₂	35-1620	148
		4	40-1620	158
		4 ¹ / ₂	45-1620	169
	23 ¹ / ₂	3	30-1623	161
		3 ¹ / ₂	35-1623	174
		4	40-1623	186
		4 ¹ / ₂	45-1623	199
	26	3	30-1626	178
		3 ¹ / ₂	35-1626	192
		4	40-1626	206
		4 ¹ / ₂	45-1626	220

W	L	C	ITEM NUMBER	NET WT.
15 ⁵ / ₈ (cont.)	29 ¹ / ₂	3	30-1629	202
		3 ¹ / ₂	35-1629	218
		4	40-1629	233
		4 ¹ / ₂	45-1629	249
16 ¹ / ₂	35 ¹ / ₂	3	30-1635	243
		3 ¹ / ₂	35-1635	262
		4	40-1635	281
		4 ¹ / ₂	45-1635	300
	23 ³ / ₄	3	30-1724	166
		3 ¹ / ₂	35-1724	179
		4	40-1724	192
		4 ¹ / ₂	45-1724	204
	29 ¹ / ₂	3	30-1729	207
		3 ¹ / ₂	35-1729	222
		4	40-1729	238
		4 ¹ / ₂	45-1729	254
17 ¹ / ₈	18	3	30-1818	132
		3 ¹ / ₂	35-1818	142
		4	40-1818	152
		4 ¹ / ₂	45-1818	161
	20	3	30-1820	147
		3 ¹ / ₂	35-1820	158
		4	40-1820	168
		4 ¹ / ₂	45-1820	179
	23 ¹ / ₂	3	30-1823	173
		3 ¹ / ₂	35-1823	185
		4	40-1823	198
		4 ¹ / ₂	45-1823	210
	26	3	30-1826	191
		3 ¹ / ₂	35-1826	205
		4	40-1826	219
		4 ¹ / ₂	45-1826	233

W	L	C	ITEM NUMBER	NET WT.
17 ¹ / ₈ (cont.)	29 ¹ / ₂	3	30-1829	217
		3 ¹ / ₂	35-1829	232
		4	40-1829	248
		4 ¹ / ₂	45-1829	264
19 ¹ / ₂	35 ¹ / ₂	3	30-1835	261
		3 ¹ / ₂	35-1835	280
		4	40-1835	298
		4 ¹ / ₂	45-1835	317
	23 ³ / ₄	3	30-1924	184
		3 ¹ / ₂	35-1924	197
		4	40-1924	209
		4 ¹ / ₂	45-1924	222
	29 ¹ / ₂	3	30-1929	229
		3 ¹ / ₂	35-1929	244
		4	40-1929	260
		4 ¹ / ₂	45-1929	276
23 ³ / ₄	35 ¹ / ₂	3	30-1935	275
		3 ¹ / ₂	35-1935	294
		4	40-1935	313
		4 ¹ / ₂	45-1935	332
	23 ³ / ₄	3	30-2424	289
		3 ¹ / ₂	35-2424	302
		4	40-2424	314
		4 ¹ / ₂	45-2424	327
	29 ¹ / ₂	3	30-2429	359
		3 ¹ / ₂	35-2429	375
		4	40-2429	390
		4 ¹ / ₂	45-2429	406
	35 ¹ / ₂	3	30-2435	432
		3 ¹ / ₂	35-2435	451
		4	40-2435	470
		4 ¹ / ₂	45-2435	488

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment


Mold Plates, Ejector and Ejector Retainer Plates and Ejector Housings

Mold Plates

For 34 & 45R, 56 & 58N, 56 & 58U Mold Assemblies

(For cavity, support and top clamping plates).

TYPE OF STEEL	A (THICKNESS)	3½ × 3¾		4" × 5"		5" × 6"		5" × 8"	
		ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
No. 2	¾	34-3	1.4	—	—	—	—	—	—
	½	34-4	1.9	—	—	—	—	—	—
	⅜	—	—	45-5	3.5	—	—	—	—
No. 3	⅞	34-7 *	3.3	45-7 *	4.9	56-7 *	7.5	58-7 *	10.0
No. 2	1	—	—	—	—	56-8	8.5	58-8	11.4
No. 3	1½	34-11	4.2	—	—	—	—	—	—
	1%	34-13 *	5.2	45-13 *	7.8	56-13 *	11.7	58-13 *	15.6
	1½	—	—	45-17 *	10.6	56-17 *	16.0	58-17 *	21.3





Thickness of plate is finish ground to a tolerance of plus or minus .001". Width and length are finished square and parallel.

NOTE: Plates marked with a * are also available as cavity insert blocks with additional stock allowance. Please specify **mold plate** when ordering these sizes from this page.

Ejector and Ejector Retainer Plates

For 34 & 45R, 56 & 58N, 56 & 58U Mold Assemblies

A	2½ × 3½		3½ × 4"		3½ × 8"	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
⅜	6-34	.5	—	—	—	—
¾	—	—	7-45	1.3	7-58	2.7
½	—	—	6-45	1.8	6-58	3.6



DME NO. 1
STEEL (EXCEPT
6-34 = SAE 1020)

EJECTOR PLATES



Thickness of plate is finish ground to a tolerance of plus or minus .001".

EJECTOR RETAINER PLATES

Thickness of plate is rotary ground to a tolerance of plus .015", minus .000".

Ejector Housings

For 34 & 45R, 56 & 58N, 56 & 58U Mold Assemblies



DME NO. 1 STEEL

W	L	C	T OR SUPPORT PLATE	N	P	Q	ITEM NUMBER	No. 1 STEEL	No. 3 STEEL	NET WT.
3¾	3½	1.080	½	1.580	⅞	2%	10-34	●	—	3.1
5	4	2	½	2½	⅞	3¾	20-45	●	—	6.8
	6	1½	1¼	2%	⅞	3¾	15-56	●	●	15.5
	8	1½	1¼	2%	⅞	3¾	15-58	●	●	20.7
7	6	2	½	2½	1⅞	5½	20-67	●	—	12.4

Ejector Housings for small-size Mold Bases are one-piece construction which provides more rigid support with fewer parts. All surfaces are machined square and parallel. The riser height is finish ground parallel to the surface of the base plate.

Die Blocks and Plates


7⁷/₈ through 13³/₈ wide – No. 5 Steel

DME No. 5 steel is a thermal shock resistant, hotwork die steel (AISI-SAE H-13 type). Supplied fully annealed (approx. 200 Bhn) for easy machinability, it can be subsequently heat treated to the desired hardness with a minimum of deformation.

Mainly used for die cast dies, it is also suitable for plastics molds with exceptional hardness or polishability requirements.

DME No. 5 Steel meets or exceeds the acceptance criteria established by the NADCA as detailed in Technical Digest Number 01-80-01D.

Thickness, width and length are milled to approximately .060" oversized (.030" per side).



A	7 ⁷ / ₈ × 7 ⁷ / ₈	
	ITEM NUMBER	NET WT.
1 ¹ / ₈	88-13	25
1 ¹ / ₈	88-17	33
2 ¹ / ₈	88-23	42
2 ¹ / ₈	88-27	51
3 ¹ / ₈	88-33	60
3 ¹ / ₈	88-37	69
4 ¹ / ₈	88-47	86

A	9 ⁷ / ₈ × 8"		9 ⁷ / ₈ × 11 ⁷ / ₈		9 ⁷ / ₈ × 16"		9 ⁷ / ₈ × 20"		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
1 ¹ / ₈	108-13	31	1012-13	46	1016-13	62	1020-13	77	1 ¹ / ₈
1 ¹ / ₈	108-17	42	1012-17	63	1016-17	84	1020-17	105	1 ¹ / ₈
2 ¹ / ₈	108-23	54	1012-23	79	1016-23	107	1020-23	133	2 ¹ / ₈
2 ¹ / ₈	108-27	65	1012-27	96	1016-27	129	1020-27	161	2 ¹ / ₈
3 ¹ / ₈	108-33	76	1012-33	113	1016-33	152	1020-33	189	3 ¹ / ₈
3 ¹ / ₈	108-37	87	1012-37	129	1016-37	174	1020-37	217	3 ¹ / ₈
4 ¹ / ₈	108-47	110	1012-47	162	1016-47	219	1020-47	273	4 ¹ / ₈
5 ¹ / ₈	108-57	132	1012-57	196	1016-57	263	1020-57	329	5 ¹ / ₈

A	10 ⁷ / ₈ × 12"		10 ⁷ / ₈ × 14"		10 ⁷ / ₈ × 18"		10 ⁷ / ₈ × 23 ¹ / ₂ "	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
1 ¹ / ₈	1112-13	51	1114-13	60	1118-13	77	1123-13	100
1 ¹ / ₈	1112-17	70	1114-17	81	1118-17	104	1123-17	136
2 ¹ / ₈	1112-23	88	1114-23	103	1118-23	132	1123-23	172
2 ¹ / ₈	1112-27	107	1114-27	125	1118-27	160	1123-27	209
3 ¹ / ₈	1112-33	125	1114-33	146	1118-33	188	1123-33	245
3 ¹ / ₈	1112-37	144	1114-37	168	1118-37	215	1123-37	281
4 ¹ / ₈	1112-47	181	1114-47	211	1118-47	271	1123-47	353
5 ¹ / ₈	1112-57	218	1114-57	254	1118-57	326	1123-57	426

A	11 ⁷ / ₈ × 12"		11 ⁷ / ₈ × 15"	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
1 ¹ / ₈	1212-13	56	1215-13	70
1 ¹ / ₈	1212-17	76	1215-17	95
2 ¹ / ₈	1212-23	96	1215-23	120
2 ¹ / ₈	1212-27	117	1215-27	146
3 ¹ / ₈	1212-33	137	1215-33	171
3 ¹ / ₈	1212-37	157	1215-37	196
4 ¹ / ₈	1212-47	197	1215-47	247
5 ¹ / ₈	1212-57	238	1215-57	297
7 ¹ / ₈	1212-77	318	1215-77	398

A	11 ⁷ / ₈ × 20"		11 ⁷ / ₈ × 23 ¹ / ₂ "	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
1 ¹ / ₈	1220-13	93	1223-13	109
1 ¹ / ₈	1220-17	127	1223-17	149
2 ¹ / ₈	1220-23	160	1223-23	188
2 ¹ / ₈	1220-27	194	1223-27	228
3 ¹ / ₈	1220-33	228	1223-33	267
3 ¹ / ₈	1220-37	261	1223-37	307
4 ¹ / ₈	1220-47	329	1223-47	386
5 ¹ / ₈	1220-57	396	1223-57	465
7 ¹ / ₈	1220-77	530	1223-77	623

A	13 ³ / ₈ × 15"		13 ³ / ₈ × 18"		13 ³ / ₈ × 20 ³ / ₄ "		13 ³ / ₈ × 23 ¹ / ₂ "	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
1 ¹ / ₈	1315-13	79	1318-13	94	1321-13	109	1323-13	123
1 ¹ / ₈	1315-17	107	1318-17	128	1321-17	148	1323-17	167
2 ¹ / ₈	1315-23	135	1318-23	162	1321-23	187	1323-23	212
2 ¹ / ₈	1315-27	164	1318-27	197	1321-27	227	1323-27	257
3 ¹ / ₈	1315-33	192	1318-33	231	1321-33	266	1323-33	301
3 ¹ / ₈	1315-37	221	1318-37	265	1321-37	305	1323-37	346
4 ¹ / ₈	1315-47	278	1318-47	333	1321-47	384	1323-47	435
5 ¹ / ₈	1315-57	334	1318-57	401	1321-57	462	1323-57	524
7 ¹ / ₈	1315-77	448	1318-77	538	1321-77	620	1323-77	702

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 5 Steel
- Method of Shipment

ALSO AVAILABLE:

- Rotary ground/milled thickness
- Finish ground thickness and/or edges
- Standard width and thickness up to 12 feet long. For prices, contact DME.


SPECIAL ORDER SIZES: Please contact DME.

Die Blocks and Plates

15⁷/₈ through 23³/₄ wide – No. 5 Steel


ALL DIE BLOCKS & PLATES ARE SPECIAL ORDER: Please contact DME.

A	15 ⁷ / ₈ × 16"		15 ⁷ / ₈ × 20"		15 ⁷ / ₈ × 23 ¹ / ₂ "		15 ⁷ / ₈ × 26"	
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
1 ³ / ₈	1616-13	99	1620-13	124	1623-13	146	1626-13	161
1 ⁷ / ₈	1616-17	135	1620-17	169	1623-17	199	1626-17	220
2 ¹ / ₈	1616-23	171	1620-23	214	1623-23	252	1626-23	278
2 ⁷ / ₈	1616-27	207	1620-27	259	1623-27	304	1626-27	337
3 ¹ / ₈	1616-33	243	1620-33	304	1623-33	357	1626-33	395
3 ⁷ / ₈	1616-37	279	1620-37	349	1623-37	410	1626-37	454
4 ¹ / ₈	1616-47	351	1620-47	439	1623-47	516	1626-47	571
5 ¹ / ₈	1616-57	423	1620-57	529	1623-57	621	1626-57	687
7 ¹ / ₈	1616-77	567	1620-77	709	1623-77	833	1626-77	921
8 ¹ / ₈	1616-87	639	1620-87	799	1623-87	938	1626-87	1038
9 ¹ / ₈	1616-97	711	1620-97	889	1623-97	1044	1626-97	1155
11 ¹ / ₈	1616-117	855	1620-117	1069	1623-117	1256	1626-117	1389



A	17 ⁷ / ₈ × 18"		17 ⁷ / ₈ × 20"		17 ⁷ / ₈ × 23 ¹ / ₂ "		17 ⁷ / ₈ × 26"		17 ⁷ / ₈ × 29 ¹ / ₂ "		17 ⁷ / ₈ × 35 ¹ / ₂ "		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
1 ³ / ₈	1818-17	171	1820-17	190	1823-17	224	1826-17	247	1829-17	281	1835-17	338	1 ³ / ₈
2 ¹ / ₈	1818-23	217	1820-23	241	1823-23	283	1826-23	313	1829-23	355	1835-23	427	2 ¹ / ₈
2 ⁷ / ₈	1818-27	263	1820-27	292	1823-27	343	1826-27	379	1829-27	430	1835-27	517	2 ⁷ / ₈
3 ¹ / ₈	1818-33	308	1820-33	342	1823-33	402	1826-33	445	1829-33	505	1835-33	607	3 ¹ / ₈
3 ⁷ / ₈	1818-37	354	1820-37	393	1823-37	462	1826-37	511	1829-37	579	1835-37	697	3 ⁷ / ₈
4 ¹ / ₈	1818-47	445	1820-47	494	1823-47	581	1826-47	642	1829-47	729	1835-47	877	4 ¹ / ₈
5 ¹ / ₈	1818-57	536	1820-57	596	1823-57	700	1826-57	774	1829-57	878	1835-57	1057	5 ¹ / ₈
7 ¹ / ₈	1818-77	718	1820-77	798	1823-77	938	1826-77	1037	1829-77	1177	1835-77	1416	7 ¹ / ₈
8 ¹ / ₈	1818-87	809	1820-87	899	1823-87	1057	1826-87	1169	1829-87	1326	1835-87	1596	8 ¹ / ₈
9 ¹ / ₈	1818-97	901	1820-97	1001	1823-97	1176	1826-97	1301	1829-97	1476	1835-97	1776	9 ¹ / ₈
11 ¹ / ₈	1818-117	1083	1820-117	1203	1823-117	1414	1826-117	1564	1829-117	1774	1835-117	2135	11 ¹ / ₈

A	19 ¹ / ₂ × 23 ³ / ₄ "		A	23 ³ / ₄ × 23 ³ / ₄ "		23 ³ / ₄ × 29 ¹ / ₂ "		23 ³ / ₄ × 35 ¹ / ₂ "	
	ITEM NUMBER	NET WT.		ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.
2 ¹ / ₈	1924-23	312	2 ¹ / ₈	2424-23	380	2429-23	472	2435-23	568
2 ⁷ / ₈	1924-27	378	2 ⁷ / ₈	2424-27	460	2429-27	571	2435-27	687
3 ¹ / ₈	1924-33	443	3 ¹ / ₈	2424-33	540	2429-33	670	2435-33	807
3 ⁷ / ₈	1924-37	509	3 ⁷ / ₈	2424-37	620	2429-37	770	2435-37	926
4 ¹ / ₈	1924-47	640	4 ¹ / ₈	2424-47	780	2429-47	968	2435-47	1165
5 ¹ / ₈	1924-57	771	5 ¹ / ₈	2424-57	939	2429-57	1167	2435-57	1404
7 ¹ / ₈	1924-77	1034	7 ¹ / ₈	2424-77	1259	2429-77	1564	2435-77	1882
8 ¹ / ₈	1924-87	1165	8 ¹ / ₈	2424-87	1419	2429-87	1762	2435-87	2120
9 ¹ / ₈	1924-97	1296	9 ¹ / ₈	2424-97	1579	2429-97	1961	2435-97	2359
11 ¹ / ₈	1924-117	1559	11 ¹ / ₈	2424-117	1898	2429-117	2358	2435-117	2837



Thickness, width and length are milled to approximately .060" oversized (.030" per side).

WHEN ORDERING, PLEASE SPECIFY:


1. Quantity & Item Number
2. No. 5 Steel
3. Method of Shipment

ALSO AVAILABLE:

1. Rotary ground thickness
2. Finish ground thickness and/or edges
3. Standard width and thickness up to 12 feet long. For prices, contact DME.

DME Standard Cavity Insert Blocks – 3", 4", 5" and 6" Series

Thickness, width and length are finished square and parallel .015" to .020" oversized (.0075" to .010" per side) to permit either fitting at assembly (No. 3 Steel) or finish grinding after heat treatment (No. 5 Steel, No. 6 Steel and AISI S-7 Steel).



A	3" (W) × 3" (L)					3" (W) × 4" (L)					3" (W) × 5" (L)					3" (W) × 6" (L)					3" (W) × 8" (L)					
	ITEM NO.	MATERIAL			NET WT.	ITEM NO.	MATERIAL			NET WT.	ITEM NO.	MATERIAL			NET WT.	ITEM NO.	MATERIAL			NET WT.	ITEM NO.	MATERIAL			NET WT.	
		NO. 3	NO. 5	S-7			NO. 3	NO. 5	S-7			NO. 3	NO. 5	S-7			NO. 3	NO. 6	NO. 5			S-7	NO. 3	NO. 5		S-7
¾	33-7	—	•	•	2.2	34-7	••	•	•	2.0	35-7	•	•	•	3.7	36-7	•	•	•	•	4.5	38-7	•	•	•	5.9
1⅓	33-13	•	•	•	3.5	34-13	••	•	•	4.7	35-13	•	•	•	5.8	36-13	•	•	•	•	7.0	38-13	•	•	•	9.3
1⅞	33-17	•	•	•	4.4	34-17	•	•	•	6.4	35-17	•	•	•	8.0	36-17	•	—	—	—	9.6	38-17	•	•	•	12.7
2⅝	33-23	•	•	•	6.1	34-23	—	•	•	8.1	35-23	•	•	•	10.1	36-23	•	•	•	•	12.1	—	—	—	—	—
2⅞	—	—	—	—	—	—	—	—	—	—	35-27	—	•	•	12.2	—	—	—	—	—	—	—	—	—	—	—
3⅝	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	36-33	•	—	—	—	17.2	38-33	—	•	•	22.9



A	4" (W) × 4" (L)					4" (W) × 5" (L)					4" (W) × 6" (L)					4" (W) × 8" (L)						
	ITEM NO.	MATERIAL				NET WT.	ITEM NO.	MATERIAL				NET WT.	ITEM NO.	MATERIAL				NET WT.				
		NO. 3	NO. 6	NO. 5	S-7			NO. 3	NO. 5	S-7	NO. 3			NO. 5	S-7	NO. 3	NO. 6		NO. 5	S-7		
3/8"	44-7	•	•	•	•	4.0	45-7	••	•	•	5.0	46-7	•	•	•	5.9	48-7	•	•	—	—	7.9
1/2"	44-13	•	•	•	•	6.2	45-13	••	•	•	7.8	46-13	•	•	•	9.3	48-13	•	•	•	•	12.5
1"	44-17	•	•	•	•	8.5	45-17	••	•	•	10.6	46-17	•	•	•	12.7	48-17	•	•	•	•	17.0
2 3/8"	44-23	•	—	•	•	10.8	45-23	•	•	•	13.5	46-23	•	•	•	16.1	48-23	•	•	—	—	21.5

A	5" (W) × 5" (L)					5" (W) × 6" (L)					5" (W) × 8" (L)				
	ITEM NO.	MATERIAL			NET WT.	ITEM NO.	MATERIAL			NET WT.	ITEM NO.	MATERIAL			NET WT.
		NO. 3	NO. 5	S-7			NO. 3	NO. 5	S-7			NO. 3	NO. 5	S-7	
7/8	55-7	•	•	•	6.2	56-7	••	•	•	7.4	58-7	••	•	•	9.9
1 1/8	55-13	•	•	•	9.7	56-13	••	•	•	11.7	58-13	••	•	•	15.6
1 1/2	55-17	•	•	•	13.3	56-17	••	•	•	15.9	58-17	••	•	•	21.2
2 1/8	55-23	•	—	—	16.8	56-23	•	•	•	20.2	58-23	•	—	—	26.9
2 1/2	—	—	—	—	—	56-27	—	•	•	24.4	58-27	•	—	—	32.6
3 1/8	—	—	—	—	—	56-33	—	—	—	28.7	—	—	—	—	—

A	6" (W) × 6" (L)						6" (W) × 8" (L)					
	ITEM NO.	MATERIAL				NET WT.	ITEM NO.	MATERIAL				NET WT.
		NO. 3	NO. 6	NO. 5	S-7			NO. 3	NO. 5	S-7		
¾	66-7	•	•	•	•	8.9	68-7	•	•	•	11.4	
1⅓	66-13	•	•	•	•	14.0	68-13	•	•	•	18.7	
1½	66-17	•	•	•	•	19.1	68-17	•	•	•	25.5	
2⅝	66-23	•	—	•	•	24.2	68-23	•	—	—	32.3	
2½	66-27	•	—	•	•	29.3	68-27	•	—	—	39.1	
3⅝	—	—	—	—	—	—	68-33	•	•	•	45.9	
3½	—	—	—	—	—	—	68-37	•	—	—	52.7	

AVAILABLE STANDARD

DME No. 3 Steel

DME No. 3 Steel is a P-20 AISI 4130 (modified) type cavity steel, pre-heat treated to 277-331 Bhn. Exceptionally clean, it provides high hardness, good machinability and exceptional polishability for both plastics molds and die cast dies.

NOTE: Sizes above marked with a double dot (••) are also available as finish ground mold plates (see previous section). Please specify **insert block** when ordering these sizes from this page.

AVAILABLE BY SPECIAL ORDER

DME No. 5 Steel

DME No. 5 Steel is a thermal shock resistant, hotwork die steel (AISI-SAE H-13 type). Supplied fully annealed (approx. 200 Bhn) for easy machinability, it can be subsequently heat treated to the desired hardness with a minimum of deformation. Mainly used for die cast dies, it is also suitable for plastics molds with exceptional hardness or polishability requirements.

DME No. 5 Steel meets or exceeds the acceptance criteria established by the NADCA as detailed in Technical Digest Number 01-80-01D.

DME No. 6 Steel

DME No. 6 Steel is a T-420 type stainless steel. It is supplied fully annealed to 220 Bhn (200-240), making it readily machinable. It can be used for injection, compression or transfer molds where the properties of the plastics materials or excessive condensation require a highly corrosion-resistant cavity steel.

DME AISI S-7 Steel (NOTE: AISI S-7 Steel is not a stainless steel and is not related to DME No. 7 Steel.)

DME S-7 Steel is supplied fully annealed to 225 Bhn maximum. This shock resisting tool steel combines toughness and wear resistance along with ease of machining and heat treatment. S-7 can be used for both hot and cold work applications as a result of its combination of properties. Due to the unique mold quality composition, minimal distortion occurs during the heat treating process. DME Mold Quality S-7 is selectively melted for improved cleanliness and excellent polishability. Follow standard procedures for heat treating AISI S-7 Steel. Double tempering is recommended.

WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 3 Steel, No. 5 Steel, No. 6 Steel, or AISI S-7 Steel
- Method of Shipment

*NOTE:

Net weight is specified for DME No. 3 Steel, No. 5 Steel, No. 6 Steel, and AISI S-7.

AVAILABLE STANDARD IN: No. 3 Steel.

AVAILABLE AS A SPECIAL ORDER IN: No. 5, No 6 Steel and AISI S-7

Large Custom Mold Plates

Precision Machined Custom Mold Plates with Lengths to 90"

Manufacturing Capabilities

- Plate lengths up to 90" (2300mm)
- Plate widths up to 60" (1500mm)
- Plate thicknesses up to 39" (1000mm)
- Plate weights up to 6,600 pounds (3000kg) after machining
– 8600 lbs. (3900kg) before machining
- Proven medical/package market specialization;
also specialize in automotive, caps & closures,
housewares and PET preform applications

Special Machining Plate Work

- Custom mold bases (especially for high cavitation)
- Mold plates, frames and other components
- Clamping plates, cavity plates, etc.
- Hot runner manifold plates
- Parting line plates
- Insulator plates, rails, etc.



Steel Material Options

- Precise machining of all alloy tool steels
 - DME #7 stainless steel (1.2085)
 - DME #3 P-20 modified steel (1.2312)
 - DME #1 steel (1.1730)
 - DME #5 H-13 hot work die steel (1.2343)
 - DME #2 steel (1.2312)
 - DME #6 stainless steel (1.4028)
 - EDRO RoyAlloy
 - Many other types
(including customer provided)



- Fully machined custom mold bases, plates and frames for high cavitation injection mold tools, die casting and press tools
- Custom manifolds for hot runner systems
- Mold base/plate assembly (bushings, pins, pillars, etc.)
- All finishing operations executed in climate-controlled areas
- Manufacturing capacity of 300 fully machined mold plates per month
- All plates 3D-measured and delivered with measurement report

Large Mold Plates 26³/₄ through 33³/₄ wide



ALL LARGE MOLD PLATES ARE SPECIAL ORDER: Please contact DME.

A	26 ³ / ₄ × 30"		26 ³ / ₄ × 36"		26 ³ / ₄ × 42"		26 ³ / ₄ × 48"		26 ³ / ₄ × 54"		29 ³ / ₄ × 30"		29 ³ / ₄ × 36"		29 ³ / ₄ × 42"		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
1 ³ / ₈	2730-13	313	2736-13	376	2742-13	438	2748-13	501	2754-13	563	3030-13	348	3036-13	418	3042-13	487	1 ³ / ₈
1 ¹ / ₂	2730-17	427	2736-17	512	2742-17	597	2748-17	683	2754-17	768	3030-17	475	3036-17	569	3042-17	664	1 ¹ / ₂
2 ¹ / ₈	2730-27	654	2736-27	785	2742-27	916	2748-27	1046	2754-27	1177	3030-27	727	3036-27	873	3042-27	1018	2 ¹ / ₈
3 ¹ / ₈	2730-37	881	2736-37	1058	2742-37	1234	2748-37	1410	2754-37	1586	3030-37	980	3036-37	1176	3042-37	1372	3 ¹ / ₈
4 ¹ / ₈	2730-47	1109	2736-47	1330	2742-47	1552	2748-47	1774	2754-47	1995	3030-47	1233	3036-47	1480	3042-47	1726	4 ¹ / ₈
5 ¹ / ₈	2730-57	1336	2736-57	1603	2742-57	1870	2748-57	2138	2754-57	2405	3030-57	1486	3036-57	1783	3042-57	2080	5 ¹ / ₈

A	29 ³ / ₄ × 48"		29 ³ / ₄ × 54"		33 ³ / ₄ × 36"		33 ³ / ₄ × 42"		33 ³ / ₄ × 48"		33 ³ / ₄ × 54"		33 ³ / ₄ × 60"		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
1 ³ / ₈	3048-13	557	3054-13	626	3436-13	474	3442-13	553	3448-13	632	3454-13	710	3460-13	789	1 ³ / ₈
1 ¹ / ₂	3048-17	759	3054-17	854	3436-17	646	3442-17	753	3448-17	861	3454-17	969	3460-17	1076	1 ¹ / ₂
2 ¹ / ₈	3048-27	1164	3054-27	1309	3436-27	990	3442-27	1155	3448-27	1320	3454-27	1485	3460-27	1650	2 ¹ / ₈
3 ¹ / ₈	3048-37	1568	3054-37	1764	3436-37	1334	3442-37	1557	3448-37	1779	3454-37	2001	3460-37	2224	3 ¹ / ₈
4 ¹ / ₈	3048-47	1973	3054-47	2219	3436-47	1679	3442-47	1958	3448-47	2238	3454-47	2518	3460-47	2797	4 ¹ / ₈
5 ¹ / ₈	3048-57	2377	3054-57	2674	3436-57	2023	3442-57	2360	3448-57	2697	3454-57	3034	3460-57	3371	5 ¹ / ₈

Thickness of plate is rotary ground/milled to a tolerance of plus .010", minus .000". Width and length are machined square and parallel to a tolerance of +.015/+0.020.

DME No. 1 Steel

DME No. 1 steel is a medium carbon (SAE 1030), silicon-killed forging quality steel with approximately 25% greater tensile strength than typical low-carbon warehouse steels.

DME No. 3 Steel

DME No. 3 steel is a P-20 AISI 4130 (modified) type cavity steel, pre-heat treated to 28-34 HRC (271-321 Bhn). It provides high hardness, good machinability and exceptional polishability for both plastics molds and die cast dies.



WHEN ORDERING, PLEASE SPECIFY:

- Quantity & Item Number
- No. 1, No. 3 Steel
- Method of Shipment

NOTE:

Other sizes and materials are available by special order.

Large Mold Plates 37³/₄ through 45³/₄ wide



ALL LARGE MOLD PLATES ARE SPECIAL ORDER: Please contact DME.

A	37 ³ / ₄ × 42"		37 ³ / ₄ × 48"		37 ³ / ₄ × 54"		37 ³ / ₄ × 60"		37 ³ / ₄ × 66"		41 ³ / ₄ × 42"		41 ³ / ₄ × 48"		41 ³ / ₄ × 54"		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
1 ³ / ₈	3842-13	618	3848-13	706	3854-13	795	3860-13	883	3866-13	971	4242-13	684	4248-13	781	4254-13	879	1 ³ / ₈
1 ⁷ / ₈	3842-17	843	3848-17	963	3854-17	1083	3860-17	1204	3866-17	1324	4242-17	932	4248-17	1065	4254-17	1198	1 ⁷ / ₈
2 ⁷ / ₈	3842-27	1292	3848-27	1476	3854-27	1661	3860-27	1845	3866-27	2030	4242-27	1429	4248-27	1633	4254-27	1837	2 ⁷ / ₈
3 ⁷ / ₈	3842-37	1741	3848-37	1990	3854-37	2238	3860-37	2487	3866-37	2736	4242-37	1925	4248-37	2200	4254-37	2475	3 ⁷ / ₈
4 ⁷ / ₈	3842-47	2190	3848-47	2503	3854-47	2816	3860-47	3129	3866-47	3441	4242-47	2422	4248-47	2768	4254-47	3114	4 ⁷ / ₈
5 ⁷ / ₈	3842-57	2639	3848-57	3016	3854-57	3393	3860-57	3770	3866-57	4147	4242-57	2919	4248-57	3336	4254-57	3753	5 ⁷ / ₈

A	41 ³ / ₄ × 60"		41 ³ / ₄ × 66"		45 ³ / ₄ × 48"		45 ³ / ₄ × 54"		45 ³ / ₄ × 60"		45 ³ / ₄ × 66"		A
	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	ITEM NUMBER	NET WT.	
1 ³ / ₈	4260-13	976	4266-13	1074	4648-13	856	4654-13	963	4660-13	1070	4666-13	1177	1 ³ / ₈
1 ⁷ / ₈	4260-17	1331	4266-17	1464	4648-17	1167	4654-17	1313	4660-17	1459	4666-17	1604	1 ⁷ / ₈
2 ⁷ / ₈	4260-27	2041	4266-27	2245	4648-27	1789	4654-27	2013	4660-27	2236	4666-27	2460	2 ⁷ / ₈
3 ⁷ / ₈	4260-37	2750	4266-37	3025	4648-37	2411	4654-37	2713	4660-37	3014	4666-37	3315	3 ⁷ / ₈
4 ⁷ / ₈	4260-47	3806	4266-47	3460	4648-47	3033	4654-47	3412	4660-47	3792	4666-47	4171	4 ⁷ / ₈
5 ⁷ / ₈	4260-57	4170	4266-57	4587	4648-57	3655	4654-57	4112	4660-57	4569	4666-57	5026	5 ⁷ / ₈

Thickness of plate is rotary ground/milled to a tolerance of plus .010", minus .000". Width and length are machined square and parallel to a tolerance of plus +.015/+ .020.

DME No. 1 Steel

DME No. 1 steel is a medium carbon (SAE 1030), silicon-killed forging quality steel with approximately 25% greater tensile strength than typical low-carbon warehouse steels.

DME No. 3 Steel

DME No. 3 steel is a P-20 AISI 4130 (modified) type cavity steel, pre-heat treated to 28-34 HRC (271-321 Bhn). It provides high hardness, good machinability and exceptional polishability for both plastics molds and die cast dies.


WHEN ORDERING, PLEASE SPECIFY:

1. Quantity & Item Number
2. No. 1, No. 3 Steel
3. Method of Shipment

NOTE:

Other sizes and materials are available by special order.

Ejector Plates and Ejector Retainer Plates for Large Mold Assemblies – DME No. 1 Steel



Thickness of plate is rotary ground/milled to a tolerance of plus .010", minus .000". Width and length are machined square and parallel to a tolerance of plus .020", minus .000".

ALL LARGE MOLD PLATES ARE SPECIAL ORDER: Please contact DME.

T-1/T-2	M	L	ITEM NUMBER	NET WT.
7/8	20 3/4	30	7-2130-7	155
		36	7-2136-7	186
		42	7-2142-7	217
		48	7-2148-7	247
		54	7-2154-7	278
	22 3/4	30	7-2330-7	170
		36	7-2336-7	204
		42	7-2342-7	237
		48	7-2348-7	271
		54	7-2354-7	305
	23 3/4	30	7-2430-7	177
		36	7-2436-7	212
		42	7-2442-7	248
		48	7-2448-7	283
		54	7-2454-7	318
	25 3/4	60	7-2460-7	354
		30	7-2630-7	192
		36	7-2636-7	230
		42	7-2642-7	269
		48	7-2648-7	307
	27 3/4	54	7-2654-7	345
		60	7-2660-7	383
		36	7-2836-7	248
		42	7-2842-7	289
		48	7-2848-7	331
	29 3/4	54	7-2854-7	372
		60	7-2860-7	413
		66	7-2866-7	454
		36	7-3036-7	266
		42	7-3042-7	310
	31 3/4	48	7-3048-7	354
		54	7-3054-7	399
		60	7-3060-7	443
		66	7-3066-7	487
		42	7-3242-7	331
	33 3/4	48	7-3248-7	378
		54	7-3254-7	425
		60	7-3260-7	473
		66	7-3266-7	520
		42	7-3442-7	352
	35 3/4	48	7-3448-7	402
		54	7-3454-7	452
		60	7-3460-7	502
		66	7-3466-7	553
		42	7-3642-7	373
	37 3/4	48	7-3648-7	426
		54	7-3654-7	479
		60	7-3660-7	532
		66	7-3666-7	585
		42	7-3842-7	394
	39 3/4	48	7-3848-7	450
		54	7-3854-7	506
		60	7-3860-7	562
		66	7-3866-7	618
		48	7-4048-7	473
	39 3/4	54	7-4054-7	533
		66	7-4060-7	592
		66	7-4066-7	651

T-1/T-2	M	L	ITEM NUMBER	NET WT.
1 3/8	20 3/4	30	6-2130-13	243
		36	6-2136-13	291
		42	6-2142-13	340
		48	6-2148-13	388
		54	6-2154-13	437
	22 3/4	30	6-2330-13	266
		36	6-2336-13	320
		42	6-2342-13	373
		48	6-2348-13	426
		54	6-2354-13	479
	23 3/4	30	6-2430-13	278
		36	6-2436-13	334
		42	6-2442-13	389
		48	6-2448-13	445
		54	6-2454-13	500
	25 3/4	60	6-2460-13	556
		30	6-2630-13	301
		36	6-2636-13	362
		42	6-2642-13	422
		48	6-2648-13	482
	27 3/4	54	6-2654-13	542
		60	6-2660-13	602
		36	6-2836-13	390
		42	6-2842-13	454
		48	6-2848-13	519
	29 3/4	54	6-2854-13	584
		60	6-2860-13	649
		66	6-2866-13	714
		36	6-3036-13	478
		42	6-3042-13	487
	31 3/4	48	6-3048-13	557
		54	6-3054-13	626
		60	6-3060-13	696
		66	6-3066-13	765
		42	6-3242-13	520
	33 3/4	48	6-3248-13	594
		54	6-3254-13	668
		60	6-3260-13	743
		66	6-3266-13	817
		42	6-3442-13	553
	35 3/4	48	6-3448-13	632
		54	6-3454-13	710
		60	6-3460-13	789
		66	6-3466-13	868
		42	6-3642-13	585
	37 3/4	48	6-3648-13	669
		54	6-3654-13	752
		60	6-3660-13	836
		66	6-3666-13	920
		42	6-3842-13	618
	39 3/4	48	6-3848-13	706
		54	6-3854-13	795
		60	6-3860-13	883
		66	6-3866-13	971
		48	6-4048-13	744
	39 3/4	54	6-4054-13	837
		66	6-4060-13	930
		66	6-4066-13	1022


T-1/T-2	M	L	ITEM NUMBER	NET WT.
1 7/8	20 3/4	30	6-2130-17	331
		36	6-2136-17	397
		42	6-2142-17	463
		48	6-2148-17	530
		54	6-2154-17	596
	22 3/4	30	6-2330-17	363
		36	6-2336-17	436
		42	6-2342-17	508
		48	6-2348-17	581
		54	6-2354-17	653
	23 3/4	30	6-2430-17	379
		36	6-2436-17	455
		42	6-2442-17	530
		48	6-2448-17	606
		54	6-2454-17	682
	25 3/4	60	6-2460-17	757
		30	6-2630-17	411
		36	6-2636-17	493
		42	6-2642-17	575
		48	6-2648-17	657
	27 3/4	54	6-2654-17	739
		60	6-2660-17	821
		36	6-2836-17	531
		42	6-2842-17	620
		48	6-2848-17	708
	29 3/4	54	6-2854-17	796
		60	6-2860-17	885
		66	6-2866-17	973
		36	6-3036-17	569
		42	6-3042-17	664
	31 3/4	48	6-3048-17	759
		54	6-3054-17	854
		60	6-3060-17	949
		66	6-3066-17	1043
		42	6-3242-17	709
	33 3/4	48	6-3248-17	810
		54	6-3254-17	911
		60	6-3260-17	1012
		66	6-3266-17	1114
		42	6-3442-17	753
	35 3/4	48	6-3448-17	861
		54	6-3454-17	969
		60	6-3460-17	1076
		66	6-3466-17	1184
		42	6-3642-17	798
	37 3/4	48	6-3648-17	912
		54	6-3654-17	1026
		60	6-3660-17	1140
		66	6-3666-17	1254
		42	6-3842-17	843
	39 3/4	48	6-3848-17	963
		54	6-3854-17	1083
		60	6-3860-17	1204
		66	6-3866-17	1324
		48	6-4048-17	1014
	39 3/4	54	6-4054-17	1141
		66	6-4060-17	1267
		66	6-4066-17	1394

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment

Spacer Blocks for Large Mold Assemblies

DME No. 1 Steel



Machined all over. Riser heights ("C" dimension) are finish ground to a tolerance of plus or minus .001".

ALL LARGE MOLD SPACER BLOCKS ARE SPECIAL ORDER: Please contact DME.

P	C	L	ITEM NUMBER	NET WT.
1⁷/₈	5	30	50-1730	80
		36	50-1736	96
		42	50-1742	112
		48	50-1748	128
		54	50-1754	144
		60	50-1760	160
		66	50-1766	176
	6	30	60-1730	96
		36	60-1736	115
		42	60-1742	134
		48	60-1748	153
		54	60-1754	173
		60	60-1760	192
		66	60-1766	211
	8	30	80-1730	128
		36	80-1736	153
		42	80-1742	179
		48	80-1748	204
		54	80-1754	230
		60	80-1760	255
		66	80-1766	281

P	C	L	ITEM NUMBER	NET WT.
2⁷/₈	5	30	50-2730	123
		36	50-2736	147
		42	50-2742	172
		48	50-2748	196
		54	50-2754	220
		60	50-2760	245
		66	50-2766	269
	6	30	60-2730	147
		36	60-2736	176
		42	60-2742	206
		48	60-2748	235
		54	60-2754	264
		60	60-2760	294
		66	60-2766	323
	8	30	80-2730	196
		36	80-2736	235
		42	80-2742	274
		48	80-2748	313
		54	80-2754	352
		60	80-2760	391
		66	80-2766	431

P	C	L	ITEM NUMBER	NET WT.
3⁷/₈	5	—	—	—
		36	50-3736	198
		42	50-3742	231
		48	50-3748	264
		54	50-3754	297
		60	50-3760	330
		66	50-3766	363
	6	—	—	—
		36	60-3736	238
		42	60-3742	277
		48	60-3748	317
		54	60-3754	356
		60	60-3760	396
		66	60-3766	435
	8	—	—	—
		36	80-3736	317
		42	80-3742	369
		48	80-3748	422
		54	80-3754	475
		60	80-3760	527
		66	80-3766	580

WHEN ORDERING, PLEASE SPECIFY:

1. Quantity
2. Item Number
3. Method of Shipment

Steel Processing Services to meet your Special Requirements



DME Company has been buying, cutting, machining and finishing high-quality steel for eight decades. We understand that our customers face unprecedented demands for speed, cost reduction and performance. To assist you in meeting your challenges, we've developed an industry-leading steel processing infrastructure, including the specialized equipment and technical expertise to handle the most demanding steel requirements. It's a unique capability that's just one way DME strives to be an essential resource to the customers we serve.

DME's North American manufacturing locations have some of the largest, most modern sawing, straightening, milling and grinding equipment in the industry. As one of the world's largest users of alloy steel plate, DME has a close working relationship with the leading steel mills. This provides you with the ability to meet whatever special steel requirements you may have by working with us. Steel plates and blocks of any size and grade of steel are available from DME.

Any specified steel condition – rough, semi-finished or finished (milled or ground) is available to order. Even specially machined large blocks and plates are available.

Steel Plate

Let DME quote your machining requirements for steel plate.

As a convenient, one-stop solution, DME can reduce your overall costs whether your needs only require plate machining, or drilling, tapping, boring, and milling, as well. DME prides itself on providing highly competent technical support and highly responsive customer service. We specialize in supplying the steel product that meets your exact specification.

Steel Processing Services

DME's steel processing services for moldmakers and die casters provide a full array of steel machining capabilities to customers worldwide. DME can supply plates, strips and blocks from our inventory or accept your material for the machining services we offer.

Steel Processing Services to meet your Special Requirements

Available Services

DME can execute CNC machining to your exact specifications whether we're provided hand drawings or CAD files. The list below includes just some of the services that we handle every day:

- Steel plates, strips and blocks up to 6 $\frac{1}{8}$ " thick available in 1030, P-20 and 420F
- Plate sawing up to 150" long and 20" thick
- Flame cut strips up to 6 $\frac{1}{8}$ " thick
- Horizontal and vertical band sawing
- Flattening with 2,000-ton press or roller leveling
- Milling up to 150" long, 46" wide and 20" thick
- Edge milling up to 70" square; beveled edge machining
- Rotary grinding on 84" or 42" Blanchard or double-disc grinding
- Finish grinding up to 40" wide

Quality You Can Count On!

Quality has been and continues to be a part of our fabric at DME, and our undying commitment to quality extends throughout all facets of our business. To maintain customer focus, all DME Quality Management Systems are ISO 9001:2015 certified. We undergo continuous testing for quality including consistently measuring tooling, calibrating our machinery, and inspecting finished work to ensure our customers receive quality they can count on. The DME high standard for quality has been a hallmark of DME since its inception and is just another aspect of how we partner with you every step of the way.

**CLEAN AND PROTECT YOUR
MOLDS WITH DME MOLD
CLEANER AND MOLD SAVER**



Mold Cleaner and Mold Saver

DME MOLD CLEANER

DME Mold Cleaner is used to remove corrosion forming substances such as lactic acid, urea and sodium chloride, which are common in perspiration residues left by ordinary handling of polished cavities. In addition to cleaning the polished cavity it also provides up to 20 days rust protection at temperatures to 120°F at 100% humidity.

Use DME Mold Cleaner to clean polished mold surfaces and protect them for up to 20 days. Use DME Mold Saver for long lasting protection from corrosion.



For the complete line of
DME Molding Supplies,
scan the QR code below.



ITEM NUMBER	MOLD CLEANER DESCRIPTION
CLE 0001	(1) 12 oz. aerosol can
CLE 0012	Case of (12) 12 oz. aerosol cans
CLE 0004	(1) one gallon can
CLE 0016	Case of (4) one gallon cans

**Available in
12 oz. aerosol
or**

**1 gallon non-aerosol...
individually or by the case.**


DME MOLD SAVER

DME Mold Saver is an ideal protective coating for molds to be stored over a long period of time. It protects polished cavities and all metal parts from costly corrosion damage. Its thin, transparent film averages about .0003" thick. It is soft, dry and waxy and can be easily wiped off without solvents. One can of Mold Saver covers about 80 square feet.



ITEM NUMBER	MOLD SAVER DESCRIPTION
SAV 0001	(1) 12 oz. aerosol can
SAV 0012	Case of (12) 12 oz. aerosol cans
SAV 0004	(1) one gallon can
SAV 0016	Case of (4) one gallon cans

ACCESSORIES FOR MOLD CLEANER AND MOLD SAVER



TRIGGER PUMPS
for 15 oz. cans

ITEM NUMBER	DESCRIPTION
SAV 0003	Package of (6) trigger pumps



"SURE SHOT" COMPRESSED-AIR SPRAY CANISTER


Holds one quart of Mold Cleaner or Mold Saver. Metal can is refillable and reusable. Includes stemmed air valve.

ITEM NUMBER

SAV 0002

Table of Contents

<i>Metric Equivalents and Conversions</i>	216
<i>Steel Hardness Chart</i>	217
<i>Tensile Strength</i>	218
<i>Steel Designations</i>	219
<i>Determining Metric Tolerances</i>	220-229



Metric Equivalents and Conversions

Equivalents: Inch, fraction, decimal, millimeter

INCHES	MILLIMETERS	INCHES	MILLIMETERS
1	25.4	34	863.6
2	50.8	35	889.0
3	76.2	36	914.4
4	101.6	37	939.8
5	127.0	38	965.2
6	152.4	39	990.6
7	177.8	40	1016.0
8	203.2	41	1041.4
9	228.6	42	1066.8
10	254.0	43	1092.2
11	279.4	44	1117.6
12	304.8	45	1143.0
13	330.2	46	1168.4
14	355.6	47	1193.8
15	381.0	48	1219.2
16	406.4	49	1244.6
17	431.8	50	1270.0
18	457.2	51	1295.4
19	482.6	52	1320.8
20	508.0	53	1346.2
21	533.4	54	1371.6
22	558.8	55	1397.0
23	584.2	56	1422.4
24	609.6	57	1447.8
25	635.0	58	1473.2
26	660.4	59	1498.6
27	685.8	60	1524.0
28	711.2	61	1549.4
29	736.6	62	1574.8
30	762.0	63	1600.2
31	787.4	64	1625.6
32	812.8	65	1651.0
33	838.2	66	1676.4

INCHES	MILLIMETERS	INCHES	MILLIMETERS
1/64	0.015625	33/64	0.515625
1/32	0.031250	17/32	0.531250
3/64	0.046875	35/64	0.546875
1/16	0.062500	9/16	0.562500
5/64	0.078125	37/64	0.578125
3/32	0.093750	19/32	0.593750
7/64	0.109375	39/64	0.609375
1/8	0.125000	5/8	0.625000
9/64	0.140625	41/64	0.640625
5/32	0.156250	21/32	0.656250
11/64	0.171875	43/64	0.671875
3/16	0.187500	11/16	0.687500
13/64	0.203125	45/64	0.703125
7/32	0.218750	23/32	0.718750
15/64	0.234375	47/64	0.734375
1/4	0.250000	3/4	0.750000
17/64	0.265625	49/64	0.765625
9/32	0.281250	25/32	0.781250
19/64	0.296875	51/64	0.796875
5/16	0.312500	13/16	0.812500
21/64	0.328125	53/64	0.828125
11/32	0.343750	27/32	0.843750
23/64	0.359375	55/64	0.859375
3/8	0.375000	7/8	0.875000
25/64	0.390625	57/64	0.890625
13/32	0.406250	29/32	0.906250
27/64	0.421875	59/64	0.921875
7/16	0.437500	15/16	0.937500
29/64	0.453125	61/64	0.953125
15/32	0.468750	31/32	0.968750
31/64	0.484375	63/64	0.984375
1/2	0.500000	1	1.000000

Equivalents: Decimal, millimeter

INCHES	MILLIMETERS	INCHES	MILLIMETERS	INCHES	MILLIMETERS
0.001	0.0254	0.01	0.254	0.1	2.54
0.002	0.0508	0.02	0.508	0.2	5.08
0.003	0.0762	0.03	0.762	0.3	7.62
0.004	0.1016	0.04	1.016	0.4	10.16
0.005	0.1270	0.05	1.270	0.5	12.70
0.006	0.1524	0.06	1.524	0.6	15.24
0.007	0.1778	0.07	1.778	0.7	17.78
0.008	0.2032	0.08	2.032	0.8	20.32
0.009	0.2286	0.09	2.286	0.9	22.86

Measurement conversions

MULTIPLY BY	FROM	TO	MULTIPLY BY
0.03937	inch	millimeter	25.4
0.0016	inch ²	millimeter ²	645.16
0.061	inch ³	centimeter ³	16.3871
0.2642	gallon (U.S.)	liter	3.7854
0.03527	oz. (avdp.)	gram	28.3495
2.2044	pound	kilogram	0.4536
62.43	lbs/ft ³	g/cm ³	0.0160
0.145	psi	kPa	6.8948
14.2247	psi	kg/cm ²	0.0703
1.8°C + 32	°F	°C	(°F-32)/1.8

Steel Hardness Chart

CROSS-REFERENCE BETWEEN DIFFERENT HARDNESS MEASUREMENTS					
BRINELL HARDNESS BHN*	VICKERS HARDNESS HV	ROCKWELL HARDNESS HRA	ROCKWELL HARDNESS HRB	ROCKWELL HARDNESS HRC	SHORE HARDNESS HS
10mm BALL, 3000kgf LOAD	136° DIAMOND PYRAMID, 10kgf LOAD	BALE PENETRATOR, 60kgf LOAD	1/16 INCH BALL, 100kgf LOAD	BALE PENETRATOR, 150kgf LOAD	
86	90		48		
95	100		56.2		
105	110		62.3		
114	120		66.7		
124	130		71.2		20
133	140		75		21
143	150		78.7		22
152	160		81.7	(0)	24
162	170		85	(3)	25
171	180		87.1	(6)	26
181	190		89.5	(8.5)	28
190	200		91.5	(11)	29
200	210		93.4	(13.4)	30
209	220		95	(15.7)	32
219	230		96.7	(18)	33
228	240	60.7	98.1	20.3	34
238	250	61.6	99.5	22.2	36
247	260	62.4	(101)	24	37
256	270	63.1	(102)	25.6	38
265	280	63.8	(103.5)	27.1	40
275	290	64.5	(104.5)	28.5	41
284	300	65.2	(105.5)	29.8	42
303	320	66.4	(107)	32.2	45
322	340	67.6	(108)	34.4	47
341	360	68.7	(109)	36.6	50
360	380	69.8	(110)	38.8	52
379	400	70.8		40.8	55
397	420	71.8		42.7	57
415	440	72.8		44.5	59
433	460	73.6		46.1	62
452	480	74.5		47.7	64
471	500	75.3		49.1	66
488	520	76.1		50.5	67
507	540	76.7		51.7	69
525	560	77.4		53	71
545	580	78		54.1	72
564	600	78.6		55.2	74
582	620	79.2		56.3	75
601	640	79.8		57.3	77
620	660	80.3		58.3	79
638	680	80.8		59.2	80
656	700	81.3		60.1	81
670	720	81.8		61	83
684	740	82.2		61.8	84
698	760	82.6		62.5	86
710	780	83		63.3	87
722	800	83.4		64	88
745	840	84.1		65.3	91
767	880	84.7		66.4	93

*A 10mm steel ball is used for 450 BHN and below. A 10mm carbide ball is used above 450 BHN.

Also known as Firth Diamond Hardness Number.

Values in parentheses are not contained in the normal definition range for hardness checking, but are often used in a comparable measure.

All values shown in this chart are approximate and intended only as a reference guide.

Tensile Strength

GENERAL STEEL GROUP THROUGH HARDNESS VERSUS APPROXIMATE TENSILE STRENGTH									
HARDNESS		TENSILE STRENGTH							
BRINELL HARDNESS BHN*	ROCKWELL HARDNESS HRC	PLAIN CARBON STEEL AND LOW ALLOY STEEL		STAINLESS STEEL AUSTENITIC TYPE			STAINLESS STEEL CHROMIUM TYPE		
10mm BALL, 3000kgf LOAD	BRINELL PENETRATOR, 150kgf LOAD	N/mm ² (APPROX.)	PSI (APPROX.)	kgf/mm ² (APPROX.)	N/mm ² (APPROX.)	PSI (APPROX.)	kgf/mm ² (APPROX.)	N/mm ² (APPROX.)	PSI (APPROX.)
86		285	41,334						
95		320	46,410						
105		350	50,761						
114		385	55,837						
124		415	60,188						
133		450	65,264						
143		480	69,615	50	490	71,115	50	490	71,115
152	(0)	510	73,966	56	549	79,649	53	520	75,382
162	(3)	545	79,042	62	608	88,183	59	579	83,916
171	(6)	575	83,393	62	608	88,183	59	579	83,916
181	(8.5)	610	88,470	68	667	96,716	65	637	92,450
190	(11)	640	92,820	68	667	96,716	65	637	92,450
200	(13.4)	675	97,897	75	736	106,673	71	696	100,983
209	(15.7)	705	102,248	75	736	106,673	71	696	100,983
219	(18)	740	107,324	80	785	113,784	78	765	110,939
228	20.3	770	111,675	80	785	113,784	78	765	110,939
238	22.2	800	116,026	85	834	120,896	81	794	115,206
247	24	835	121,102	88	863	125,162			
256	25.6	865	125,453	91	892	129,429	88	863	125,162
265	27.1	900	130,529	94	922	133,696			
275	28.5	930	134,880	97	951	137,963	96	941	136,541
284	29.8	965	139,956	100	981	142,230			
303	32.2	1,030	149,383	109	1,069	155,031	106	1,040	150,764
322	34.4	1,095	158,810	118	1,157	167,831	113	1,108	160,720
341	36.6	1,155	167,512	127	1,245	180,632	120	1,177	170,676
360	38.8	1,220	176,939	136	1,334	193,433	127	1,245	180,632
379	40.8	1,290	187,091	145	1,422	206,234	134	1,314	190,588
397	42.7	1,350	195,793	156	1,530	221,879			
415	44.5	1,420	205,945	167	1,638	237,524			
433	46.1	1,485	215,372	178	1,746	253,169			
452	47.7	1,555	225,525	189	1,853	268,815			
471	49.1	1,630	236,402	200	1,961	284,460			
488	50.5	1,700	246,554	209	2,050	297,261			
507	51.7	1,775	257,432	218	2,138	310,061			
525	53	1,845	267,584	227	2,226	322,862			
545	54.1	1,920	278,461	236	2,314	335,663			
564	55.2	1,995	289,339	245	2,403	348,464			
*A 10mm steel ball is used for 450 BHN and below. A 10mm carbide ball is used above 450 BHN.		The Tensile Strength relationship to hardness is inexact, even for the steel, unless it is determined for a specific material. Therefore, this chart provides only very general approximate Tensile Strength values.							
Values in parentheses are not contained in the normal definition range for hardness checking, but are often used in a comparable measure.									

All values shown in this chart are approximate and intended only as a reference guide.

Steel Designations

GENERAL STEEL GROUP DESIGNATIONS					
PLAIN CARBON STEEL	LOW ALLOY CARBON STEEL	COLD WORK TOOL STEEL	HOT WORK TOOL STEEL	STAINLESS STEEL AUSTENITIC TYPE	STAINLESS STEEL CHROMIUM TYPE (MARTENSITIC & FERRITIC)
AISI	AISI	AISI	AISI	AISI	AISI
1000 SERIES	4000 SERIES	A2	H10	201	410
	5000 SERIES	A3A	H11	203	416
	6000 SERIES	4	H12	205	420
	8000 SERIES	A5	H13	301	429
	9000 SERIES	A6	H14	302	430
		A7	H19	303	431
		A8	H21	304	434
		A9	H22	305	436
		A10	H23	307	439
		D2	H24	308	440
		D3	H25	309	442
		D4	H26	310	444
		D5	H40	314	446
		D7	H41	316	
			H42	317	
			H43	318	
				321	
				329	
				330	
				332	
				334	
				347	
				348	
				384	
				385	

GENERAL STEEL CROSS-REFERENCE INFORMATION*	
GERMAN WERKSTOFF STANDARD NUMBER FOR STEEL	U.S. STEEL NUMBER AISI
1.0716	NO CROSS-REFERENCE
1.0718	12 L 13 TYPE*
1.1191	1045 TYPE*
1.1730	NO CROSS-REFERENCE
1.2210	L-2 TYPE*
1.2344	H-13 TYPE*
1.2826	NO CROSS-REFERENCE
1.4305	303 TYPE STAINLESS*
1.5710 (AFNOR 35 NC 6)	3135 TYPE*
1.7131	5115 TYPE (SIMILAR TO 1018 & 8620)*
1.8159 (DIN 50 CrV 4)	6150 TYPE*

*Exchangeability should only be considered after thorough examination of individual case.

Tables for Determining Metric Tolerances

Table 1: Description of Preferred Fits

Table 1 is pulled from the ANSI metric tolerances section of the machinists' handbook, which conforms to the ISO and DIN tolerances for hole basis and shaft basis fits. Table 1 provides an overview of the hole basis and shaft basis fits that make up clearance fit, transition fit and interference fit combinations.

	ISO SYMBOL			
	HOLE BASIS	SHAFT BASIS		
CLEARANCE FITS	H11/c11	C11/h11	LOOSE RUNNING FIT	FOR WIDE COMMERCIAL TOLERANCES OR ALLOWANCES ON EXTERNAL MEMBERS.
	H9/d9	D9/h9	FREE RUNNING FIT	NOT FOR USE WHERE ACCURACY IS ESSENTIAL, BUT GOOD FOR LARGE TEMPERATURE VARIATIONS, HIGH RUNNING SPEEDS, OR HEAVY JOURNAL PRESSURES.
	H8/f7	F8/h7	CLOSE RUNNING FIT	FOR RUNNING ON ACCURATE MACHINES AND FOR ACCURATE LOCATION AT MODERATE SPEEDS AND JOURNAL PRESSURES.
	H7/g6	G7/h6	SLIDING FIT	NOT INTENDED TO RUN FREELY, BUT TO MOVE AND TURN FREELY AND LOCATE ACCURATELY.
	H7/h6	H7/h6	LOCATIONAL CLEARANCE FIT	PROVIDES SNUG FIT FOR LOCATING STATIONARY PARTS; BUT CAN BE FREELY ASSEMBLED AND DISASSEMBLED.
TRANSITION FITS	H7/k6	K7/h6	LOCATIONAL TRANSITION FIT	FOR ACCURATE LOCATION, A COMPROMISE BETWEEN CLEARANCE AND INTERFERENCE.
	H7/n6	N7/h6	LOCATIONAL TRANSITION FIT	FOR MORE ACCURATE LOCATION WHERE GREATER INTERFERENCE IS PERMISSIBLE.
INTERFERENCE FITS	H7/p6*	P7/h6	LOCATIONAL INTERFERENCE FIT	FOR PARTS REQUIRING RIGIDITY AND ALIGNMENT WITH PRIME ACCURACY OF LOCATION BUT WITHOUT SPECIAL BORE PRESSURE REQUIREMENTS.
	H7/s6	S7/h6	MEDIUM DRIVE FIT	FOR ORDINARY STEEL PARTS OR SHRINK FITS ON LIGHT SECTIONS, THE TIGHTEST FIT USABLE WITH CAST IRON.
	H7/u6	U7/h6	FORCE FIT	SUITABLE FOR PARTS WHICH CAN BE HIGHLY STRESSED OR FOR SHRINK FITS WHERE THE HEAVY PRESSING FORCES REQUIRED ARE IMPRACTICAL.

Excerpt from *Machinists' Handbook*, pg. 661, 25 Ed., Industrial Press.

*The H7/p6 Hole Basis fit is a transition fit for basic sizes in ranges from 0 through 3mm.

Table 2: Commonly Used Hole-Basis System of Fits

Table 2 shows closer detail on the hole-basis system of fits than Table 1. When using the hole-basis system of fits, the smallest diameter in the hole tolerance range is fixed to the zero line (basic nominal hole size or diameter), and the clearance between the shaft and hole extends below the zero line, or negative relative to the basic nominal hole size.

BASIC HOLES	LETTER SYMBOLS AND GRADE NUMBERS OF SHAFTS																
	CLEARANCE FITS						TRANSITION FITS				INTERFERENCE FITS						
	b	c	d	e	f	g	h	js	k	m	n	p	r	s	t	u	x
H5						4	4	4	4	4							
H6						5	5	5	5	5							
					6	6	6	6	6	6	6*	6*					
H7				6	6	6	6	6	6	6	6	6*	6*	6	6	6	6
				7	7	7	7	7	7	7	7	7*	7*	7	7	7	7
					7		7										
H8				8	8		8										
			9	9													
H9			8	8			8										
		9	9	9			9										
H10	9	9	9														

*Exceptions occur in some steps of dimensions.

Tables for Determining Metric Tolerances

Table 3: Commonly Used Shaft-Basis System of Fits

Table 3 shows closer detail on the shaft-basis system of fits than Table 1. When using the shaft-basis system of fits, the largest diameter in the shaft tolerance range is fixed to the zero line (basic nominal shaft size or diameter), and the clearance between the shaft and hole extends above the zero line, or positive relative to the basic shaft size.

BASIC SHAFTS	LETTER SYMBOLS AND GRADE NUMBERS OF HOLES																
	CLEARANCE FITS						TRANSITION FITS				INTERFERENCE FITS						
	B	C	D	E	F	G	H	Js	K	M	N	P	R	S	T	U	X
h4							5	5	5	5							
h5							6	6	6	6	6*	6					
h6					6	6	6	6	6	6	6	6*					
				7	7	7	7	7	7	7	7	7*	7	7	7	7	7
h7				7	7	7	7	7	7	7	7	7	7*	7			
					8		8										
h8			8	8	8		8										
			9	9			9										
h9			8	8			8										
		9	9	9			9										
	10	10	10														

*Exceptions occur in some steps of dimensions.

Table 4: IT Standard Tolerances

Table 4 details the ISO-basic tolerances (International Tolerance Grades, or, "IT") which apply to all linear sizes (external and internal sizes, diameters, lengths, widths and thicknesses). An IT-grade number establishes the magnitude of the tolerance zone, while the tolerance position letter determines where the tolerance zone is in relation to the zero line. The combination of tolerance position letter (A-X, a-x) and IT-grade number (01-8) creates the overall tolerance symbol (i.e., F8/h7 when using the shaft-basis system of fits).

For nominal size range up to 500mm according to DIN 7151/ISO 286, and for nominal size range over 500mm, according to DIN 7172/ISO 286.

ITEMS IN mm		IT STANDARD TOLERANCES (UNITS IN 0.001mm)																				
OVER	TO	IT01	IT0	IT1	IT2	IT3	IT4	IT5	IT6	IT7	IT8	IT9	IT10	IT11	IT12	IT13	IT14	IT15	IT16	IT17	IT18	
NOMINAL SIZE RANGE	0	3	0.3	0.5	0.8	1.2	2	3	4	6	10	14	25	40	60	100	140	250	400	600	—	—
	3	6	0.4	0.6	1	1.5	2.5	4	5	8	12	18	30	48	75	120	180	300	480	750	—	—
	6	10	0.4	0.6	1	1.5	2.5	4	6	9	15	22	36	58	90	150	220	360	580	900	1500	—
	10	18	0.5	0.8	1.2	2	3	5	8	11	18	27	43	70	110	180	270	430	700	1100	1800	2700
	18	30	0.6	1	1.5	2.5	4	6	9	13	21	33	52	84	130	210	330	520	840	1300	2100	3300
	30	50	0.6	1	1.5	2.5	4	7	11	16	25	39	62	100	160	250	390	620	1000	1600	2500	3900
	50	80	0.8	1.2	2	3	5	8	13	19	30	46	74	120	190	300	460	740	1200	1900	3000	4600
	80	120	1	1.5	2.5	4	6	10	15	22	35	54	87	140	220	350	540	870	1400	2200	3500	5400
	120	180	1.2	2	3.5	5	8	12	18	25	40	63	100	160	250	400	630	1000	1600	2500	4000	6300
	180	250	2	3	4.5	7	10	14	20	29	46	72	115	185	290	460	720	1150	1850	2900	4600	7200
	250	315	2.5	4	6	8	12	16	23	32	52	81	130	210	320	520	810	1300	2100	3200	5200	8100
	315	400	3	5	7	9	13	18	25	36	57	89	140	230	360	570	890	1400	2300	3600	5700	8900
	400	500	4	6	8	10	15	20	27	40	63	97	155	250	400	630	970	1550	2500	4000	6300	9700
	500	630	4.5	6	9	11	16	22	30	44	70	110	175	280	440	700	1100	1750	2800	4400	—	—
	630	800	5	7	10	13	18	25	35	50	80	125	200	320	500	800	1250	2000	3200	5000	—	—
	800	1000	5.5	8	11	15	21	29	40	56	90	140	230	360	560	900	1400	2300	3600	5600	—	—

Tables for Determining Metric Tolerances

Table 6: Tolerances for Inside Dimensions (Holes)

Table 6 details tolerances for inside dimensions (holes) based relative to the tolerance symbol. Upper and lower values are provided as either positive or negative (or zero) values relative to the nominal size chosen. Pick the range in which the desired nominal value falls, and then either add or subtract the tolerances to find the upper and lower tolerance range for the desired nominal size.

UNITS IN mm		TOLERANCES FOR INSIDE DIMENSIONS (HOLES) (UNITS IN 0.001mm)																			
OVER	TO	A11	B8	B11	C11	D9	D10	D11	E8	E9	F6	F7	F8	G6	G7	H5	H6	H7	H8	H9	H10
0	1	—	—	—	+120	+45	+60	+80	+28	+39	+12	+16	+20	+8	+12	+4	+6	+10	+14	+25	+40
1	3	+330 +270	+154 +140	+200 +140	+60	+20	+20	+20	+14	+14	+6	+6	+6	+2	+2	0	0	0	0	0	0
3	6	+345 +270	+158 +140	+215 +140	+145 +70	+60 +30	+78 +30	+105 +30	+38 +20	+50 +20	+18 +10	+22 +10	+28 +10	+12 +4	+16 +4	+5 0	+8 0	+12 0	+18 0	+30 0	+48 0
6	10	+370 +280	+172 +150	+240 +150	+170 +80	+76 +40	+98 +40	+130 +40	+47 +25	+61 +25	+22 +13	+28 +13	+35 +13	+14 +5	+20 +5	+6 0	+9 0	+15 0	+22 0	+36 0	+58 0
10	14	+400 +290	+177 +150	+260 +150	+205 +95	+93 +50	+120 +50	+160 +50	+59 +32	+75 +32	+27 +16	+34 +16	+43 +16	+17 +6	+24 +6	+8 0	+11 0	+18 0	+27 0	+43 0	+70 0
14	18	+400 +290	+177 +150	+260 +150	+205 +95	+93 +50	+120 +50	+160 +50	+59 +32	+75 +32	+27 +16	+34 +16	+43 +16	+17 +6	+24 +6	+8 0	+11 0	+18 0	+27 0	+43 0	+70 0
18	24	+430 +300	+193 +160	+290 +160	+240 +110	+117 +65	+149 +65	+195 +65	+73 +40	+92 +40	+33 +20	+41 +20	+53 +20	+20 +7	+28 +7	+9 0	+13 0	+21 0	+33 0	+52 0	+84 0
24	30	+430 +300	+193 +160	+290 +160	+240 +110	+117 +65	+149 +65	+195 +65	+73 +40	+92 +40	+33 +20	+41 +20	+53 +20	+20 +7	+28 +7	+9 0	+13 0	+21 0	+33 0	+52 0	+84 0
30	40	+470 +310	+209 +170	+330 +170	+280 +120	+142	+180	+240	+89	+112	+41	+50	+64	+25	+34	+11	+16	+25	+39	+62	+100
40	50	+480 +320	+219 +180	+340 +180	+290 +130	+80	+80	+80	+50	+50	+25	+25	+25	+9	+9	0	0	0	0	0	0
50	65	+530 +340	+236 +190	+380 +190	+330 +140	+174	+220	+290	+106	+134	+49	+60	+76	+29	+40	+13	+19	+30	+46	+74	+120
65	80	+550 +360	+246 +200	+390 +200	+340 +150	+100	+100	+100	+60	+60	+30	+30	+30	+10	+10	0	0	0	0	0	0
80	100	+600 +380	+274 +220	+440 +220	+390 +170	+207	+260	+340	+126	+159	+58	+71	+90	+34	+47	+15	+22	+35	+54	+87	+140
100	120	+630 +410	+294 +240	+460 +240	+400 +180	+120	+120	+120	+72	+72	+36	+36	+36	+12	+12	0	0	0	0	0	0
120	140	+710 +460	+323 +260	+510 +260	+450 +200																
140	160	+770 +520	+343 +280	+530 +280	+460 +210	+245	+305	+395	+148	+185	+68	+83	+106	+39	+54	+18	+25	+40	+63	+100	+160
160	180	+830 +580	+373 +310	+560 +310	+480 +230	+145	+145	+145	+85	+85	+43	+43	+43	+14	+14	0	0	0	0	0	0
180	200	+950 +660	+412 +340	+630 +340	+530 +240																
200	225	+1030 +740	+452 +380	+670 +380	+550 +260	+285	+355	+460	+172	+215	+79	+96	+122	+44	+61	+20	+29	+46	+72	+115	+185
225	250	+1110 +820	+492 +420	+710 +420	+570 +280	+170	+170	+170	+100	+100	+50	+50	+50	+15	+15	0	0	0	0	0	0
250	280	+1240 +920	+561 +480	+800 +480	+620 +300	+320	+400	+510	+191	+240	+88	+108	+137	+49	+69	+23	+32	+52	+81	+130	+210
280	315	+1370 +1050	+621 +540	+860 +540	+650 +330	+190	+190	+190	+110	+110	+56	+56	+56	+17	+17	0	0	0	0	0	0
315	355	+1560 +1200	+689 +600	+960 +600	+720 +360	+350	+440	+570	+214	+265	+98	+119	+151	+54	+75	+25	+36	+57	+89	+140	+230
355	400	+1710 +1350	+769 +680	+1040 +680	+760 +400	+210	+210	+210	+125	+125	+62	+62	+62	+18	+18	0	0	0	0	0	0
400	450	+1900 +1500	+857 +760	+1160 +760	+840 +440	+385	+480	+630	+232	+290	+108	+131	+165	+60	+83	+27	+40	+63	+97	+155	+250
450	500	+2050 +1650	+937 +840	+1240 +840	+880 +480	+230	+230	+230	+135	+135	+68	+68	+68	+20	+20	0	0	0	0	0	0

Tables for Determining Metric Tolerances

Table 6: Tolerances for Inside Dimensions (Holes) – continued

UNITS IN mm		TOLERANCES FOR INSIDE DIMENSIONS (HOLES) (UNITS IN 0.001mm)																			
OVER	TO	H11	H12	H13	J6	J7	J8	K6	K7	K8	M6	M7	M8	N6	N7	N8	R7	JS6	JS7	JS8	JS9
0	1	+60	+100	+140	+2	+4	+6	0	0	0	-2	-2	-2	-4	-4	-4	-10	+3	+5	+7	+12.5
1	3	0	0	0	-4	-6	-8	-6	-10	-14	-8	-12	-16	-10	-14	-18	-20	-3	-5	-7	-12.5
3	6	+75	+120	+180	+5	+6	+10	+2	+3	+5	-1	0	+2	-5	-4	-2	-11	+4	+6	+9	+15
		0	0	0	-3	-6	-8	-6	-9	-13	-9	-12	-16	-13	-16	-20	-23	-4	-6	-9	-15
6	10	+90	+150	+220	+5	+8	+12	+2	+5	+6	-3	0	+1	-7	-4	-3	-13	+4.5	+7.5	+11	+18
		0	0	0	-4	-7	-10	-7	-10	-16	-12	-15	-21	-16	-19	-25	-28	-4.5	-7.5	-11	-18
10	14	+110	+180	+270	+6	+10	+15	+2	+6	+8	-4	0	+2	-9	-5	-3	-16	+5.5	+9	+13.5	+21.5
14	18	0	0	0	-5	-8	-12	-9	-12	-19	-15	-18	-25	-20	-23	-30	-34	-5.5	-9	-13.5	-21.5
18	24	+130	+210	+330	+8	+12	+20	+2	+6	+10	-4	0	+4	-11	-7	-3	-20	+6.5	+10.5	+16.5	+26
24	30	0	0	0	-5	-9	-13	-11	-15	-23	-17	-21	-29	-24	-28	-36	-41	-6.5	-10.5	-16.5	-26
30	40	+160	+250	+390	+10	+14	+24	+3	+7	+12	-4	0	+5	-12	-8	-3	-25	+8	+12.5	+19.5	+31
40	50	0	0	0	-6	-11	-15	-13	-18	-27	-20	-25	-34	-28	-33	-42	-50	-8	-12.5	-19.5	-31
50	65	+190	+300	+460	+13	+18	+28	+4	+9	+14	-5	0	+5	-14	-9	-4	-30	+9.5	+15	+23	+37
		0	0	0	-6	-12	-18	-15	-21	-32	-24	-30	-41	-33	-39	-50	-60	-9.5	-15	-23	-37
65	80																-32				
																	-62				
80	100	+220	+350	+540	+16	+22	+34	+4	+10	+16	-6	0	+6	-16	-10	-4	-38	+11	+17.5	+27	+43.5
		0	0	0	-6	-13	-20	-18	-25	-38	-28	-35	-48	-38	-45	-58	-73	-11	-17.5	-27	-43.5
100	120																-41				
																	-76				
120	140																-48				
																	-88				
140	160	+250	+400	+630	+18	+26	+41	+4	+12	+20	-8	0	+8	-20	-12	-4	-50	+12.5	+20	+31.5	+50
		0	0	0	-7	-14	-22	-21	-28	-43	-33	-40	-55	-45	-52	-67	-90	-12.5	-20	-31.5	-50
160	180																-53				
																	-93				
180	200																-60				
																	-106				
200	225	+290	+460	+720	+22	+30	+47	+5	+13	+22	-8	0	+9	-22	-14	-5	-63	+14.5	+23	+36	+57.5
		0	0	0	-7	-16	-25	-24	-33	-50	-37	-46	-63	-51	-60	-77	-109	-14.5	-23	-36	-57.5
225	250																-67				
																	-113				
250	280	+320	+520	+810	+25	+36	+55	+5	+16	+25	-9	0	+9	-25	-14	-5	-74	+16	+26	+40.5	+65
		0	0	0	-7	-16	-26	-27	-36	-56	-41	-52	-72	-57	-66	-86	-126	-16	-26	-40.5	-65
280	315																-78				
																	-130				
315	355	+360	+570	+890	+29	+39	+60	+7	+17	+28	-10	0	+11	-26	-16	-5	-87	+18	+28.5	+44.5	+70
		0	0	0	-7	-18	-29	-29	-40	-61	-46	-57	-78	-62	-73	-94	-144	-18	-28.5	-44.5	-70
355	400																-93				
																	-150				
400	450	+400	+630	+970	+33	+43	+66	+8	+18	+29	-10	0	+11	-27	-17	-6	-103	+20	+31.5	+48.5	+77.5
		0	0	0	-7	-20	-31	-32	-45	-68	-50	-63	-86	-67	-80	-103	-166	-20	-31.5	-48.5	-77.5
450	500																-109				
																	-172				

Tables for Determining Metric Tolerances

Table 6: Tolerances for Inside Dimensions (Holes) – continued

UNITS IN mm		TOLERANCES FOR INSIDE DIMENSIONS (HOLES) (UNITS IN 0.001mm)								
OVER	TO	JS10	JS11	JS12	JS13	JS14	JS15	JS16	JS17	JS18
0	1	+20	+30	+50	+70	+125	+200	+300	—	—
1	3	-20	-30	-50	-70	-125	-200	-300	—	—
3	6	+24	+37.5	+60	+90	+150	+240	+375	—	—
		-24	-37.5	-60	-90	-150	-240	-375	—	—
6	10	+29	+45	+75	+110	+180	+290	+450	+750	—
		-29	-45	-75	-110	-180	-290	-450	-750	—
10	14	+35	+55	+90	+135	+215	+350	+550	+900	+1350
14	18	-35	-55	-90	-135	-215	-350	-550	-900	-1350
18	24	+42	+65	+105	+165	+260	+420	+650	+1050	+1650
24	30	-42	-65	-105	-165	-260	-420	-650	-1050	-1650
30	40	+50	+80	+125	+195	+310	+500	+800	+1250	+1950
40	50	-50	-80	-125	-195	-310	-500	-800	-1250	-1950
50	65	+60	+95	+150	+230	+370	+600	+950	+1500	+2300
65	80	-60	-95	-150	-230	-370	-600	-950	-1500	-2300
80	100	+70	+110	+175	+270	+435	+700	+1100	+1750	+2700
100	120	-70	-110	-175	-270	-435	-700	-1100	-1750	-2700
120	140	+80	+125	+200	+315	+500	+800	+1250	+2000	+3150
140	160	-80	-125	-200	-315	-500	-800	-1250	-2000	-3150
160	180									
180	200									
200	225	+92.5	+145	+230	+360	+575	+925	+1450	+2300	+3600
225	250	-92.5	-145	-230	-360	-575	-925	-1450	-2300	-3600
250	280	+105	+160	+260	+405	+650	+1050	+1600	+2600	+4050
280	315	-105	-160	-260	-405	-650	-1050	-1600	-2600	-4050
315	355	+115	+180	+285	+445	+700	+1150	+1800	+2850	+4450
355	400	-115	-180	-285	-445	-700	-1150	-1800	-2850	-4450
400	450	+125	+200	+315	+485	+775	+1250	+2000	+3150	+4850
450	500	-125	-200	-315	-485	-775	-1250	-2000	-3150	-4850

Tables for Determining Metric Tolerances

Table 7: Tolerances for Outside Dimensions (Shafts)

Table 7 details tolerances for outside dimensions (shafts) based relative to the tolerance symbol. Upper and lower values are provided as either positive or negative (or zero) values relative to the nominal size chosen. Pick the range in which the desired nominal value falls, and then either add or subtract the tolerances to find the upper and lower tolerance range for the desired nominal size.

UNITS IN mm		TOLERANCES FOR OUTSIDE DIMENSIONS (SHAFTS) (UNITS IN 0.001mm)																					
OVER	TO	a11	b8	b11	c11	d9	d10	d11	e7	e8	e9	f6	f7	f8	f9	g5	g6	g7	h4	h5	h6	h7	
NOMINAL SIZE RANGE	0	1	—	—	—	-60	-20	-20	-20	-14	-14	-14	-6	-6	-6	-6	-2	-2	-2	0	0	0	0
	1	3	-270 -330	-140 -154	-140 -200	-120	-45	-60	-80	-24	-28	-39	-12	-16	-20	-31	-6	-8	-12	-3	-4	-6	-10
	3	6	-270 -345	-140 -158	-140 -215	-70 -145	-30 -60	-30 -78	-30 -105	-20 -32	-20 -38	-20 -50	-10 -18	-10 -22	-10 -28	-10 -40	-4 -9	-4 -12	-4 -16	0 -4	0 -5	0 -8	0 -12
	6	10	-280 -370	-150 -172	-150 -240	-80 -170	-40 -76	-40 -98	-40 -130	-25 -40	-25 -47	-25 -61	-13 -22	-13 -28	-13 -35	-13 -49	-5 -11	-5 -14	-5 -20	0 -4	0 -6	0 -9	0 -15
	10	14	-290 -400	-150 -177	-150 -260	-95 -205	-50 -93	-50 -120	-50 -160	-32 -50	-32 -59	-32 -75	-16 -27	-16 -34	-16 -43	-16 -59	-6 -14	-6 -17	-6 -24	0 -5	0 -8	0 -11	0 -18
	14	18																					
	18	24	-300 -430	-160 -193	-160 -290	-110 -240	-65 -117	-65 -149	-65 -195	-40 -61	-40 -73	-40 -92	-20 -33	-20 -41	-20 -53	-20 -72	-7 -16	-7 -20	-7 -28	0 -6	0 -9	0 -13	0 -21
	24	30																					
	30	40	-310 -470	-170 -209	-170 -330	-120 -280	-80	-80	-80	-50	-50	-50	-25	-25	-25	-25	-9	-9	-9	0	0	0	0
	40	50	-320 -480	-180 -219	-180 -340	-130 -290	-142	-180	-240	-75	-89	-112	-41	-50	-64	-87	-20	-25	-34	-7	-11	-16	-25
	50	65	-340 -530	-190 -236	-190 -380	-140 -330	-100	-100	-100	-60	-60	-60	-30	-30	-30	-30	-10	-10	-10	0	0	0	0
	65	80	-360 -550	-200 -246	-200 -390	-150 -340	-174	-220	-290	-90	-106	-134	-49	-60	-76	-104	-23	-29	-40	-8	-13	-19	-30
	80	100	-380 -600	-220 -274	-220 -440	-170 -390	-120	-120	-120	-72	-72	-72	-36	-36	-36	-36	-12	-12	-12	0	0	0	0
	100	120	-410 -630	-240 -294	-240 -460	-180 -400	-207	-260	-340	-107	-126	-159	-58	-71	-90	-123	-27	-34	-47	-10	-15	-22	-35
	120	140	-460 -710	-260 -323	-260 -510	-200 -450																	
	140	160	-520 -770	-280 -343	-280 -530	-210 -460	-145	-145	-145	-85	-85	-85	-43	-43	-43	-43	-14	-14	-14	0	0	0	0
	160	180	-580 -830	-310 -373	-310 -560	-230 -480	-245	-305	-395	-125	-148	-185	-68	-83	-106	-143	-32	-39	-54	-12	-18	-25	-40
	180	200	-660 -950	-340 -412	-340 -630	-240 -530																	
	200	225	-740 -1030	-380 -452	-380 -670	-260 -550	-170	-170	-170	-100	-100	-100	-50	-50	-50	-50	-15	-15	-15	0	0	0	0
	225	250	-820 -1110	-420 -492	-420 -710	-280 -570	-285	-355	-460	-146	-172	-215	-79	-96	-122	-165	-35	-44	-61	-14	-20	-29	-46
250	280	-920 -1240	-480 -561	-480 -800	-300 -620	-190	-190	-190	-110	-110	-110	-56	-56	-56	-56	-17	-17	-17	0	0	0	0	
280	315	-1050 -1370	-540 -621	-540 -860	-330 -650	-320	-400	-510	-162	-191	-240	-88	-108	-137	-186	-40	-49	-69	-16	-23	-32	-52	
315	355	-1200 -1560	-600 -689	-600 -960	-360 -720	-210	-210	-210	-125	-125	-125	-62	-62	-62	-62	-18	-18	-18	0	0	0	0	
355	400	-1350 -1710	-680 -769	-680 -1040	-400 -760	-350	-440	-570	-182	-214	-265	-98	-119	-151	-202	-43	-54	-75	-18	-25	-36	-57	
400	450	-1500 -1900	-760 -857	-760 -1160	-440 -840	-230	-230	-230	-135	-135	-135	-68	-68	-68	-68	-20	-20	-20	0	0	0	0	
450	500	-1650 -2050	-840 -937	-840 -1240	-480 -880	-385	-480	-630	-198	-232	-290	-108	-131	-165	-223	-47	-60	-83	-20	-27	-40	-63	

Tables for Determining Metric Tolerances

Table 7: Tolerances for Outside Dimensions (Shafts) – continued

UNITS IN mm			TOLERANCES FOR OUTSIDE DIMENSIONS (SHAFTS) (UNITS IN 0.001mm)																			
OVER	TO	h8	h9	h10	h11	j5	j6	j7	k5	k6	k7	k8	m5	m6	m7	n5	n6	n7	r6	js6	js7	
NOMINAL SIZE RANGE	0	1	0	0	0	0	+2	+4	+6	+4	+6	+10	+14	+6	+8	+12	+8	+10	+14	+16	+3	+5
	1	3	-14	-25	-40	-60	-2	-2	-4	0	0	0	0	+2	+2	+2	+4	+4	+4	+10	-3	-5
	3	6	0	0	0	0	+3	+6	+8	+6	+9	+13	+18	+9	+12	+16	+13	+16	+20	+23	+4	+6
			-18	-30	-48	-75	-2	-2	-4	+1	+1	+1	0	+4	+4	+4	+8	+8	+8	+15	-4	-6
	6	10	0	0	0	0	+4	+7	+10	+7	+10	+16	+22	+12	+15	+21	+16	+19	+25	+28	+4.5	+7.5
			-22	-36	-58	-90	-2	-2	-5	+1	+1	+1	0	+6	+6	+6	+10	+10	+10	+19	-4.5	-7.5
	10	14	0	0	0	0	+5	+8	+12	+9	+12	+19	+27	+15	+18	+25	+20	+23	+30	+34	+5.5	+9
	14	18	-27	-43	-70	-110	-3	-3	-6	+1	+1	+1	0	+7	+7	+7	+12	+12	+12	+23	-5.5	-9
	18	24	0	0	0	0	+5	+9	+13	+11	+15	+23	+33	+17	+21	+29	+24	+28	+36	+41	+6.5	+10.5
	24	30	-33	-52	-84	-130	-4	-4	-8	+2	+2	+2	0	+8	+8	+8	+15	+15	+15	+28	-6.5	-10.5
	30	40	0	0	0	0	+6	+11	+15	+13	+18	+27	+39	+20	+25	+34	+28	+33	+42	+50	+8	+12.5
	40	50	-39	-62	-100	-160	-5	-5	-10	+2	+2	+2	0	+9	+9	+9	+17	+17	+17	+34	-8	-12.5
	50	65	0	0	0	0	+6	+12	+18	+15	+21	+32	+46	+24	+30	+41	+33	+39	+50	+60	+9.5	+15
			-46	-74	-120	-190	-7	-7	-12	+2	+2	+2	0	+11	+11	+11	+20	+20	+20	+41	-9.5	-15
	65	80																		+62		
																				+43		
	80	100	0	0	0	0	+6	+13	+20	+18	+25	+38	+54	+28	+35	+48	+38	+45	+58	+73	+11	+17.5
			-54	-87	-140	-220	-9	-9	-15	+3	+3	+3	0	+13	+13	+13	+23	+23	+23	+51	-11	-17.5
	100	120																		+76		
																				+54		
	120	140																		+88		
																				+63		
	140	160	0	0	0	0	+7	+14	+22	+21	+28	+43	+63	+33	+40	+55	+45	+52	+67	+90	+12.5	+20
			-63	-100	-160	-250	-11	-11	-18	+3	+3	+3	0	+15	+15	+15	+27	+27	+27	+65	-12.5	-20
	160	180																		+93		
																				+68		
	180	200																		+106		
																				+77		
200	225	0	0	0	0	+7	+16	+25	+24	+33	+50	+72	+37	+46	+63	+51	+60	+77	+109	+14.5	+23	
		-72	-115	-185	-290	-13	-13	-21	+4	+4	+4	0	+17	+17	+17	+31	+31	+31	+80	-14.5	-23	
225	250																		+113			
																			+84			
250	280	0	0	0	0	+7	+16	+26	+27	+36	+56	+81	+43	+52	+72	+57	+66	+86	+126	+16	+26	
		-81	-130	-210	-320	-16	-16	-26	+4	+4	+4	0	+20	+20	+20	+34	+34	+34	+94	-16	-26	
280	315																		+130			
																			+98			
315	355	0	0	0	0	+7	+18	+29	+29	+40	+61	+89	+46	+57	+78	+62	+73	+94	+144	+18	+28.5	
		-89	-140	-230	-360	-18	-18	-28	+4	+4	+4	0	+21	+21	+21	+37	+37	+37	+108	-18	-28.5	
355	400																		+150			
																			+114			
400	450	0	0	0	0	+7	+20	+31	+32	+45	+68	+97	+50	+63	+86	+67	+80	+103	+166	+20	+31.5	
		-97	-155	-250	-400	-20	-20	-32	+5	+5	+5	0	+23	+23	+23	+40	+40	+40	+126	-20	-31.5	
450	500																		+172			
																			+132			

Tables for Determining Metric Tolerances

Table 7: Tolerances for Outside Dimensions (Shafts) – continued

UNITS IN mm		TOLERANCES FOR OUTSIDE DIMENSIONS (SHAFTS) (UNITS IN 0.001mm)										
OVER	TO	js8	js9	js10	js11	js12	js13	js14	js15	js16	js17	js18
0	1	+7	+12.5	+20	+30	+50	+70	+125	+200	+300	—	—
1	3	-7	-12.5	-20	-30	-50	-70	-125	-200	-300	—	—
3	6	+9	+15	+24	+37.5	+60	+90	+150	+240	+375	—	—
		-9	-15	-24	-37.5	-60	-90	-150	-240	-375	—	—
6	10	+11	+18	+29	+45	+75	+110	+180	+290	+450	+750	—
		-11	-18	-29	-45	-75	-110	-180	-290	-450	-750	—
10	14	+13.5	+21.5	+35	+55	+90	+135	+215	+350	+550	+900	+1350
14	18	-13.5	-21.5	-35	-55	-90	-135	-215	-350	-550	-900	-1350
18	24	+16.5	+26	+42	+65	+105	+165	+260	+420	+650	+1050	+1650
24	30	-16.5	-26	-42	-65	-105	-165	-260	-420	-650	-1050	-1650
30	40	+19.5	+31	+50	+80	+125	+195	+310	+500	+800	+1250	+1950
40	50	-19.5	-31	-50	-80	-125	-195	-310	-500	-800	-1250	-1950
50	65	+23	+37	+60	+95	+150	+230	+370	+600	+950	+1500	+2300
65	80	-23	-37	-60	-95	-150	-230	-370	-600	-950	-1500	-2300
80	100	+27	+43.5	+70	+110	+175	+270	+435	+700	+1100	+1750	+2700
100	120	-27	-43.5	-70	-110	-175	-270	-435	-700	-1100	-1750	-2700
120	140	+31.5	+50	+80	+125	+200	+315	+500	+800	+1250	+2000	+3150
140	160	-31.5	-50	-80	-125	-200	-315	-500	-800	-1250	-2000	-3150
160	180											
180	200	+36	+57.5	+92.5	+145	+230	+360	+575	+925	+1450	+2300	+3600
200	225	-36	-57.5	-92.5	-145	-230	-360	-575	-925	-1450	-2300	-3600
225	250											
250	280	+40.5	+65	+105	+160	+260	+405	+650	+1050	+1600	+2600	+4050
280	315	-40.5	-65	-105	-160	-260	-405	-650	-1050	-1600	-2600	-4050
315	355	+44.5	+70	+115	+180	+285	+445	+700	+1150	+1800	+2850	+4450
355	400	-44.5	-70	-115	-180	-285	-445	-700	-1150	-1800	-2850	-4450
400	450	+48.5	+77.5	+125	+200	+315	+485	+775	+1250	+2000	+3150	+4850
450	500	-48.5	-77.5	-125	-200	-315	-485	-775	-1250	-2000	-3150	-4850

Technical Reference

Table 8 details tolerances for inside dimensions (holes) based relative to the tolerance symbol. This table works the same way as Table 6, but is pulled from a different source (ANSI standards) and details S7 and U7 fits. Pick the nominal size value that is **closest** to the desired nominal size to determine the required tolerance range relative to the chosen tolerance symbol.

	TOLERANCES FOR INSIDE DIMENSIONS (HOLES) (UNITS IN 0.001mm)					
	PICK CLOSEST VALUE TO DESIRED DIMENSION (UNITS IN mm)	S7	U7	PICK CLOSEST VALUE TO DESIRED DIMENSION (UNITS IN mm)	S7	U7
NOMINAL SIZE RANGE	1	-14 -24	-18 -28	25	-27 -48	-40 -61
	1.2	-14 -24	-18 -28	30	-27 -48	-40 -61
	1.6	-14 -24	-18 -28	40	-34 -59	-51 -76
	2	-14 -24	-18 -28	50	-34 -59	-61 -86
	2.5	-14 -24	-18 -28	60	-42 -72	-76 -106
	3	-14 -24	-18 -28	80	-48 -78	-91 -121
	4	-15 -27	-19 -31	100	-58 -93	-111 -146
	5	-15 -27	-19 -31	120	-66 -101	-131 -166
	6	-15 -27	-19 -31	160	-85 -125	-175 -215
	8	-17 -32	-22 -37	200	-105 -151	-219 -265
	10	-17 -32	-22 -37	250	-123 -169	-267 -313
	12	-21 -39	-26 -44	300	-150 -202	-330 -382
	16	-21 -39	-26 -44	400	-187 -244	-414 -471
	20	-27 -48	-33 -54	500	-229 -292	-517 -580

Tables for Determining Metric Tolerances

Table 9: Tolerances for Outside Dimensions (Shafts)





Table 9 details tolerances for outside dimensions (shafts) based relative to the tolerance symbol. This table works the same way as Table 7, but is pulled from a different source (ANSI standards) and details s6 and u6 fits. Pick the nominal size value that is **closest** to the desired nominal size to determine the required tolerance range relative to the chosen tolerance symbol.

HOLE BASIS FIT		[mm]	Hole:		
Example:	Nominal size:	24	[mm]		
	Size range to be used:	18 to 30			
	ISO-Grade No.:	IT6			
	Tolerance Symbol:	F6/h6			
	Desired Fit:	Clearance Fit			
This Gives:	Allowance for hole:	0.013mm			
	Allowance for shaft:	0.013mm			

24	F6	+0.033	(0.013mm range)
		+0.020	

24	h6	0	(0.013mm range)
		-0.013	

TOLERANCES FOR OUTSIDE DIMENSIONS (SHAFTS) (UNITS IN 0.001mm)						
NOMINAL SIZE RANGE	PICK CLOSEST VALUE TO DESIRED DIMENSION (UNITS IN mm)	s6	u6	PICK CLOSEST VALUE TO DESIRED DIMENSION (UNITS IN mm)	s6	u6
	1	+20 +14	+24 +18	25	+48 +35	+61 +48
	1.2	+20 +14	+24 +18	30	+48 +35	+61 +48
	1.6	+20 +14	+24 +18	40	+59 +43	+76 +60
	2	+20 +14	+24 +18	50	+59 +43	+86 +70
	2.5	+20 +14	+24 +18	60	+72 +53	+106 +87
	3	+20 +14	+24 +18	80	+78 +59	+121 +102
	4	+27 +19	+31 +23	100	+93 +71	+146 +124
	5	+27 +19	+31 +23	120	+101 +79	+166 +144
	6	+27 +19	+31 +23	160	+125 +100	+215 +190
	8	+32 +23	+37 +28	200	+151 +122	+265 +236
	10	+32 +23	+37 +28	250	+169 +140	+313 +284
	12	+39 +28	+44 +33	300	+202 +170	+382 +350
	16	+39 +28	+44 +33	400	+244 +208	+471 +435
	20	+48 +35	+54 +41	500	+292 +252	+580 +540



MOLD BASES AND PLATES

DME Company USA

29111 Stephenson Highway
Madison Heights, MI 48071
800-626-6653 (toll-free)
248-398-6000
DME@DME.net

DME Canada

5345 Outer Drive - Unit 3
Oldcastle, ON
N9G 0C4 Canada
800-387-6600 (toll-free)
905-677-6370
DME_Canada@DME.net

DME Mexico

Circuito el Marques Norte
No. 55
Parque Industrial El Marques
El Marques, Queretaro,
CP 76246
52.442.713.5666
DME_MX@DME.net



2025 DME Company LLC All rights reserved.
Printed in the U.S.A.